PROJECT FEATURE

PROJECT TITLE	:	**IMPROVEMENT OF PTB**
LOCATION	:	**San Carlos Port, San Carlos City, Negros Occidental**
SCOPE OF WORK	:	

1.00 GENERAL EXPENSES
1.01 Mobilization/Demobilization and Clearing
1.02 Provide Safety and Health Program
1.03 Provide Temporary Facilities for the Engineer and Staff (Rental)
2.00 CONSTRUCTION/EXTENSION OF PTB
2.01 Demolish and dispose existing concrete pavement
2.02 Excavation for building foundations, drainage and septic vault
2.03 Supply, place and compact aggregate subbase course
2.04 Supply, place and compact gravel bedding for building foundation
2.05 Supply and install steel reinforcement for building structures
2.06 Supply and place 4,000 psi concrete for building structures

2.07 Construct 150mm thick CHB for exterior wall and 100mm thick CHB for interior wall including reinforcement
2.08 Supply and place 25mm thick cement plaster finish
2.09 Supply and install electrical lines and fixtures
2.10 Supply and install Glazed Ceramic Floor Tiles, Non-slip Floor Tiles, Glazed Ceramic Wall Tiles and Granite tile splash board and countertop

2.11 Supply and install Aluminum Clip-in Perforated Panel including accessories (0.60 x 0.60 x 0.07)
2.12 Supply and install PVC Ceiling Panel including accessories
2.13 Supply, delivery and installation of airconditioning unit including testing and commisioning
2.14 Supply, deliver and install Gang-chairs and accessories
2.15 Supply and install water line, sanitary pipes and fittings and toilet fixtures including accessories
2.16 Construct septic vault, supply and install catchbasin and downspout

2.17 Supply, fabricate, paint and install steel truss, rafter, purlins and roofing sheets including accessories
2.18 Supply and install PPA Logo for PTB including accessories
2.19 Supply, fabricate and install Phenolic antibacterial waterproof Toilet partition 12mm thk. including stainless
0.00 hinges indicators, bottom support door knobs and coat hooks
2.20 Supply and install Aluminum Composite Panels and accessories
Supply and install fabricated 1.5mm thk. Aluminum Framed Doors and Windows including glass and
2.21 accessories
2.22 Supply and place landscaping material in plant boxes
2.23 Supply and apply elastomeric paint interior and exterior
2.24 Supply, fabricate and install powder-coated steel tube
2.25 Supply, deliver and install Fire Detection Alarm System (FDAS)
2.26 Supply, deliver and install fire extinguishers and other accessories
2.27 Supply, fabricate and install stainless handrail at entry porch PWD ramp 1
2.28 Construct plantboxes including plastering and painting
Supply, fabricate and install Aluminum Frame and Glass Partition for GAD Amenities, Ballistic and
2.29 Terminal Fee Rooms including accessories.
2.30 Supply, fabricate and install wpc indoor wall panel, marine laminated plywood
3.00 REFURBISHING OF EXISTING PTB
Demolition and disposal of existing CHB wall partition, removal of existing ceiling and floor tiles and
3.01 removal of canopy
Supply and install Aluminum Clip-in Perforated Panel including accessories (0.60 x 0.60 x 0.07)
3.02
3.03 Supply and install PVC Ceiling Panel (2.9m x .25m x 0.075m)
3.04 Supply and install Glazed Ceramic Floor Tiles and Non-skid Ceramic Floor Tiles
3.05 Supply and Install Aluminum Composite Panels and accessories
3.06 Supply, fabricate and install powder-coated steel tube
3.07 Supply and install electrical lines and fixtures
3.08 Supply and apply elastomeric paint

3.09 Supply and place concrete including reinforcement for canopy, entry porch and PWD ramp 2
3.1 Supply and Place Stone Cladding
3.11 Construct plantboxes including plastering and painting
3.12 Supply, fabricate and install stainless handrail at entry porch PWD ramp 2
3.13 Supply, fabricate and install Phenolic antibacterial waterproof Toilet partition 12mm thk. including stainless hinges indicators, bottom support door knobs and coat hooks
3.14 Provision of cafeteria counter, chairs and tables including accessories

APPROVED BUDGET FOR THE CONTRACT	:	**PHP 23,008,806.32**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**PHP 26,000,046.52**
PROJECT DURATION	:	**300 Calendar Days**

Medium B - Building or Industrial Plant