

PROJECT FEATURE

PROJECT TITLE	:	**Proposed Construction of RC Pier, RoRo Ramp, Perimeter Fence, Gate and Guard House**
LOCATION	:	**Port of Himamaylan, Himamaylan City, Negros Occidental**
SCOPE OF WORK	:	

1.00 GENERAL EXPENSES
1.01 Mobilization/Demobilization and Clearing
1.02 Provide Safety and Health Program
1.03 Provide Temporary Facilities for the Engineer and Staff (Rental)
2.00 Construction of RC Pier and RoRo Ramp
2.01 Supply and delivery of RC Piles (6,000 psi concrete)
2.02 Handle, Pitch and Drive Batter RC Piles
2.03 Handle Pitch and Drive Vertical RC Piles
2.04 Chipping of Driven RC Piles up to Cut-off Elevation
2.05 Supply and Place 4000 psi concrete for the superstructure
2.06 Supply and Install Reinforcing Steel Bars
2.07 Supply, Deliver and Install Mooring Bollard T Head (35 T, T-head) including accessories
2.08 Install nine (9) sets of In stock Rubber Dock Fender V Type(V500 x 1500L) including accessories

3.00 Construction of Perimeter Fence, Gate and Guard House
3.01 Excavation for Column and Wall Footing of Fence, Gate and Guard House and Septic Vault
3.02 Fabrication and Installation of Formworks and Scaffoldings
3.03 Supply and Install Reinforcing Steel Bars
3.04 Concrete Works
3.05 Masonry Works
3.06 Supply and Install of Guard House Roof Frame and Roofing and Sidewalk Canopy
3.07 Supply and Install of Fibercement Board Ceiling on Metal Furring Frame
3.08 Painting Works
3.09 Supply and Install of Guard House Doors and Windows and PPA Logo
3.10 Supply and Install of Floor Tiles
3.11 Fabrication and Installation of Steel Fence and Gate Including Accessories
3.12 Supply and Install of Plumbing Fixtures, Water Line, Sanitary Line and Septic Vault
3.13 Supply and Install Electrical Line and Fixtures

APPROVED BUDGET FOR THE CONTRACT	:	**PHP 44,170,947.93**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**PHP 49,913,171.16**
PROJECT DURATION	:	**360 Calendar Days**

Medium A - Port, Harbor and Offshore Engg.