w/ CAF

PROJECT FEATURE

PROJECT TITLE	:	**CONSTRUCTION OF BARANGAY PANGAPUYAN COMMUNITY PORT**
LOCATION	:	**Pangapuyan Island, Zamboanga City**
SCOPE OF WORK	:	**A. CONSTRUCTION OF BACK UP AREA AND ROCK CAUSEWAY WITH STAIRLANDING** 1 Supply and place 50-100 kg/pc core rocks (3,905 cu.m.) and 500 kg/pc armour rocks (2,079 cu.m.) 2 Supply, spread and compact sand & gravel fill (2,833 cu.m.), aggregate subbase course (596 cu.m.), aggregate base course (176 cu.m.) and geotextile fabric (1,369 sq.m) 3 Construct 250mm thick Portland cement concrete pavement (761 sq.m.) including dowel bars (325.76 4 Supply and place 3,500 psi concrete for RC curb, stairlanding, and lamp post foundation (143 cu.m.) including steel reinforcements (6,387 kg) and gravel bedding (2 cu.m.) 5 Supply and install mooring cleats including accessories (4 sets) 6 Supply and install port lighting system **B. CONSTRUCTION OF PASSENGER SHED** 1 Construction of passenger shed (Area = 141 sq.m.) including structural, architectural, plumbing and sanitary works.

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**43,550,797.62**
SOURCES OF FUNDING	:	**General Appropriations Act (GAA)**	
TOTAL PROJECT COST	:	**Php**	**49,212,401.31**
PROJECT DURATION	:	**390**	**Calendar Days**

4