PROJECT FEATURE

PROJECT TITLE	:	RECONSTRUCTION OF GENERAL LUNA PORT
LOCATION	:	Port of General Luna, Siargao Island, Surigao Del Norte
SCOPE OF WORK	:	**A. REMOVAL, DISPOSAL AND EXCAVATION WORKS** 1 Removal and disposal of existing passenger shed including turn-over materials with value to the authority 2 Removal and disposal of existing rc pier 3 Chipping of existing RC curb and smoothen with mortar 4 Excavation of Existing seabed 5 Cutting & disposal of existing piles upto seabed elevation 6 Excavation and backfilling works **B. CONSTRUCTION OF ACCESS TRESTLE ON PILES** 1 Supply & driving of Steel Pipe pile (500mm dia.) including protective coating 2 Handling, pitching & driving of Steel Pipe piles 3 Supply & placing of concrete filler for SPP 4 Supply & installation of reinforcing steel cage for SPP 5 Supply, fabricate & install structural steel materials including HDG 6 Supply & placing of steel matting including concrete filler and reinforcement 7 Supply & placing of precast concrete slab 8 Supply & placing of 4,000 psi. concrete for rc curb & slab gap connections 9 Supply & installation of reinf. steel bar for rc curb 10 Supply, fabricate & install WPC floor decking complete with metal floor framing and other accessories 11 Supply & apply corrosion protection/metal protecting coat and epoxy paint for all welded connections 12 Supply, fabricate & install covered walkway complete with frammings, railings, roofings, electrical works and other necessary accessories 13 Supply, fabricate & install pontoon complete with gangways and other necessary accessories **C. CONSTRUCTION OF CAUSEWAY** 1 Supply & placing of 3,500 psi. concrete 2 Supply & installation of reinf. steel bar 3 Supply & placing of 50 to 100 kg. of plastered core rocks 4 Supply & placing of fill materials 5 Supply & placing of aggregate base course 6 Construction of PCC Pavement
APPROVED BUDGET FOR THE CONTRACT	:	Php 193,829,570.42
SOURCES OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	Php 219,027,414.57
PROJECT DURATION	:	120 Calendar Days

8