PROJECT FEATURE

PROJECT TITLE	:	**Rehabilitation of Security Perimeter Fence with 2 Gates**
LOCATION	:	**Port of Cagayan de Oro**
SCOPE OF WORK	:	

1.00	Demolish Remove & Dispose Existing CHB Wall & Other Structures (811.10 L.M)
2.00	Demolish, Remove and Dispose Existing Concrete Pavement (1,870.22 SQ.M.)
3.00	Excavation Works (2,805.33 CU.M.)
4.00	Lean concrete (35.87 CU.M.)
5.00	Concreting of Superstructures (Foundation, Column, and Beam) - (1,104.80 CU.M.)
6.00	Supply, Fabrication and Installation of Steel Reinforcement (62,278.65 KGS.)
7.00	150mm CHB Wall (Including Reinforcing Steel) - (2,102.26 SQ.M.)
8.00	Cement Plaster Finish (5,083.21 SQ.M.)
9.00	Painting Works (5,419.81 SQ.M.)
10.00	Steelworks (1 LOT)
11.00	Fabrication and Installation of Security Gate 1A including Painting Works (1 LOT)
12.00	Fabrication and Installation of Security Gate 1C including Painting Works (1 LOT)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**30,217,142.75**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**30,513,000.00**
PROJECT DURATION	:	**270 Calendar Days**	