

PROJECT FEATURE

PROJECT TITLE : **IMPROVEMENT OF BACK-UP AREA**

LOCATION : **Port of Lubang, Occidental Mindoro**

- SCOPE OF WORK** :
- A. BACK-UP AREA**
 - 1. Demolish and Dispose of Existing Concrete Pavement and Retaining Wall, including Removal of Impacted Solar Street Lights (1.0 l.s.)
 - 2. Excavation Work, Including the Disposal of Unsuitable Items (1,374.74 sq.m.)
 - 3. Remove and Re-install Core Rocks (10 to 20 kgs.) and Armour Rocks (50 to 100 kgs.) (1.0 l.s.)
 - 4. Supply and Place Concrete Blocks (308.43 cu.m.)
 - 5. Supply and Place Geotextile Fabric (271.33 sq.m.)
 - 6. Supply, Spread and Compact Selected Filling Materials (1,374.74 cu.m.)
 - 7. Supply, Spread and Compact 200mm Thick Gravel Base Course Materials (274.95 cu.m.)
 - 8. Supply and Place Reinforcing Steel Bars for Pavement (7,479.72 kgs.)
 - 9. Supply and Place 3500 psi Concrete for Pavement (412.42 cu.m.)
 - 10. Supply and Place 3500 psi Concrete for Retaining Wall (36.81 cu.m.)
 - 11. Supply and Place Reinforcing Steel Bars for Retaining Wall (4,007.20 kgs.)
 - 12. Supply and Place One Concrete Pedestal including Re-installation of Steel Post for Solar Lighting System (1 set)
 - 13. Supply and Install 100W LED Solar Street Lights including Accessories and Turnover of Items (20 sets)

APPROVED BUDGET FOR THE CONTRACT : **Php 22,792,289.76** ✓

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 25,755,287.43** ✓

PROJECT DURATION : **210 Calendar Days** ✓