



PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Ozamiz Port

LOCATION : Ozamiz City, Misamis Occidental

MAJOR SCOPE OF WORK :

- 1) Dredging/Excavation along the berths and maneuvering areas of the Port to a designed depths of 5.0, 10.0 and 12.0 meters below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged :
250,000.00 cu.m. of loose to medium dense clayish soil, mud, silt, and sand with possible compacted/hard materials
- 3) Disposal of dredged/excavated soil materials
16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 126,056,648.80

TOTAL PROJECT COST : P 129,208,065.02

PROJECT (DREDGING) UNIT COST : P 477.98 per cubic meter
(Dredging Works Only)

PROJECT DURATION : 300 calendar days
(inclusive of Sundays / Holidays and unworkable condition)