

c. **Cement Finish Application**

A brown coat with sufficient pressure shall be applied to fill the gaps, and to secure a good bond. Moistened for 48 hours, each coat of cement plaster shall be kept after application and allow to dry.

A finish coat shall be applied after the brown coat has set. The brown coat shall be moistened before application of the finish coat. Finish coat shall be floated to plumb, even planes and surfaces.

Final plaster finishes shall be rubber sponged.

d. **Tolerance**

The Contractor shall finish plaster work plumb, level, square and true within tolerance of 3mm in 3 meters, without cracks and other imperfections.

e. **Patching and Cleaning**

Upon completion of the building, and when directed, all loose, cracked, damaged or defective plastering shall be cut out and re-plastered in a satisfactory and approved manner.

2. **Wall Tiles**

a. **Mortar Preparation**

All mortar setting beds shall be mixed by volume in the proportion of 1 part Portland cement and 3 parts dry sand and not more than 1/10 part hydrated lime.

Mortar materials shall be measured in approved containers, which will insure that the specified proportions of materials will be controlled and accurately maintained during the progress of the work. Measuring materials with shovels, "shovel count", will not be permitted. Unless specified otherwise, mortar shall be mixed in proportions by volume, in an approved mortar box.

The quantity of water shall be controlled accurately and uniformly. The aggregates shall be introduced and mixed in such manner that the materials will be distributed uniformly throughout the mass. A sufficient amount of water shall be added gradually and the mass further mixed until a mortar of the elasticity necessary for purpose intended is obtained. Mortar boxes, pans and wall surfaces shall be kept clean and free from debris or dried mortar. The mortar shall be used before the initial set of the cement has occurred. Re-tempering of mortar in which cement has started to set will not be allowed.

b. **Application of Wall Tile**

Interior masonry shall be clean, thoroughly dry, sound and sufficiently rough to provide strong mechanical bond. Surfaces shall be evenly damped immediately prior to the application of the scratch coat.

Scratch coat shall be applied to masonry, as backing for wall tile, not less than 24 hours or more than 48 hours before starting the tile setting. The scratch coat shall not be less than 6 mm from the face of the masonry. The scratch coat shall be applied with sufficient pressure to ensure a proper bond with the base for the setting bed. While the mortar is still plastic, the scratch coat shall be cut with a trowel

at all internal vertical angles for the depth of the coat with the full height of the tile bed and shall be cross-scratched, in 25 mm centers for the extent of the tile bed.

Immediately before the application of mortar setting bed, the scratch coat shall be moistened thoroughly but not saturated. Temporary screeds shall be applied to the scratch coat with mortar to provide a true and plumb surface, the proper distance back from the finished wall line. The setting bed shall be applied, rodded and floated flush with the screeds over an area not greater than the area to be covered with the tile while the bed remains plastic. The thickness of the setting bed shall not exceed 15mm and the mortar shall not be re-tempered. The setting bed shall be cut with a trowel at all internal corners as specified for the scratch coat.

Mounted tiles shall be soaked in clean water a minimum of one hour before they are set. Absorptive mounted tiles shall be damped by placing sheets on a wetted cloth in a shallow pan before setting. A skim coat of neat Portland cement mortar, mixed with water to the consistency of a pasty, thick cream, shall be applied 0.8mm to 1.6mm thick to the mortar setting bed, or to the back of each tile as laid. The tiles shall then be pressed firmly on the setting bed and tamped until flush and in the plane of the other tiles. The tiles shall be applied before the mortar bed has taken its initial set.

Intersections and returns shall be formed accurately. Where cutting of tiles is necessary it shall be done at the internal angles of the walls or wainscots. Cutting and drilling tiles shall be done neatly without marring the surfaces. The cut edges of tiles against trim, built-in fixtures, and similar surfaces shall be ground and jointed carefully. The tiles shall fit closely with plumbing fixtures and around electric outlets, pipes and fittings, so that the plates or escutcheons will properly overlap the tiles. Wainscots shall be within one half of the heights indicated without cutting of the tiles.

Bases, caps, bull-nose corners, and all other trimmers moulded or shaped features, and accessories shall be backed thoroughly with mortar and set firmly into place. All lines shall be kept straight and true, and all finished surfaces brought to true and even planes, straight and plumb, and internal corners squared and external corners rounded.

Horizontal joints shall be maintained level and vertical joints plumb and in alignment. The completed work shall be free of broken, cracked, damaged or otherwise faulty tiles.

Joints shall be parallel and uniform in width, plumb, level and in alignment. End joints in broken-joint work shall be made as far as practicable, on the center line of adjoining tiles. Except in special arrangement and design, as indicated or specified, square tiles shall be set with straight joints, and oblong tiles shall be set with broken joints.

Joint widths shall be uniform and spaced to accommodate the tile in the given spaces with a minimum of cutting. Tiles shall be wetted, if they have become dry, before applying grout. Joints 3mm or less in width shall be grouted with a neat Portland cement grout of the consistency of thick cream. Other joints shall be pointed with mortar consisting of one part Portland cement and two parts pointing sand. The grout for walls and other vertical surfaces shall contain non-staining white Portland cement. Grout and pointing mortar shall be forced into joints by using trowel, brush or finger application.

Before the grout or mortar sets, the joints of cushion edge tiles shall be struck or tooled to the depth of cushion, filling all skips or gaps, and the joints of square edge tiles shall be filled completely flush with their surface. Dark cement shall not show through grouted white joints. Care shall be taken to avoid scratching glazed finishes. All mortar or grout shall be removed before it has set or hardened.

c. **Cleaning and Curing**

All completed tile work shall be thoroughly sponged and washed diagonally across joints, and finally polished with clean, dry cloth. Acid cleaning of unglazed tile, when necessary, shall not be done within ten days after setting tile. All metal shall be covered with an approved grease and the tile shall be wetted with clean water, before tile is cleaned with 10% muriatic acid solution. After acid cleaning, the tile shall be flushed with clean water, and the grease coating on metal shall be removed. Acid cleaners shall not be used on glazed tile.

d. **Protection**

Tiled walls outside corners (external angles) shall be protected with board corner strips in areas used as passage ways by workmen. Extreme care should be taken not to disturb walled tiled until mortar has fully set.

3. **Painting Works**

a. **Surface Preparation**

Allow new masonry to dry for 14 days (for exterior surfaces) to 28 days (for interior surfaces) under normal conditions before painting. Surface to be painted should be clean and dry, free from oil, grease, dirt, dust, contaminants, and all loose grit and mortar.

Without mesh:

1st Coat: Elastomeric Wall Covering Sealer

2nd and 3rd Coat: Elastomeric Wall Covering Basecoat

4th Coat: Elastomeric Wall Covering Topcoat

With mesh:

1st Coat: Elastomeric Wall Covering Sealer

2nd Coat: Elastomeric Wall Covering Basecoat
Reinforcing Membrane: Fiberglass Matting

3rd and 4th Coat: Elastomeric Wall Covering Basecoat

5th Coat: Elastomeric Wall Covering Topcoat

FLOOR FINISHES

1. Vitrified Ceramic Tiles

a. Mortar Preparation

Mortar mix proportion and preparation shall be in accordance with the requirements.

b. Surface Preparation

Surfaces to receive the tiles shall be clean, free of dust, dirt, oil, grease, and other deleterious substances. Floor tile operations in spaces receiving wall tile shall not be started until wall tile installation has been completed. Before tile is applied with a dryset mortar bed, the structural floor shall be tested for levelness or uniformity of slope by flooding it with water. Areas where the water ponds shall be filled and leveled with mortar and shall be retested before the setting bed is applied.

c. Placing of Setting Beds and Floor Tile

Mortar setting beds shall have a minimum thickness of 20mm for floors. The structural concrete slab shall be soaked thoroughly with clean fresh water on the day before the setting bed is to be applied. Immediately preceding the application of the setting bed, the structural slab shall again be wetted thoroughly, but no free water shall be permitted to remain on the surface.

A skim coat of neat Portland cement mortar shall then be applied not more than 4mm thick. The mortar shall be spread until its surface is true and even and thoroughly compacted, either level or sloped uniformly for drainage, as the case requires. A setting bed, as large as can be covered with tile before the mortar has reached its initial set, shall be placed on one operation; but in the event that more setting mortar has been placed than can be covered, the unfinished portion shall be removed and cut back to a clean beveled edge.

All mounted tiles shall be soaked in clean water a minimum of one hour before they are set. Absorptive mounted tile shall be dampened by placing sheets on a wetted cloth in a shallow pan before setting. No free water shall remain on the tiles at the time of setting. Before the initial set has taken place in the setting bed, a skim coat of neat Portland cement mortar, 0.7mm to 1.6mm thick, shall be trowelled or brushed over the setting bed and/or the back of the tile, or a thin layer of Portland cement, 0.79mm to 2mm thick, may be hand-dusted uniformly over the setting bed and worked lightly with a trowel or brush until thoroughly damp.

The tiles shall then be pressed firmly upon the setting bed, and beaten into the mortar until true and even with the plane of the finished floor line. Beating and leveling shall be completed within one hour after placing tiles or sheets. Borders and defined lines shall be laid before the field or body of the floor. Where floor drains are provided, the floors shall be sloped to drain properly to the drains. Intersections and returns shall be formed accurately.

Cutting of tile, where necessary, shall be done along the outer edges of the floor. As far as practicable, no tiles of less than half size shall be used. Cutting and drilling of tiles shall be done neatly without marring the tile surfaces. The cut edges of tile against trim, bases, thresholds, pipes, built-in fixtures, and similar surfaces shall be ground and jointed carefully. Tile shall fit closely and neatly at all plumbing fixtures and around electrical outlets, pipes and fittings so that cover plates or escutcheons will overlap the tiles properly. Tiles shall be secured firmly in place and loose tiles or tiles sounding hollow shall be removed and replaced. All lines shall be kept straight,

parallel, and true, and all finished surfaces brought to true and even planes. The inner edges of borders shall be kept straight and, where practicable, shall form right angles at all returns. The paper and glue shall be removed from mounted tile, without using excess water, within one hour after installing the tiles.

Joints shall be parallel and uniform in width, plumb, level and in alignment. End joints in broken-joint work shall be made as far as practicable, on the center lines of adjoining tiles. Except in special arrangement and design, as indicated or specified, square tiles shall be set with straight joints, and oblong tiles shall be set with broken joints.

Joint widths shall be uniform and spaced to accommodate the tile in the given spaces with a minimum of cutting. Tiles shall be wetted, if they have become dry, before applying grout. Joints 3.2 mm or less in width shall be grouted with a neat Portland cement grout of the consistency of thick cream. Other joints shall be pointed with mortar consisting of one part Portland cement and two parts pointing sand. The grout or mortar for joints on floors shall be white Portland cement or as specified by the Engineer. Grout pointing mortar shall be forced into joints by using trowel, brush or finger application. Before the grout or mortar sets, the joints of cushion edge tile shall be struck or tooled to the depth of the cushion, filling all skips or gaps, and the joints of square edged tiles shall be filled completely flush with their surface. Dark cement shall not be seen through grouted white joints.

All surplus mortar or grout shall be removed before it has set or hardened.

d. **Cleaning and Curing**

Floors shall be covered with waterproofed paper with all joints lapped at least 96 mm and allowed to damp cure for at least 72 hours before foot traffic is permitted thereon.

All completed tile work shall be thoroughly sponged and washed diagonally across joints, and finally polished with clean, dry cloth. Acid cleaning of unglazed tile, when necessary, shall not be done within ten days after setting the tile. All metal shall be covered with approved grease and the tile shall be wetted with clean water, before tile is cleaned with 10% muriatic acid solution. After acid cleaning, the tile shall be flushed with clean water, and the grease coating on metal shall be removed.

Finished tile floors shall be covered with clean building paper before foot traffic is permitted on them. Board walkways shall be placed on floors that are to be continuously used as passage ways by workmen. Thresholds shall be covered with boards. Tiles vertical outside corners (external angles) shall be protected with board corners strips in areas used as passage by workmen.

3. **Plain Cement Floor Finish with Non-metallic Floor Hardener**

a. **Trial Mix**

No plain cement floor finish work shall be started without the approval of the Engineer of the trial mix.

b. **Application**

The concrete sub-floor shall be cleaned and projection, dust, loose particles and other materials which would prevent good bond shall be removed. The sub-floor surface shall be moistened but not soaked, dry cement shall then be sprinkled over it and the mortar shall be spreaded on the setting bed. The surface shall be tamped to

assure a good bond over the entire area and screeded to provide a smooth and level bed at proper height.

Mortar mix shall be one part Portland cement to three parts sand. Following the placing of leveling concrete on the floor and after the concrete is free from excess water, a dry mixture of 2 parts of floor hardener and 1 part Portland cement shall be uniformly dusted over the floor. Three kilograms of floor hardener shall be used for every square meter of flooring or in accordance with approved manufacturer's specifications. The dry mixture shall be floated thoroughly into the surface which shall be finished by steel trowelling and cured by water or curing compound for seven (7) days.

4. Protection

- a. Before turn over of the building to the Owner, wash pebble surfaces with 1 part muriatic acid to 6 parts clean water.
- b. Apply an overlapping strokes of water shield using brush or by low pressure spraying. Dries to a tack-free surface in 4-6 hours and cures to form an effective water repellant film in approximately 24 hours.
- c. Protect finished surface with specified hardeners and sealants.

ALUMINUM COMPOSITE PANEL

1. Surface Preparation

Ensure surfaces to receive panels are structurally sound, even, smooth, clean, dry, and free from defects detrimental to work.

2. Sub-Framing Installation

Lay-out the location of the aluminum tube at every termination or as required in the approved shop drawing.

Drill the wall where the expansion bolt is to be placed and fix the angle bracket to the wall by securing it firmly with the expansion bolt.

Connect the aluminum tube to the expansion bolt by waferteks

3. Fabrication and Installation

Lay-out the dimension of the panel as per approved termination based on actual measurements and as per approved by the Engineer.

Cut the panel sizes using cutting machine

Finally, install the produced panel to the aluminum tube by waferteks.

4. Sealant Application

After the panel is put into place, peel off the protective film at the edges of the panel.

Fill in the gap with the backer rod. Wipe the edges of the panel by rags. Cover the edges of the panel with masking tape. Apply the sealant of approved color.

As soon as the application of sealant is finished, carefully remove the masking tape and wipe off excess sealant on the panel.

5. Cleaning and Protection

Removed temporary protective films. Clean finished surfaces as recommended by aluminum composite panel manufacturer. Clear weep holes and drainage channels of obstructions, dirt and sealant. Maintain in a clean condition during construction.

Replace damaged panels and accessories that cannot be repaired by finish touch-up or minor repair

6. Warranty

a. Workmanship Warranty

The installer shall warrant the finished assembly to remain in its integrity under normal condition for a period of one (1) year. Normal condition shall not cover force majeure, deliberate vandalism, improvement repair works and the likes.

b. Paint Finish Warranty

The manufacturer shall warrant against fading, chalking, peeling, or cracking of paint finish for a period of ten (10) years.

INSTALLATION OF DOORS

1. Surface Preparation

Ensure surfaces to receive panels are structurally sound, even, smooth, clean, dry, and free from defects detrimental to work.

DOORS AND WINDOWS

DOORS

- D-1 - 1.5mm thk. Aluminum Framed Powder Coated Finish with 10 mm thk. Reflective Tempered Glass Double Swing Door with Fixed Type Transom Window (1.90m x 2.10m)
- D-2 - 1.5mm thk. Aluminum Framed Powder Coated Finish with 10 mm thk. Reflective Tempered Glass Swing Door with Fixed Type Transom Window (1.00m x 2.10m)
- D-3 - 1.5mm thk. Aluminum Framed Powder Coated Finish with 8 mm thk. Reflective Tempered Glass 4-Panel Sliding Door with Fixed Type Transom Window (3.70m x 2.10m)
- D-4 - 1.5mm thk. Aluminum Framed Powder Coated Finish with 10 mm thk. Reflective Tempered Glass Double Swing Door with Fixed Type Transom Window (1.90m x 2.10m)
- D-5 - 6mm Thk. Marine Plywood Finish Flush Door with 8mm thk. Clear Glass (0.70m x 2.10m)

- D-6 - 6mm Thk. Marine Plywood Finish Flush Door with 8mm thk. Clear Glass (0.90m x 2.10m)
- D-7 - 6mm Thk. Marine Plywood Finish Flush Door (0.90m x 2.10m)
- D-8 - 6mm Thk. Marine Plywood Finish Flush Door (0.80m x 2.10m)
- D-9 - PVC Door with vent louver at the bottom part (1.0m x 2.10m)
- D-10 - PVC Door with vent louver at the bottom part (0.90m x 2.10m)
- D-11 - 200 mm Thk. Phenolic door, Plain colored (0.60m x 1.57m)
- D-12 - PVC louver double swing Door (0.80m x 2.10m)
- D-13 - Cold Rolled Steel Emergency Exit Door with Panic Push Bar Lock (0.90m x 2.10m)

INSTALLATION OF WINDOWS

1. Surface Preparation

Ensure surfaces to receive panels are structurally sound, even, smooth, clean, dry, and free from defects detrimental to work.

- W-1 1.5mm thk. Aluminum Framed Powder Coated Fixed Type Window with 10mm Thk. Reflective Tempered Glass (W-1) (3.60m x 2.55m)
- W-2 1.5mm thk. Aluminum Framed Powder Coated Casement Type Windows with 10mm thk. Reflective Tempered Glass (1.80 m x 1.20m)
- W-3 1.5mm thk. Aluminum Framed Powder Coated Casement Type Window with 10mm thk. Reflective Tempered Glass (1.50m x 1.20m)
- W-4 1.5mm thk. Aluminum Framed Powder Coated Fixed Type Window with 8mm thk. Reflective Tempered Glass (0.70m x 1.20m)
- W-5 1.5mm thk. Aluminum Framed Powder Coated Casement Type Window with 10mm thk. Reflective Tempered Glass (3.60m x 1.20m)
- W-6 1.5mm thk. Aluminum Framed Powder Coated Fixed Type Window with 10mm thk. Reflective Tempered Glass (4.0m x 2.10m)
- W-7 1.5mm thk. Aluminum Framed Powder Coated Awning Type Window with 10mm thk. Reflective Tempered Glass (2.40m x 0.60m)
- W-8 1.5mm thk. Aluminum Framed Powder Coated Awning Type Window with 10mm thk. Reflective Tempered Glass (1.20m x 0.60m)

- W-9** 1.5mm thk. Aluminum Framed Powder Coated Casement Type Windows with 10mm thk. Reflective Tempered Glass (3.60m x 1.20m)
- W-10** 1.5mm thk. Aluminum Framed Powder Coated Awning Type Window with 10mm thk. Reflective Tempered Glass (W-10) (1.80m x 0.60m)
- W-11** 1.5mm thk. Aluminum Framed Powder Coated Fixed Type Window with 10mm thk. Reflective Tempered Glass (0.80m x 2.35m)
- W-12** 1.5mm thk. Aluminum Framed Powder Coated Transom Type Window with 10mm thk. Reflective Tempered Glass (0.80m x 0.80m)
- W-13** 1.5mm thk. Aluminum Framed Powder Transom Window with 10mm thk. Reflective Tempered Glass (0.95m x 0.80m)

ITEM 15 : PAINTING**GENERAL**

General Requirements contain provisions and requirements essential to these Specifications; and apply to this section, whether or not referred to herein.

SCOPE OF WORK

This Section covers the surface preparation, coating materials and application of coatings systems required for the Works.

The work shall consist of furnishing of all labor, materials, equipment and other incidentals necessary for the supply of painting materials and the complete painting of surfaces as shown on the drawings in accordance with this Specification and as directed by the Engineer.

The term paint as hereinafter used includes emulsion paints, varnishes, oils, pigments, thinner and dryers.

All exposed metal surfaces, except metal surfaces embedded in concrete, shall be painted unless otherwise specified.

STANDARD

The following publications listed below, but referred to thereafter by basic designation only, forms a part of these Specifications to the extent indicated by the reference thereto:

Steel Structures Painting Council (SSPC) U.S. Specification JIS K 5628 Red-lead Zinc Chromate Anti-Corrosive Paint.

SUBMITTAL

1. The Contractor shall submit work method statements with lists of materials to the Engineer for approval twenty eight days before the starting of works. This statement shall include following items:
 - a. Type of paint and manufacturer
 - b. Manufacturer's specifications
 - c. Storage and delivery of materials
 - d. Surface preparation
 - e. Finish painting and drying
 - f. Touch-up painting, if any
 - g. Equipment
2. The Contractor, before placing order for the painting materials, shall submit to the Engineer for approval samples of materials. No placing of orders for material shall be made without his approval.

STORAGE AND DELIVERY

1. The Contractor shall deliver all material to the site in the original labeled sealed cans and containers, with labels intact and seal unbroken.
 - a. Seals shall remain unbroken until after inspection and acceptance of material by the Engineer.

- b. The Contractor shall deliver materials in ample quantities sufficiently in advance of the need to avoid any delay or interruptions in the works.
2. Paint in thinner shall be stored in accordance with the approved manufacturer's instructions.
 - a. All regulations required for storage of paint shall be observed and all necessary safety signs required by governing codes shall be posted.
 - b. Any damage caused by failure to exercise proper precautions in paint storage shall be repaired.

MATERIAL REQUIREMENTS

PAINT

Paints for the protective coating system shall be the product of a manufacturer approved by the Engineer.

Paints for exterior finish must be with tile like durability and elegance, fast drying, solvent based acrylic, highly suitable for coastal or polluted areas with excellent anti-fungus properties and alkali resistance.

100% Acrylic, water based, quick-drying, easy to clean-up and environmentally friendly, resist dirt, stains, alkali, water, humidity, algae, mold and mildew growth and highly durable paint for interior finish.

An all-purpose synthetic quick dry paint for all types of wood and metal surfaces. It has high gloss, good color retention and outstanding durability.

For pipes, valves and equipment, galvanized and ungalvanized ferrous metal, use a 100% acrylic gloss paint, has excellent resistance to ultraviolet rays and resists chalking, cracking and color fading, dries fast and environmentally friendly.

SCHEDULE OF PAINTING

Paint manufacturers shall be BOYSEN, DAVIES or approved equal.

Architectural Items	
a. Exterior Finishes	
1. On Concrete Walls	
Three Coats, Concrete Masonry Paint	Boysen Titan Superflex, Elastomeric Paint or approved equal
2. Unprimed Ferrous Metal	
First Coat	Boysen Red Oxide Primer, #310 or approved equal
Second & Third Coat	Boysen Quick Dry Enamel or approved equal

3. On Concrete Block Wall	
Masonry Neutralizer	Boysen Masonry Neutralizer #44 or approved equal
Three Coats Concrete Masonry Paint	Boysen Titan Superflex Elastomeric Paint or approved equal
4. On Wood	
First Coat Exterior Wood Primer	Boysen Flatwall Enamel or approved equal
Second & Third Coat Exterior enamel	Boysen Quick Drying Enamel or approved equal
b. Interior Finishes Location of the various finishes are listed in the Finish Schedule on the drawings or else will be confirmed by PPA	
1. On primer and coated metal two coats of interior semi-gloss enamel or as indicated in the Schedule finish	Boysen Red Oxide Primer #310, Boysen Quick Dry Enamel or approved equal
2. On Plaster	
First Coat	Boysen Masonry Neutralizer #44 or approved equal
Three Coats	Boysen Titan Superflex, Elastomeric Paint or approved equal
3. On Wood	
First Coat Enamel undercoater	Boysen Flatwall Enamel or approved equal
Second & Third Coat Exterior enamel	Boysen Quick Drying Enamel or approved equal
4. Wood Stain Finish	
First Coat Second & Third Coats Fourth & Fifth Coats	Boysen Oil Wood Stain , Boysen Lacquer Sanding Seale #1254 Boysen Clear Gloss Lacquer #1250 or approved equal
c. Non – Architectural Items (Piping, valves, equipment, etc.)	
1. Piping, valves, equipment etc. in rooms are to be painted	
2. Galvanized pipes and ducts	
Primer – one coat	Boysen Red Oxide Primer, #310 or approved equal
Finish – one coat	Boysen Quick Dry Enamel or approved equal
3. Black steel pipes	
Primer – one coat	Boysen Red Oxide Primer, #310

Finish – one coat	or approved equal Boysen Quick Dry Enamel or approved equal
4. Mechanical Items	
a. Ungalvanized ferrous metal Primer – one coat Finish – one coat	Boysen Red Oxide Primer, #310 or approved equal Boysen Quick Dry Enamel or approved equal or approved equal
b. Galvanized ferrous metal Primer – one coat Finish – one coat	Boysen Red Oxide Primer, #310 or approved equal Boysen Quick Dry Enamel or approved equal or approved equal
c. Submerged galvanized ferrous metal Primer – one coat	Boysen Red Oxide Primer, #310 or approved equal
d. Buried miscellaneous ferrous surface valves, & flanged joints (excl. pipe) Primer – one coat	Boysen Red Oxide Primer, #310 or approved equal

EXECUTION

SURFACE PREPARATION OF STEEL

1. Steel surfaces shall be cleaned as follows:
 - a. All round welds, burrs and sharp surface projections shall be ground smooth and all weld splatter shall be removed prior to blast cleaning.
 - b. Sand abrasives, if used, shall be clean, and free from salt and extraneous matter. The sand shall pass through a 2.0mm test sieve, and be substantially retained on a 0.18mm test sieve, with at least 25 percent retained on a 0.355mm test sieve.
 - c. Metallic abrasive, if used, shall be sharp, hard and free from dust, and shall pass through a 1.8 mm test sieve.
 - d. Blast cleaning operations shall not be conducted on surfaces that will be wet after blasting and before coating, or when the surfaces are less than 10°C above degree points, or when the relative humidity of the air is greater than 95 percent.
 - e. Any oil, grease, soil, dust or other foreign matter deposited on the cleaned surfaces shall be removed prior to painting. In the event that rusting occurs after completion of the surface preparation, the surfaces shall be cleaned again in accordance with the specified method.
 - f. Particular care shall be taken to prevent the contamination of other corrosive chemicals before the application of the paint. Such contamination shall be removed from the cleaned surface by flash blasting and the paint applied immediately.

- g. Care shall be taken to prevent contamination of cleaned and painted surfaces by cleaning operations in an adjacent area.
- h. Surfaces not to be painted shall be suitably protected from the effects of cleaning and painting operations.

SURFACE PREPARATION OF WOOD

1. Wood surfaces shall be sanded to a fresh surface. Surface mould where present, shall be removed by washing, rubbing down and burning off as necessary. Resinous exudation and large knots shall be removed and replaced with filler or other materials approved by the Engineer.
2. Parts of timber to be enclosed in walls shall always be primed unless already impregnated. Priming shall be brushed on and a minimum of two coats applied to end grain. When the priming paint is hard, all cracks, holds, open joints, etc. shall be made good with hard stopping and rubbed down with fine abrasive paper. Priming of joinery shall be applied only on site after the Engineer has approved such joinery and before it is fixed. For internal surfaces primer coats shall be carefully flatted.

SURFACE PREPARATION OF CONCRETE AND PLASTER

Concrete and cement plaster surfaces to be painted shall be prepared by removing efflorescence, dust, dirt, grease, oil, asphalt, tar, excessive mortar and mortar dropping and by roughening to remove glaze. A zinc sulfate solution shall be applied before prime coat.

SURFACE PREPARATION FOR FIBER CEMENT SURFACES

Shall be dry and clean prior to application of the specified first-coat material. Oil, grease, or rust stains shall be carefully removed by the use of suitable solvent. Wire brushing will not be permitted. After the first coat has become dry and prior to application of finish coats, touch-up coats shall be applied to suction spots.

ALUMINUM FRAMES FOR DOORS AND WINDOWS

All metal surfaces shall undergo pre-treatment process which includes: desmutting, water-rinsing, degreasing/etching, water rinsing, zinc phosphating, water rinsing and acid rinsing.

Powder coating application, shall be factory applied and shall be done in one operation using an electro-static powder gun. The materials to be coated should be well connected to earth. Coating thickness should be kept to a minimum of 60 microns for exposed areas. On details which are to be treated mechanically after coating (drilling, sawing, etc.), the coating film must not exceed 100 microns.

The powder coating shall be oven cured in the range of 20 minutes at 220° C (metal temperature measured on the area with greatest metal thickness). The temperature variation in the oven should not exceed +/- 10° C.

Handling

Coated items should be cooled to no less than 40° Centigrade before handling. Precautions should be taken to avoid damages on the finished coating during stacking, storing and transportation.

Storage and Delivery

Inspect materials delivered to the site for damage. Unload and store with minimum handling. Provide storage space in dry location with adequate ventilation, free from dust or water and easily accessible for inspection and handling. Store materials neatly on the floor, properly stacked on non-absorptive strips or wood platforms. Protect finished surfaces during shipping and handling using manufacturer's standard method.

WOOD REPAIR

Badly decayed areas shall be removed and repaired. Areas and pieces decayed beyond repair shall be replaced with new pieces that match originals in all respects. Moderately decayed areas, weathered, or gouged wood shall be patched with approved patching compounds, and shall be sanded smooth. The source or cause of wood decay shall be identified and corrected prior to application of patching materials. Wet wood shall be completely dried to a moisture content not exceeding 12 percent, as measured by a moisture meter, to its full depth before patching, unless otherwise authorized. Wood that is to be patched shall be clean of dust, grease, and loose paint.

1. Epoxy Wood Repair

Epoxy wood repair materials shall be applied in accordance with manufacturer's written instructions. Health and safety instructions shall be followed in accordance with the manufacturer's instructions. Clean mixing equipment shall be used to avoid contamination. Mix and proportions shall be as directed by the manufacturer. Batches shall be only large enough to complete the specific job intended. Patching materials shall be completely cured before painting or reinstallation of patched pieces.

2. Epoxy Consolidant and Epoxy Paste

Epoxy liquid wood consolidant shall be used:

1. To penetrate and impregnate deteriorated wood sections in order to reinforce wood fibers that have become softened or absorbent.
2. As a primer for areas that are to receive epoxy paste filler. Epoxy paste shall be used to fill areas where portions of wood are missing such as holes, cracks, gaps, gouges, and other voids.

MIXING AND THINNING

Mixing and thinning of paint shall be done in accordance with the approved manufacturer's printed instructions. The pot life of each paint as stated by the manufacturer shall not be exceeded.

WEATHER CONDITION

The paint shall not be applied when the relative humidity is above 85 percent. The paint shall not be applied in rain, wind, fog, dust or mist.

APPLICATION

Workmanship shall be first class in every respect. All work shall be done in a workmanship manner so that the finished surfaces shall be free from runs, chop, ridges, waves, laps and unnecessary brush marks. All coats shall be applied in such manner as to produce an even film of uniform thickness. Edges, corners, crevices, welds and rivets shall receive special attention to ensure that

they receive an adequate thickness of paint.

All painting shall be done by thoroughly experienced workmen.

Safety regulations shall be adhered to at all times, including the wearing of respirators by persons engaged on assisting in spray painting. Adjacent areas and installation shall be protected by the use of cloths or other approved precautionary measures.

Plain enamel and varnish shall be applied carefully with good clean brushes or approved spraying equipment, except that the initial coat on any surface shall be applied with brush. Sufficient time shall be allowed between coats to assure thorough drying and each coat shall be in proper condition before receiving the next coat.

Sanding and dusting as required shall be performed between coats in varnishing work. Finish coat shall be smooth and free from runs, sags, and other defects. Exterior paint shall not be applied during rainy days.

All paint when applied shall provide a satisfactory film and smooth, even surface. Paint shall be thoroughly stirred and kept at a uniform consistency during application. Powdered metallic pigments added at the time of use shall be mixed by adding the powder in small increments to about one-third of the base paint or vehicle, with thorough mixing to obtain a smooth paste. The remainder of the base paint shall then be thoroughly stirred in.

Different brands of emulsion paints shall not be mixed prior to application of the materials.

Where necessary to suit conditions of surface temperature, weather and method of application, the package paint may be thinned immediately prior to application in accordance with the approved manufacturer's directions, but not in excess of 125 cc of suitable thinner per liter (one pint per gallon). Before using, the paint shall be mixed to a uniform consistency and shall be stirred frequently during application.

Paints other than water-thinned paints shall be applied only to surfaces which are completely free of moisture as determined by sight or touch and only such combinations of humidity to be painted as will cause evaporation rather than condensation.

Surfaces which have been cleaned, pretreated and/or otherwise been prepared for painting shall be primed or painted with one coat of finish paint as soon as practicable after such preparation has been completed, but in any event prior to any deterioration of the prepared surfaces.

The first coat of paint on all exterior surfaces shall be applied by brush. Interior prime coats and all other subsequent coats on either exterior or interior surfaces may be applied by brush or spray. Whenever spraying is permitted all areas inaccessible to spray painting shall be coated by brushing or other suitable means. Brushes to be used for application of water-emulsions shall be soaked in water for a period of 2 hours prior to use.

All cloths and cotton waste which might constitute a fire hazard shall be placed in closed metal containers or destroyed at the end of each day.

Upon completion of the work, all staging, scaffolding, and containers shall be removed from the site or destroyed in a manner approved by the Engineer. Paint spots, or stains upon adjacent surfaces shall be removed and the entire job left clean and acceptable to the Engineer.

No smoking shall be permitted in the vicinity where painting is going on.

TOUCH-UP PAINTING

Touch-up painting shall be done with the same paint as used for the original coat. The resulting minimum dry film shall be the same as for the original coat.

Touch-up painting shall include cleaning and painting of field connections, welds and all damaged or defective paint and rusted areas.

During touch-up painting, only loose, cracked, brittle or non-adherent paint shall be removed during cleaning. All exposed edges shall be feathered. Touch-up painting shall be performed in a manner which will minimize damage to sound paint. Rust spots shall be thoroughly cleaned and edges of the existing paint shall be scraped back to sound material.

DRYING

1. No primer or paint shall be forced to be dried under conditions which will cause cracking, wrinkling, blistering, formation of pores which would detrimentally affect the condition of the paint.
2. No drier shall be added to the paint unless specified in the approved manufacturer's instructions.
3. Painted surfaces shall be protected from dust, dirt, and the elements of the weather until dry to the fullest extent practicable.
4. After drying, any areas of paint damaged from any cause shall be removed, the surface again prepared and then touched-up with the same paint and to the same thickness as the undamaged areas as specified in sub-section 4.14.3.7 above.

HANDLING

1. Precautions shall be taken to minimize damage to paint films resulting from stacking for drying.
2. Paint which is damaged in handling shall be scraped off and touched-up with the same paint and in the same thickness as was previously applied to the damaged area at Contractor's expense.

INSPECTION

1. All works and materials supplied under this Specification shall be subject to inspection by the Engineer.
2. The Contractor shall correct such works or replace such materials found defective under these Specifications at his own expense.

ITEM 16 : ANTI-RUST PAINTING (METAL PROTECTING COAT)**SCOPE OF WORK**

This section covers the minimum requirements for the application of anti-rust paint or metal protecting coat.

USES

Corrosion prevention for Iron, Aluminum, Concrete structures in industrial facilities, bridges, tank exteriors, marine weathering, offshore, oil tanks, piping, roofs, water towers, vehicles and other exposures. And has good chemical resistance to splash / spillage, fumes and immersion in natural, fresh and salt water.

MATERIAL REQUIREMENTS

- VOC compliant.
- High performance general maintenance coating for new and old steel.
- Fast Drying.
- Cures through wide temperature range.
- Can be over-coated with wide range of topcoats.
- Compatible with prepared damp surfaces.
- Compatible with adherent rust remaining on prepared surfaces.
- Very thin layer in every coat.
- Can be applied to substrates with temperature up to 120oF (49oC)
- Suits Interior/exterior places

PHYSICAL PROPERTIES

Color	:	white-off white
Finish	:	Black after conversion
Number of components	:	one
Volume Solid	:	69%±2%
VOC (EPA 8260)	:	<0.06 g/l;
Specific Gravity	:	1.3-1.4gr/cc

MIXTURE

Ingredient Name	Identifiers	Percent
Bis(isopropyl)naphthalene	CAS number: 38640-62-9 EC number: 254-052-6	0.05- 0.24
Aluminium hydroxide	CAS number: 21645-51-2 EC number: 244-492-7	10-30
Barium sulfate	CAS number: 7727-43-7 EC number: 231-784-4	2-10

EXECUTION

SURFACE PREPARATION

Surface must be clean, dry and in sound condition. Remove all oil, dust, grease, dirt, loose rust and other foreign material to ensure adequate adhesion. Coating performance is proportional to the degree of surface preparation. Remove all loose paint, mill scale and rust. The surface to be coated must be dimensionally stable, clean and free of grease, oil and another foreign materials accordance with SSPC-SP-1. When high pressure water jetting is not practical, surface should be chipped, clean and wire brushed to clean material.

STEEL:

Remove oil or soap film with water-based detergent or emulsion cleaner. For atmospheric service use, high-pressure water cleaning [over 7500 psi], power tool cleaned to ISO-St3 or hand tool cleaned to ISO-St2 or abrasive blast to ISO-Sa2.5.

GALVANIZED STEEL:

Remove oil or soap film with water-based detergent or emulsion cleaner.

Galvanizing that has had at least 12 months of exterior weathering may be coated after power washing to remove all contaminations and white rust.

ALUMINUM:

Remove oil or soap film with water-based detergent or emulsion cleaner.

PREVIOUSLY PAINTED SURFACES AND REPAIRS:

If in sound condition, clean the surface of all foreign material as mentioned above.

NOTE:

Brush or Roll application may require multiple coats to achieve maximum film thickness and uniformity of appearance.

CLEAN UP INSTRUCTIONS:

Clean spills and spatters immediately with water. Clean tools immediately after use with water.

FIRST AID MEASURES

Eyes contact:

In case of contact with eyes, rinse immediately with plenty of water for at least 15 minutes. Get medical attention if needed.

Skin contact:

Take off contaminated clothing and shoes immediately. Wash off with soap and plenty of water. Get medical attention.

Inhalation: Remove the victim from site of exposure to fresh air. If breathing is difficult, give oxygen. If not breathing give artificial respiration. Get medical attention.

Ingestion: Do not induce vomiting. If victim is conscious, wash mouth thoroughly with plenty of water. Never give anything by mouth to an unconscious person. Get medical attention.

FIRE-FIGHTING MEASURES

Extinguishing Media:

Suitable:

Foam, carbon dioxide, dry powder or water spray.

Not suitable:

High volume water jet.

Special Hazards Arising from The Substance or Mixture:

Hazardous combustion products: carbon oxides, nitrogen oxides, sulphur oxides, barium oxide, aldehydes, acids and unidentified mixtures of organic compounds.

Advice for Firefighters:

Special protective equipment for fire fighters: Fire fighters should wear full protective clothing and self-contained breathing apparatus in positive pressure mode.

ACCIDENTAL RELEASE MEASURES

Personal precautions, protective equipment and emergency procedures:

Use personal protective equipment. Avoid breathing vapors, mist or gas. Ensure adequate ventilation. Ventilate area of spill.

Environmental Precautions:

Prevent entry into waterways, sewers, basements or confined areas.

Methods and materials for containment and cleaning up:

Contain spillage, and then collect with non-combustible absorbent material, (e.g. sand, earth, diatomaceous earth, vermiculite) and place in container for disposal according to local / national regulations.

HANDLING AND STORAGE

Precautions for Safe Handling:

Avoid contact with skin and eyes. Avoid inhalation of vapors, mist or gas. Wash thoroughly after handling. Handle in accordance with good industrial hygiene and safety practice.

Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also section 8 for additional information measures.

Conditions for Safe Storage, Including Any Incompatibilities:

Storage: Keep container tightly closed in a dry, cool and well-ventilated place. Keep away from oxidizing agents, acids, bases and reducing agents.

Engineering Measures:

Use process enclosures, local exhaust ventilation, or others engineering controls to keep airborne levels below recommend exposure limits. If user operations generate dust, fume or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit.

Person Protective Measures:

Respiratory protection: Suitable respirator. Be sure to use an approved/certified equipment or equivalent equipment. Wear appropriate respirator when ventilation is inadequate.

Hand Protection:

Wear protective gloves to prevent skin exposure.

Eye Protection:

Wear protective safety glasses.

Skin Protection:

Wear appropriate long-sleeved clothing to minimize skin contact.

Other Symptoms:

Inhalation of vapors may cause headache, irritation of nasal passages, throat or lungs in a closed space. Direct contact with eyes may cause irritation. Prolong or repeated contact with skin may cause light irritation.

WASTE TREATMENT METHODS

Product:

Waste must be disposed of in accordance with federal, state and local environmental control regulations.

Packing:

Empty containers should be taken for local recycling, recovery or waste disposal.

ITEM 17 : ELECTRICAL WORKS

SCOPE OF WORK

The work to be done shall consist of furnishing, delivering and installing electrical materials/fixtures completed in accordance with all the details of the electrical works as shown on the drawings including materials, labor, tools and equipment and all incidental works as found necessary.

Refer to electrical plans/drawings for location and extent of work involved.

GENERAL REQUIREMENTS

- a) All works shall be done in accordance with the requirements of the publications and agencies having jurisdiction, as well as the requirements of the approved standards.
1. National Fire Protection Association - (NFPA)
 2. National Electrical Manufacturer Association - (NEMA)
 3. Underwriter Laboratories, Inc. - (UL)
 4. Philippine Electrical Code - (PEC)
Philippine National Standard - (PNS)
 5. Federation Specification:
Circuit Breaker, Molded Case, Branch
Circuit and Service
 6. American National Standard Institute - (ANSI)
 7. American Society for Testing and Materials - (ASTM)
 8. Illuminating Engineering Society - (IES)
 9. Light Emitting Diode - (LED)
- b) The electrical power will be connected to the existing supply. The supply voltages shall be 220 volt, single phase (1Ø), and 60 hertz.
- c) The Contractor shall employ a licensed Registered Electrical Engineer or Master electrician to perform or to supervise and to conduct the continuous inspection of all electrical work.
- d) The Contractor shall first obtain approval from the Authority before procurement, fabrication or delivery of electrical materials to the site. Partial submittals will not be acceptable and will be returned without review. Submittals shall include the Manufacturer's Name, Trade Name, Place of Manufacture, Catalog Model or Number, Nameplate Data, Size, Layout Dimensions, Capacity, Project Specification and Paragraph Reference, Technical Society Publication References and other information necessary to establish contract compliance of each item to be furnished.
- e) The materials and equipment to be furnished shall be standard products of reputable manufacturer engaged in the reproduction of such materials and equipment.

- f) All permits and electrical fees required for this work shall be obtained at the expense of the Contractor. The Contractor shall furnish the Engineer-in-Charge, the final Certificates of Inspections and approval from the proper government authorities after the completion of work. The Contractor shall prepare all as-built plans and all other paper works as required by the enforcing authorities.
- g) The Contractor shall furnish and install electrical materials as shown in the drawings. A licensed Electrical Engineer or Master Electrician is required to implement the installation of the electrical system. A licensed electrical contractor shall oversee/conduct the installation of the main circuit breaker.
- h) Electrical installation shall conform to the requirements of Philippine Electrical Code (PEC) and the other approved standards.
- i) The contractor shall install all electrical works with the supervision of the qualified Registered Electrical Engineer (REE) or Master Electrician. All electrical installation applications regardless of capacity and voltage whether new, addition or revision shall be accompanied by electrical plans signed and sealed by a duly licensed Professional Electrical Engineer (PEE).

MATERIAL REQUIREMENTS

All materials shall be brand new and shall be of the approved type meeting all the requirements of the Philippine Electrical Code and bearing the Philippine Standard Agency (PSA) mark.

PRODUCTS

WIRES AND CABLES

The conductor material to be furnished and installed shall be copper wire Heat-Resistant Thermoplastic (THHN/THWN-2). All conductors shall be rated 600 volts insulation and shall be standard for all sizes.

CONDUIT AND FITTINGS

Underground PVC conduit shall be polyvinyl chloride with concrete covered. It shall be manufactured to schedule 40 outside diameter. All fittings and bends shall be solvent bonded using manufacturers recommended product.

WEATHERPROOF HOUSING WITH 2*36 WATT LED FLUORESCENT LIGHT or (EQUIVALENT)

Compatible with T8 Tube lights with the principal element of modern energy saving and ecological lighting of closed space, like offices and municipal lighting.

Provide a large range of housing products that will surely fit the lighting needs; while maintaining a high degree of protection for LED Lights.

The unit is meticulously manufactured and built with high-quality standards.

Specifications:

Dimensions	: 1280 * 150 * 95 mm
No. of lamp	: 2 pcs 1200 m Tube
Light Compatible	: T8 Tube Light
Material	: Polycarbonate Housing
Holder	: G13
Mounting	: Surface Mounted, Suspended
Material CLIP	: Plastic / Metal Clip
Wiring Connection	: Double End
IP Rating	: IP 67

EXECUTION

INSTALLATION

Weatherproof double housing fluorescent lamp shall be installed as shown on the approved plans.

WORKMANSHIP

The work throughout shall be executed in the best and most thorough manner under the direction of and at the satisfaction of the Registered Electrical Engineer or Master Electrician, who will interpret the intent meaning of the drawings and specification and shall have the power to reject any work and materials which in his judgment, are not in full accordance therewith.

TESTING OPERATIONS

When the electrical installation is completed, the Contractor shall test the installed electrical materials and equipment in the presence of Registered Electrical Engineer or Master Electrician. The system shall be free from any defects, shorts or grounds. The Contractor at no extra cost shall furnish all necessary instruments and personnel required for the testing.

GUARANTEE

Upon completion and before final acceptance of the work, the Contractor shall furnish the Engineer a written guarantee stating that all works executed are free from defects on materials and workmanship. The guarantee shall be for a period of one year from the date of the final acceptance. Any work that becomes defective during the said period shall be corrected / replaced by the Contractor at his own expense in a manner satisfactory to the Authority.

ITEM 18 : PROJECT BILLBOARD


SPECIFICATION

The Project Billboard shall be installed at location(s) designated by the Engineer.


The size and specifications of materials for the standard billboard shall be 4ft. x 8ft. (1,200mm x 2,400mm) using ½ inch (12mm) marine plywood or tarpaulin poster on 3/16 inch (5mm) marine plywood.

Project billboards shall not contain Name(s) and/or picture(s) of any personages.

See attached drawings for further details of the standard billboard.



STANDARD PROJECT BILLBOARD



BILLBOARD FRAME

(NOT TO SCALE, ALL DIMENSIONS ARE IN MILLIMETERS)

“To all our contractors, suppliers, and service providers, all we ask is for you to

SPEED UP

your contracts and **FINISH**

AHEAD of schedule,

WITHOUT SACRIFICING

QUALITY

of work, and **REASONABLENESS OF COST** agreed upon. Gawin niyo ‘yan at hindi tayo maghihiwalay ng landas (Do that and we will not part ways).”

A Message from
DOTr Secretary Arthur Tugade



@DOTrPH

@DOTrPH

www.dotr.gov.ph

ITEM 19 : SAFETY SIGNAGES AND BARRICADES

DESCRIPTION

This work includes the furnishing and installing of safety signages and barricades in accordance with the specifications and to the details shown below in the drawings, or as directed by the Engineer.


SPECIFICATION

The Signage's and Barricades shall be installed at location(s) designated by the Engineer.

The sizes of the standard signages shall be 2-2/3ft x 4ft (800mm X 1,200mm) for fixed type and 2ft x 2-2/3ft (600mm x 800mm) for mobile type. For barricade standard 2ft x 2-2/3ft (600mm x 800mm) shall be provided.

The materials to be used for signages and barricades are ½ inch (12mm) marine plywood or tarpaulin poster on 2" x 2" (50mm x 50mm) good lumber frame (see drawing below).

The printing or painting shall be the discretion of the Engineer.



SECTION VII
PROJECT DRAWINGS

SECTION VII

PROJECT DRAWINGS (SEE ISSUED APPROVED PLANS)

LIST OF DRAWINGS:

- 01 of 19 Vicinity Map, Development Plan, General Notes and List of Drawings and Design Parameters
- 02 of 19 Demolition, Removal and Clearing Layout
- 03 of 19 General Plan and Mooring and Fendering System Layout
- 04 of 19 Containment and Anchorage Layout and Storm Drainage Layout
- 05 of 19 Off-Shore Elevation, Rear Elevation, Side Fence, Blow-Up Detail -1 and Blow-Up Detail - 2
- 06 of 19 Station 0 + 000, Section Thru X, Station 0 + 010, Station 0 + 030, Station 0 + 050 and Station 0 + 070
- 07 of 19 Station 0+090, Station 0+100, Station 0+110, Station 0+130, Station 0+133 and Station 0+145.5
- 08 of 19 Detail of Pre-Stressed Concrete Sheet Pile
- 09 of 19 Detail of Reinforced Concrete Corner Sheet Pile
- 10 of 19 Detail of Coping Wall, Detail of Mooring Block and Mooring Attachment and Detail of Fender Block and Fender Attachment
- 11 of 19 Installation Detail of Roller Ramp and Detail of Roller Ramp.
- 12 of 19 Typical Details of Tie-Rod Assembly, Detail of Anchor Wall, Detail of Retaining Wall and Detailed Schedule of Concrete Blocks.
- 13 of 19 Typical Portland Cement Concrete Pavement Details, Detail of Reinforced Concrete Pavement, Detail of 15 Ton Mooring Bollard (Single Pillar) and Detail of D-Type Fender (500H X 500W X 2000L)
- 14 of 19 Wharf View of Covered Walkway, Rear View of Covered Walkway Showing Attached Fence Rear View of Covered Walkway Showing Attached Fence and Gate and Detail of Gate (Inner Elevation)
- 15 of 19 Section Thru B (Truss-2), Section Thru A (Truss-1) and Side Fence Detail
- 16 of 19 Ceiling Blow-Up Detail, Truss-2 Ceiling Detail and Truss-1 Ceiling Detail
- 17 of 19 Column-Truss Connection Detail, Truss-Purlin Connection Detail, Reinforcement Detail of Side Fence and Detail of Foundation/ Pedestal Post

- 18 of 19 Walkway Roofing Elevation, Detail of Girder, Detail of Truss-2, Detail of Truss-1, Section Z – Z and Plans Showing Purlins
- 19 of 19 Reflected Ceiling Plan, Lighting Layout Plan, Section Thru B, General Notes, Legend and LP Schedule of Load.

SECTION VIII

BILL OF QUANTITIES
and
ATTACHMENTS

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
1	GENERAL EXPENSES				
1.01	Mobilization, demobilization and cleaning	lot	1		
1.02	Rental of temporary site office and residence for the Engineer and staff	mo.	12		
1.03	Maintain temporary site office and residence for the Engineer and staff	mo.	12		
1.04	Provide Construction Safety and Health Program in the execution of the project	mo.	12		
TOTAL FOR BILL NO. 1					

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2	FASTCRAFT BERTH				
2.01	Demolish and dispose existing covered walk	sq.m.	48		
2.02	Demolish and dispose existing fence	l.m.	13		
2.03	Demolish and dispose existing plant box and smoothen with mortar	sq.m.	494		
2.04	Excavation of existing seabed	cu.m.	500		
2.05	Supply and place 3,500 psi concrete for rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block	cu.m.	413		
2.06	Supply and install steel reinforcement for rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block	kg.	39,621		
2.07	Supply, fabricate and install Concrete blocks including lifting handle	cu.m.	65		
2.08	Supply and deliver to site 0.35m x 0.60m PSC sheet piles	l.m.	2,964		
2.09	Supply and deliver to site R.C. Corner piles a) R.C. Corner pile No. 1 b) R.C. Corner pile No. 2	l.m. l.m.	12 12		
2.10	Handle, pitch and drive PSC sheet piles and RC corner piles	l.m.	2,988		
2.11	Chipping of newly driven PSC sheet piles & R.C. Corner piles including disposal	no.	249		

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.12	Supply and place 50-100 kg. Core rocks	cu.m.	1,753		
2.13	Supply and Install Geotextile Fabric	sq.m.	1,382		
2.14	Supply and place Sand and Gravel fill	cu.m.	3,404		
2.15	Supply, spread and compact Selected fill	cu.m.	864		
2.16	Supply, spread and compact aggregate base course	cu.m.	320		
2.17	Supply, and place gravel bedding	cu.m.	22		
2.18	Construct portland cement concrete pavement (300mm thk.) including dowel bars and construction joints	sq.m.	680		
2.19	Construct portland cement concrete pavement (200mm thk.) including dowel bars and construction joints	sq.m.	918		
2.20	Supply and install Tie-rod including accessories a) 42mm Ø x 8.60m	set	65		
2.21	Supply and deliver to site rubber dock fender (D-type, 500H x 500W x 2000L) including accessories	set	30		
2.22	Install rubber dock fender and accessories	set	30		

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.23	Supply and deliver to site mooring bollard (15 Tons, Single Pillar) including accessories	set	15		
2.24	Install mooring bollards (Single Pillar) and accessories	set	15		
TOTAL FOR BILL NO. 2					

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
3	COVERED WALKWAY				
3.01	Excavation and backfilling works	cu.m.	1		
3.02	Supply and place gravel bedding	cu.m.	3		
3.03	Supply and place 3,500 psi concrete for covered walkway foundation	cu.m.	12		
3.04	Supply and install steel reinforcement for covered walkway foundation	kg.	1,591		
3.05	Construct 150mm thick CHB wall including reinforcement	sq.m.	9		
3.06	Supply and place cement plaster finish	sq.m.	20		
3.07	Supply, fabricate & install cyclone wire for fence & gate including accessories	sq.m.	258		
3.08	Supply, fabricate & install G.I pipe (200mm diameter) column & accessories	set	34		
3.09	Supply and install roof framings and accessories	lot	1		
3.10	Supply and install polycarbonate roofing materials and accessories	sq.m.	185		
3.11	Supply and install aluminum cladding and accessories	sq.m.	1,575		
3.12	Painting works for concrete surfaces	sq.m.	20		
3.13	Application of anti-rust paint for metal surfaces	sq.m.	1,561		

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
3.14	Painting works for metal surfaces (Quick dry enamel)	sq.m.	1,561		
3.15	Supply, fabricate and install roller ramp & accessories	set	7		
3.16	Supply and install electrical materials for the covered walkway	lot	1		
TOTAL FOR BILL NO. 3					

BILL OF QUANTITIES
CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
 Port of Tagbilaran, Bohol



NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
4.01	4 REIMBURSABLE ITEMS Provide reimbursable items necessary in the implementation of the project as determined by the Authority	lot	1	601,706.28	601,706.28
TOTAL FOR BILL NO. 4					601,706.28

BASIS OF PAYMENT FOR WORK ITEMS INCLUDED IN THE PROPOSAL

The work items included in the proposal and the basis of payments are as follows:

BILL NO. 1

GENERAL EXPENSES

Item 1.01 Mobilization, demobilization and cleaning

The quantity to be paid for shall be the minimum equipment requirement enumerated in the bid documents mobilized, demobilized and cleaning of the site and accepted by the Engineer. The contract lump sum price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to mobilize and demobilize all the minimum equipment requirement enumerated in the bid documents including cleaning of the site. Fifty percent (50%) of the total amount shall be payable after the mobilization activity while the remaining (50%) payable after demobilization and cleaning.

Item 1.02 Rental of temporary site office and residence for the Engineer and staff

The quantity to be paid for shall be the actual rental for temporary site office and residence for the engineer and staff and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary for the provision of temporary site office and residence for the engineer and staff at least 48.00 m²

Item 1.03 Maintain temporary site office and residence for the Engineer and staff

The quantity to be paid for shall be the actual services rendered in maintaining the site office and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the maintenance of the temporary site office and residence as well as other expenses such as provision for electric power, telephone bill, potable water supply, janitorial and security services.

Item 1.04 Provide construction safety and Health Program in the execution of the project

The quantity to be paid for shall be the actual implementation of construction safety and health program and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the implementation of the Construction Safety and Health Program, as required and approved by the Department of Labor and Employment (DOLE).

BILL NO. 2

FASTCRAFT BERTH

Item 2.01 Demolish and dispose existing covered walk

The quantity to be paid for shall be the actual area in square meter of existing covered walk, demolished and disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.02 Demolish and dispose existing fence

The quantity to be paid for shall be the actual length in linear meter of existing fence, demolished and disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.03 Demolish and dispose existing plant box and smoothen with mortar

The quantity to be paid for shall be the actual area in square meter of existing plant box, demolished and disposed and smoothened with mortar in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.04 Excavation of existing seabed

The quantity to be paid for shall be the actual volume in cubic meter of existing seabed, excavated in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.05 Supply and place 3,500 psi concrete for the rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete for the rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.06 Supply and install steel reinforcements for the rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel bars for the rc curb, coping wall, anchor wall, retaining wall, mooring block and fender block, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.07 Supply, fabricate and install concrete blocks including lifting handle

The quantity to be paid for shall be the actual volume in cubic meter of concrete blocks including lifting handle, supplied, fabricated and installed in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.08 Supply and deliver to site 0.35m x 0.60m PSC sheet piles

The quantity to be paid for shall be the actual length in linear meter of 0.35m x 0.60m PSC sheet piles, supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.09 Supply and deliver to site RC corner piles

- a) RC corner pile no. 1
- b) RC corner pile no. 2

The quantity to be paid for shall be the actual length in linear meter of RC corner piles of various sizes, supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.10 Handle, pitch and drive PSC sheet piles and RC corner piles

The quantity to be paid for shall be the actual length in linear meter of PSC sheet piles and RC corner piles to be handled, pitched and driven in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.11 Chipping of newly driven PSC sheet piles and RC corner piles including disposal

The quantity to be paid for shall be the actual length in linear meter of newly driven PSC sheet piles and RC corner piles to be chipped off up to required elevation including disposal of debris in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.12 Supply and place 50-100 kg. rocks

The quantity to be paid for shall be the actual volume in cubic meter of 50-100 kg. rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.13 Supply and install geotextile fabric

The quantity to be paid for shall be the actual area in square meter of geotextile filter fabric, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.14 Supply and place sand and gravel fill

The quantity to be paid for shall be the actual volume in cubic meter of sand and gravel fill, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of sand and gravel fill shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.15 Supply, spread and compact selected fill

The quantity to be paid for shall be the actual volume in cubic meter of selected fill to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.16 Supply, spread and compact aggregate base course

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course, to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.17 Supply and place gravel bedding

The quantity to be paid for shall be the actual volume in cubic meter of gravel bedding, to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.18 Construct portland cement concrete pavement (PCCP, 300mm thk.) including dowel bars and construction joints

The quantity to be paid for shall be the actual area in square meter of portland cement concrete pavement (PCCP, 300mm thk.) including dowel bars and construction joints to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.19 Construct reinforced concrete pavement (200mm thk.) including temperature bars

The quantity to be paid for shall be the actual area in square meter of reinforced concrete pavement (= 200mm thk.) including temperature bars to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.20 Supply and install 42mmØ x 8.60m tie-rod including accessories

The quantity to be paid for shall be the actual quantity in set of 42mmØ x 8.60m tie-rod including accessories, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.21 Supply and deliver to site rubber dock fender (D-type 500H x 500W x 2000L) including accessories

The quantity to be paid for shall be the actual quantity in set of rubber dock fender (D-type 500H x 500W x 2000L) including accessories, supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.22 Install rubber dock fender including accessories

The quantity to be paid for shall be the actual quantity in set of rubber dock fender including accessories, installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.23 Supply and deliver to site mooring bollard (15 Tons, Single Pillar) including accessories

The quantity to be paid for shall be the actual quantity in set of mooring bollard (15 Tons, Single Pillar) including accessories, supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 2.24 Install mooring bollard (Single Pillar type) including accessories

The quantity to be paid for shall be the actual quantity in set of mooring bollard (Single Pillar) including accessories, installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

BILL NO. 3

COVERED WALKWAY

Item 3.01 Excavation and backfilling works

The quantity to be paid for shall be the actual volume in cubic meter of backfilling works, excavated and backfilled in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.02 Supply and place gravel bedding

The quantity to be paid for shall be the actual volume in cubic meter of gravel bedding, to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.03 Supply and place 3,500 psi concrete for covered walkway foundation

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete for covered walkway foundation, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.04 Supply and install steel reinforcements for superstructure

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel bars, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.05 Construct 150mm thk. CHB wall including reinforcement

The quantity to be paid for shall be the actual area in square meter of reinforced concrete pavement (= 200mm thk.) including temperature bars to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.06 Supply and place cement plaster finish

The quantity to be paid for shall be the actual area in square meter of cement plaster finish, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.07 Supply, fabricate and install cyclone wire for fence and gate including accessories

The quantity to be paid for shall be the actual area in square meter of cyclone wire for fence and gate including accessories, supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.08 Supply, fabricate and install GI Pipe (200mm diameter) column and accessories

The quantity to be paid for shall be the actual quantity in set of GI Pipe (200mm diameter) column and accessories, supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.09 Supply and install roof framings and accessories

The quantity to be paid for shall be the actual quantity in lot of roof framings and accessories, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.10 Supply and install polycarbonate roofing materials and accessories

The quantity to be paid for shall be the actual area in square meter of polycarbonate roofing materials and accessories, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.11 Supply and install aluminum cladding and accessories

The quantity to be paid for shall be the actual area in square meter of aluminum cladding and accessories, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.12 Painting works for concrete surfaces

The quantity to be paid for shall be the actual area in square meter of concrete surfaces to be painted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.13 Application of anti-rust paint for metal surfaces

The quantity to be paid for shall be the actual area in square meter of metal surfaces to be applied with anti-rust paint in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.14 Painting works for metal surfaces (quick dry enamel)

The quantity to be paid for shall be the actual area in square meter of metal surfaces (quick dry enamel) to be painted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.15 Supply, fabricate and install roller ramp and accessories

The quantity to be paid for shall be the actual quantity in set of roller ramp and accessories, supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

Item 3.16 Supply and install electrical materials for the covered walkway

The quantity to be paid for shall be the actual quantity in lot of electrical materials for the covered walkway, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

BILL NO. 4

REIMBURSABLE ITEMS

Item 4.01 Provide reimbursable items necessary in the implementation of the project as determined by the Authority.

The quantity to be paid for shall be the actual quantity of determined items by the Authority deemed necessary in the implementation of the project, supplied, delivered and accepted by the Authority. Payment for said items shall be made only upon complete delivery/acceptance of such. The contract lump sum price shall be full compensation for providing all determined items. The Contractor's Profit and Overhead, Contingencies and Miscellaneous (OCM) should not be included in the cost of said items. The amount of bid should be fixed as indicated in the amount stated in the Bid Data Sheet [ITB Clause 13.1(a)] and as provided in the Bill of Quantities (BOQ). Claims for payment shall be supported by Official Receipt(s) (OR) and at least three (3) canvasses. The amount to be paid for shall be the price indicated in the OR but should not exceed the contract lump sum price. The determined items shall be the property of PPA. Operation and maintenance shall be borne by PPA.

FACILITIES TO BE PROVIDED FOR THE ENGINEER & HIS STAFF

TEMPORARY FACILITIES OF THE CONTRACTOR

The Contractor shall provide and maintain such temporary offices, stores, workshops, latrines, housing and messing accommodations as are necessary. The location, dimension and layout of such buildings and places shall be subject to the approval in writing of the Engineer. By the end of the contract, the Contractor shall remove all buildings and the area shall be cleared and graded as required by the Engineer.

SITE OFFICE AND RESIDENCE FOR THE ENGINEER & STAFF

The Contractor shall provide and maintain a temporary site office and residence with an area of at least 48 square meters for use of the Engineer and staff, including all the necessary electricity, water, communication services and consumables.

MINIMUM EQUIPMENT REQUIREMENTS

1	unit/s	Air-Compressor (250 cfm, minimum), owned/leased
1	unit/s	Backhoe (0.40 cu.m., 94.30 hp, minimum), owned/leased
1	unit/s	Clamshell, owned
1	unit/s	Concrete Cutter, owned
2	unit/s	Concrete Mixer (1-bagger, minimum), owned
1	unit/s	Concrete Bucket, owned
1	unit/s	Concrete Screeder, owned
2	unit/s	Concrete Vibrator (3.5 hp, minimum), owned
1	unit/s	Crane Barge (319 GW, minimum) with 60T crane, owned/leased
1	unit/s	Crawler Crane (30T, minimum), owned/leased
1	unit/s	Pile Hammer (Diesel, 10,500 kg.m.), owned/leased
1	unit/s	Diving Equipment (complete), owned/leased
1	unit/s	Drop Hammer (2T, minimum), owned
2	unit/s	Dump Truck (8 cu.m., minimum), owned
2	unit/s	Bar Bender (electric, 25mm dia min.), owned
2	unit/s	Bar Cutter (electric, 25mm dia min.), owned
1	unit/s	Jack Hammer, owned/leased
1	unit/s	Oxy/Acetylene Cutting Outfit, owned
1	unit/s	Payloader (80 hp, minimum), owned/leased
1	unit/s	Plate Compactor (5hp, minimum), owned
1	unit/s	Road Grader (125 hp, minimum), owned/leased
1	unit/s	Road Roller (12.05T, vibratory, minimum), owned/leased
2	unit/s	Transit Mixer (5-6 cu.m. cap., minimum), owned/leased
1	unit/s	Tugboat (500hp, minimum), owned/leased
1	unit/s	Water Truck with pump (1,000 gal., minimum), owned
2	unit/s	Welding Machine (400 amp., minimum), owned
1	unit/s	Cargo Truck (5T, minimum), owned

CONSTRUCTION SAFETY AND HEALTH REQUIREMENT

The Contractor shall implement the construction safety and health program in accordance with the applicable provisions of the Occupational Safety and Health Standards (OSHS) of the Department of Labor and Employment (DOLE).

The Contractor, subject to the approval of the Engineer shall provide and maintain throughout the duration of the contract a medical room with at least 15 square meters together with all necessary supplies to be sited in the Contractor's main area.

The Contractor shall provide the following minimum requirements:

LABOR

- 1 no. Safety Engineer / Officer
- 1 no. Nurse / Health Officer

EQUIPMENT / MATERIALS

Personnel Protective Equipment

- 49 pcs. Hard Hats
- 49 pcs. Gloves
- 7 pcs. Goggles
- 1 pcs. Aprons
- 1 pcs. Safety Belts
- 49 pcs. Safety Shoes
- 1 pcs. Life Lines

Safety Devices

- 1 lot Barricades
- 1 lot Warning signs
- 2 units Fire extinguisher

Medical and First Aid System - For fourteen (14) mos.

NOTE:

The Contractor shall provide the above-cited minimum construction safety and health requirements or as required by the Engineer.

**REVISED SCHEDULE OF MINIMUM TEST REQUIREMENTS OF
 CONSTRUCTION MATERIALS FOR PPA INFRASTRUCTURE PROJECTS**

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
I. Construction of Pier/Wharf, Platform and Ramp		
Structural Concrete (SC)		
A Portland Cement	Quality Test	For every 2,000 bags (40kg) or fraction thereof
B Fine Aggregate	Quality Test for Grading, Elutration (wash), Bulk Specific Gravity, Absorption, Mortar Strength, Soundness, Organic Impurities, Unit Weight, % Clay Lumps and Shale	For every 1,500 cubic meter or fraction thereof
C Coarse Aggregate	Quality Test for Grading, Bulk Specific Gravity, Absorption and Abrasion	For every 1,500 cubic meter or fraction thereof
D Water	Certificate from the Engineer or Quality Test for Density and Chloride Content	One per source
E Steel Bars	Mill Certificate and Quality Test for Chemical Composition and Mechanical Properties	For every 10,000 kg or fraction thereof
F Concrete	Compressive Strength on cylinder samples	1 set consisting of 3 concrete cylinder samples shall be taken from each day's pouring and to represent not more than 75 cu m of concrete or fraction thereof
	Slump Test	For every mix
G Admixture and Concrete Curing Materials	Quality Test	One per shipment
Piling (P)		
A Concrete Piles	Fabrication Report	One per fabrication
1 Concrete	Same test as for SC (F)	Same frequency as SC (F)
2 Steel Bars	Same test as for SC (E)	Same frequency as SC (E)
3 High Tension Strand	Test for Chemical Composition and Mechanical Properties	For every 20000kg or fraction thereof

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
4 Coarse Aggregates	Same Test as for SC (C)	Same frequency as SC (C)
5 Fine Aggregates	Same Test as for SC (B)	Same frequency as SC (B)
B Steel Pipe Piles	Fabrication Report, Mill Certificate and Quality Test for Chemical and Mechanical properties	One per fabrication
1 Steel	Chemical Composition (refer below) <ul style="list-style-type: none"> - Under 14" (355 60mm) Outside Diameter - 14" to 36" (355 6 to 914mm) Outside Dia - Over 36" (914mm) Outside Diameter Mechanical/Tensile	2 from 200 pipe or fraction thereof 2 from 100 pipe or fraction thereof 2 from 3000ft (914m) or fraction thereof One (1) tension test shall be made on one length or fraction thereof of each size, or one piece of skelp representing each lot of 200 lengths or fraction thereof of each size
2 Polyurethane Coating	Mill Certificate and Quality Test	One per fabrication
3 Concrete	Same test as for SC (F)	Same frequency as SC (F)
4 Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
5 Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
6 Steel Bars	Same Test as SC (E)	Same frequency as SC (E)
7 Water	Same Test as SC (D)	Same frequency as SC (D)
Rubber Dock Fenders (RDF)	Physical Test	All units
Accessories	Performance Test for Energy Absorption and Reaction Force	All units
Washer and Fixing Bolt, Anchor Bolt	Physical Test	All units
	Quality Test for Chemical Composition and Mechanical Properties	One per fabrication

Handwritten signature/initials

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Mooring Bollard (MB) and Accessories (Hexagon Nuts, Plain Washer, Anchor Ring and Anchor Bolt)	Physical Test Quality Test for Chemical Composition and Mechanical Properties	All Units One per fabrication
II. Construction of Back-Up Area, Causeway and Pavement Sheet Piling (SP) <ul style="list-style-type: none"> A Concrete Sheet Piles <ul style="list-style-type: none"> 1 Concrete 2 Steel Bars 3 High Tension Strands 4 Fine Aggregates 5 Coarse Aggregates B Steel Pipe Piles <ul style="list-style-type: none"> 1 Steel 2 Concrete 3 Fine Aggregate 4 Steel Bars 	Same test as for SC (F) Same test as for SC (E) Same test as for P (A 3) Same test as for SC (B) Same Test as for SC (C) Same test as for P (B1) Same test as for SC (F) Same test as for SC (B) Same test as for SC (E)	Same frequency as SC (F) Same frequency as SC (E) Same frequency as P (A 3) Same frequency as SC (B) Same frequency as SC (C) Same frequency as P (B1) Same frequency as SC (F) Same frequency as SC (B) Same frequency as SC (E)

Handwritten signature/initials

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Rocks	Test for Apparent Specific Gravity and Abrasion	For every 1,500 cubic meter or fraction thereof
Geotextile Filter	Physical and Mechanical Test Mill Certificate	One per batch One per batch
Sand and Gravel Fill	Quality Test for Organic Impurities and Grading	For every 1,500 cubic meter or fraction thereof
Selected Fill	Quality Test for Grading, Plasticity and Laboratory Compaction Test Laboratory California Bearing Ratio (CBR) Field Density Test	For every 1,500 cubic meter or fraction thereof For every 2,500 cubic meter or fraction thereof For every layer of 150mm of compacted depth at least one group of three In-situ density test for every 500 sq m or fraction thereof
Aggregate Base Course	Quality Test for Grading and Plasticity Quality Test for Grading, Plasticity, Abrasion and Laboratory Compaction Test Laboratory California Bearing Ratio (CBR) Field Density Test	For every 300 cubic meter or fraction thereof For every 1,500 cubic meter or fraction thereof Same frequency as Selected Fill Same frequency as Selected Fill
Portland Cement Concrete Pavement (PCCP)		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Steel Bars (Dowels)	Same test as for SC (E)	Same frequency as SC (E)
F Joint Filler	Quality Test	One (1) per shipment

Handwritten signature/initials

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
G Admixture and Concrete Curing Material	Same test as for SC (G)	Same frequency as SC (G)
H Concrete	Same test as for SC (F) Flexural Test	Same frequency as SC (F) 3 beam samples for every 330 sq m or fraction thereof
I Completed Pavement	Core Test	1 set (3 specimen) for every 2,500 sq m and fraction thereof
Interlocking Concrete Blocks		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Admixture & Concrete Curing Materials	Same test as for SC (G)	Same frequency as SC (G)
F Completed Blocks	Physical Test and Compressive Strength	6 blocks per day of fabrication
Cement Treated Base Course (CTB)		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine & Coarse Aggregates	Quality Test for Grading, Abrasion and Soundness	For every 1,500 cubic meter or fraction thereof
C Water	Same test as for SC (D)	Same frequency as SC (D)
D Completed CTB	Field Density Test	For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof
Retaining Wall/Coping Wall/RC Curb/RC Ditch/Shear Key/Concrete Blocks/Lean Concrete		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)

lme

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Steel Bars	Same test as for SC (E)	Same frequency as SC (E)
F Admixture and Concrete Cunnng	Same test as for SC (G)	Same frequency as SC (G)
G Concrete	Same test as for SC (F)	Same frequency as SC (F)
Tie Rod		
A Steel	Same test as for SC (E)	One per batch
B Assembly	Performance Test (Tension)	One per batch
Tie Bars and Dowels	Same test as for SC (E)	For every 10,000 kg or fraction thereof per Tie bars and Dowels
Pipe Culverts and Storm Drains		
A Pipes	Test for Strength, Absorption and Physical	For every 50 pieces
B Mortar or Joint	Same Test as for SC (A, B and D) Alternative Test Same test as for SC (F) and Inspection Report	For every 25 pieces
Concrete Hollow Blocks		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Water	Same test as for SC (D)	Same frequency as SC (C)
D Concrete	Same test as for SC (F)	Same frequency as SC (F)
E Completed CHB	Quality Test	One for every 500 pieces or fraction thereof
Construction Joints (CJ)		
A Angle Bars	Test for Physical and Mechanical Properties	One per batch
B Steel Bars	Same test as for SC (E)	One per batch
C Zinc (Hot Dip Galvanizing) Coatings	Physical Test for Appearance, Stripping, Weighing, Adherence and Adhesion Coating Thickness Magnetic Thickness Measurement	All units 1 set (3 specimen) for every 100,000 sq mm or fraction thereof

Handwritten signature/initials

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Sacked Concrete		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Concrete	Same test as for SC (F)	Same frequency as SC (F)
F Sack (jute)	Physical Test	One for every 50 pieces
Rubble Concrete		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Concrete	Same test as for SC (F)	Same frequency as SC (F)
F Rocks	Same test as for ROCKS	Same frequency as ROCKS
Earthworks		
A Sub-grade preparation	Grading Test Plasticity Test (LL, PL, PI) Laboratory Compaction Test Density Test	For every 1,500 cubic meter or fraction thereof For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof
B Structure Excavation	If excavated materials shall be used as Backfill Grading Test Plasticity Test (LL, PL, PI) Laboratory Compaction Test Density Test	For every 1,500 cubic meter or fraction thereof For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof

CAC

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
III Port Operations Building/Passenger Terminal Building/Transit Shed/Warehouse		
STRUCTURAL WORKS Refer to Structural Concrete (SC) and Piling Works (P)		
ARCHITECTURAL WORKS		
Ceramic – Filled Liquid Membrane / Water Proofing, Hydrophobic Poreblocking Ingredients with Superplasticizer	Physical Property, Mechanical and Chemical Property, Leak Test / Flood Test	One per shipment
Paint	Quality Test	One 4-L can for every 100 cans or fraction thereof
Ceramic Tile	Inspection and Evaluation Report from the Engineer	One per shipment
Stainless Steel	Inspection and Evaluation Report from the Engineer	One per shipment
Roofing Materials	Inspection and Evaluation Report from the Engineer	One per shipment
Ceiling Materials	Inspection and Evaluation Report from the Engineer	One per shipment
ELECTRICAL AND MECHANICAL WORKS		
Wires / Cables	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment
Electrical Devices	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment
Fire Alarm System	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Wiring Devices	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment

Handwritten signature/initials


Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Protective Devices	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment
Telephone System	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
CCTV System	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
CATV System	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Background Music and Paging System	Inspection and Evaluation Report from the Engineer, Testing and Commissioning	One per item
Air Conditioning Units & Ventilation	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Conduit Pipes	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Lighting Fixtures	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
PLUMBING WORKS		
Pipes	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item


UAC

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Fixtures	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Pipe Culverts	Compression Strength Inspection and Evaluation Report from the Engineer	For every size not more than 25 pipes cast in the field
IV Miscellaneous Materials Fencing A Barbed Wire, Cyclone Wire Mesh, Chain Link B Concrete Post	Physical Test (Dimensions and Coatings) Refer to Superstructure (SC)	One per Batch Refer to Superstructure (SC)
Lamp Post A Structural Steel B Zinc (Hot Dip Galvanizing) Coatings	Physical Test (Dimensions) Same test as for SC (E) Same test as for CJ (C)	All units One per batch
Drainage Steel Grating	Same test as for SC (E) Inspection Report	One (1) batch
Metal Pipe (Cast Iron Galvanized, etc)	Physical Test (Dimensions and Coatings)	1 per delivery
Welding Works	Destructive and Non Destructive Test	One (1) per lot

- NOTES**
1. Testing of RDF shall be performed only by an independent Testing Laboratory duly accredited by BRS, DOST and PPA
 2. Testing of other materials shall be performed only by an independent Testing Laboratory duly accredited by BRS and PPA.
 3. All other issuances which are otherwise inconsistent herewith are hereby revoked or otherwise amended.

Approved


RAUL T. SANTOS
 Officer-In-Charge,
 Office of the General Manager



SECTION IX
BIDDING FORMS

Bid Form

Date: _____

ITB No: _____

To: **Philippine Ports Authority**
Bonifacio Drive, South Harbor,
Port Area, Manila

We, the undersigned, declare that:

- (a) We have examined and have no reservation to the Bidding Documents, including Addenda, for the **Contract Construction of Additional Fastcraft Berth, Port of Tagbilaran, Bohol**;
- (b) We offer to execute the Works for this Contract in accordance with the Bid and Bid Data Sheet, General and Special Conditions of Contract accompanying this Bid;

The total price of our Bid, excluding any discounts offered below is:

BILL NO	DESCRIPTION	TOTAL AMOUNT
1	General Expenses	P
2	Fastcraft Berth	
3	Covered Walkway	
4	Reimbursable Items	
	TOTAL AMOUNT OF BID (including VAT)	P

The discounts offered and the methodology for their application are: insert information;

- (c) Our Bid shall be valid for a period of 120 days from the date fixed for the Bid submission deadline in accordance with the Bidding Documents, and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- (d) If our Bid is accepted, we commit to obtain a Performance Security in the amount of insert percentage amount percent of the Contract Price for the due performance of the Contract;

- (e) Our firm, including any subcontractors or suppliers for any part of the Contract, have nationalities from the following eligible countries: *[insert information]*;
- (f) We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;
- (g) Our firm, its affiliates or subsidiaries, including any subcontractors or suppliers for any part of the Contract, has not been declared ineligible by the Funding Source;
- (h) We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and
- (i) We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.
- (j) We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the **Construction of Additional Fastcraft Berth, Port of Tagbilaran, Bohol of the Philippine Ports Authority.**
- (k) We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: _____

In the capacity of: _____

Signed: _____

Duly authorized to sign the Bid for and on behalf of: _____

Date: _____

**STATEMENT OF ALL ON-GOING GOVERNMENT AND PRIVATE CONTRACTS,
INCLUDING CONTRACTS AWARDED BUT NOT YET STARTED, WHETHER SIMILAR OR NOT SIMILAR IN NATURE**

Name of the Contract or Title Of the Project 1]	Owner's Name and Address	Nature/ Scope of Work 2]	Contractor's Role (in percentage) 3]	Total Contract Value At		Date of Award 5]	Value of Outstanding Works	Estimated Time of Completion	% of Accomplishment		Contract Duration 5]	
				Award	Escalated Value to Present Prices 4]				Project Completion	Planned	Actual	Start
A) Government Contracts i. On-going ii. Awarded but not yet started B) Private Contracts i. On-going ii. Awarded but not yet started												

NOTE:

- 1] As appearing or defined in the contract entered/executed by the parties
- 2] With special reference to the Scope of Works as described/enumerated in the advertised invitation To Bid.
- 3] Indicate whether as Sole Contractor, Sub-Contractor or Member in a Joint Venture / Consortium
- 4] Indicate the FOREX used if Contract Value is expressed in a currency other than the Philippine Peso. Specify the "Escalation Factor" used to escalate the Contract Value from completion date to the advertisement date of the invitation to Bid per section 23.11.2 (3) of R.A. 9184.
- 5] State Month and Year.

This Statement shall be supported by:

- a) Notice of Award and/or Contract
- b) Notice to Proceed

Name of Firm/Applicant

Authorized Signing Official

Date

STATEMENT OF THE BIDDER'S SINGLE LARGEST COMPLETED CONTRACT (SLCC) SIMILAR TO THE CONTRACT TO BE BID

Name of the Contract or Title Of the Project	Owner's Name and Address	Nature/Scope of Work	Contractor's Role and Percentage Of Participation	Total Contract Value At		Date of Award	Value of Outstanding Works	Contract Duration	
				Award	Completion			Escalated Value to Present Prices	Start

NOTE :

1. The prospective bidder must have completed an SLCC that is similar to the contract to be bid, and whose value, adjusted to current prices using the PSA consumer price indices, must be at least fifty percent (50%) of the ABC to be bid.
2. This Statement shall be supported by:
 - a. Notice of Award and / or Notice to Proceed.
 - b. Project Owner's Certificate of Final acceptance issued by the owner other than the Contractor or Constructors Performance Evaluation System (CPES) Final Rating, which must be at least satisfactory.

Name of Firm/Applicant

Authorized Signing Official

Date

EXPERIENCE RECORD ON SIMILARLY COMPLETED PROJECTS

Similar Major Operations of Work 1]	Unit of Measure	Quantity	Title of the Project				Unit of Measure	Quantity
			Title of the Project					
1. RC pile driving works (off-shore)	l.m.	1,370						
2. Reinforced Concrete Works	cu.m.	207						
3. Rock Works (50-100 kg./pc.)	cu.m.	877						
4. Placing of Fill Materials	cu.m.	2,134						
5. Construction of Portland Cement Concrete Pavement (PCCP)	sq.m.	799						

NOTE: 1] *Submit the Certificate of Completion/Certificate of Acceptance by the project owner, Final Recapitulation/Bill of Quantities and/or Constructor Performance Evaluation System (CPES) ratings, 1st, 2nd & Final visit (if applicable). Projects with no Certificate of Completion/Acceptance and Recapitulation/Bill of Quantities shall not be considered.*

2] *The Owner's Certificate of Final Acceptance; or the Constructors Performance Evaluation Summary (CPES) Final Rating and/or the Certificate of Completion, must be satisfactory.*

Name of Firm/Applicant

Authorized Signing Official

Date

FINANCIAL DATA

- A. The prospective bidder's audited Financial Statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "RECEIVED" by the Bureau of Internal Revenue (BIR), or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission.

	Year
1. Total Assets	
2. Current Assets	
3. Total Liabilities	
4. Current Liabilities	
5. Net worth (1-3)	
6. Net Working Capital (2-4)	

- B. The computation of the bidders Net Financial Contracting Capacity (NFCC) must be at least equal to the ABC to be bid, as follows:

NFCC = [(Current assets minus current liabilities) (15)] minus the value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started coinciding with the contract to be bid.

NFCC = _____

Attached herewith are certified true copies of the audited financial statements stamped received by the BIR or BIR authorized collecting agent for the latest/immediately preceding calendar year.

Name of Firm/Applicant

Authorized Signing Official

Date: _____

NOTES:

If Partnership or Joint Venture, each Partner or Member Firm of Joint venture shall submit separate financial statements.

LIST OF CONTRACTOR'S PERSONNEL

I hereby declare that the following key personnel enumerated below, with attached resume/bio-data, including valid PRC License, for the various positions / functions, are available for the project applied for:

Position of Key Personnel	Name	No. of Key Personnel	Similar Experience in the Position (Years) ¹⁾	Total Experience in the Position (Years)	Attachment(s)	Annex(es)
Project Manager					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " " -
Project Engineer					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " " -
Materials Engineer					PRC License (CE Preferred) Submit Valid and Renewed DPWH Certificate of Accreditation Submit Accreditation Identification Card as Materials Engineer Complete Qualification and Experience Data Certificate of Commitment	Annex " " -
Construction Safety and Health Officer					Certificate of Safety and Health Construction Related Course issued by DOLE Accredited Trainings Complete Qualification and Experience Data Certificate of Commitment	Annex " " -
Foreman					Complete Qualification and Experience Data Certificate of Commitment	Annex " " -
Other Position(s)					Complete Qualification and Experience Data Certificate of Commitment	Annex " " -

NOTE: 1. Minimum qualification requirements: (work experience is similar in nature and complexity to the project to be bid with regard to Registration Particulars of the Contractor's License)

- Project Manager - Five (5) years
- Project Engineer - Three (3) years
- Foreman - Five (5) years
- Materials Engineer - One (1) year
- Materials Engineer I - for projects costing up to 100M
- Materials Engineer II - for projects costing more than 100M

Name of Firm/Applicant

Authorized Signing Official

Date

REVISED FORM (September 2012)

LIST OF CONTRACTOR'S EQUIPMENT UNITS

I hereby declare that the following equipment listed below which are owned, leased or under purchase agreement are in good operating condition and are available for the duration of the project:

DESCRIPTION (Type, Model, Make)	No. of Unit(s)	Capacity Output 2]	Owned, Leased and/or under purchase agreement 1]	Submitted Proof of Ownership/Leased/ Purchase Agreement (Mark as Annex "A.....Z")	OTHER INFORMATIONS (As Applicable)				
					Manufacturer	Engine Serial No.	Chassis No./ Name of Vessel	Location	Status

1] Indicate if owned or leased as listed in the Checklist/Bidding Documents. For owned equipment, as required, submit proof of ownership (i.e. deed of sale, sales invoice, official receipt). For Water Truck, Dump Truck and Transit Mixer submit LTO Certificate of Registration and valid Official Receipt. For owned barge/tugboat, submit Marina Certificate of Ownership and valid Cargo Ship Safety Certificate. For newly purchased barge/tugboat, submit Deed of Sale together with an application for Marina Certificate of Ownership duly received/authenticated by Marina with corresponding valid Cargo Ship Safety Certificate. For leased equipment, submit duly notarized copy of lease contract together with a copy of the Marina Owner's (Lessor's) Certificate and valid Cargo Ship Safety Certificate.

2] The unit of each equipment shall be as indicated in the Checklist/Bidding Documents, i.e GW (for crane barge), DWT (for deck barge and hopper barge), TON (for crane, road roller and drop hammer), kg.-m/blow (for diesel hammer), cu.m (for dump truck), hp. (for tugboat, road grader, bulldozer and concrete vibrator), cfm (for compressor), gal. (for water truck with pump), amp. (for welding machine), bagger (for concrete mixer).

Name of Firm/Applicant

Authorized Signing Official

Date

OMNIBUS SWORN STATEMENT FOR SOLE PROPRIETORSHIP

REPUBLIC OF THE PHILIPPINES)
CITY OF _____)SS

AFFIDAVIT

I (Name), of legal age, (Civil Status), (Nationality), and residing at (Address), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the sole proprietor or authorized representative of (Name of Bidder) with office address at _____:
2. As the owner and sole proprietor or authorized representative of (Name of Bidder), I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, (as shown in the attached duly notarized "Special Power of Attorney" for the authorized representative);
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
6. The owner or sole proprietor is not related to the Head of Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the end – user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Name of Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
 - a) Carefully examine all of the Bidding Document;
 - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
 - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
 - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Construction of Additional Fastcraft Berth, Port of Tagbilaran, Bohol*.

9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this ___ day of ___ 20__ at _____, Philippines.

Bidder's Representative / Authorized Signatory

SUBSCRIBED AND SWORN to before me this ___ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. _____ and his/her Community Tax Certificate No. _____ issued on ___ at _____.

Witness my hand and seal this ___ day of [month] [year].

NAME OF NOTARY PUBLIC

Serial No. of Commission _____

Notary Public for _____ until _____

Roll of Attorneys No. _____

PTR No. _____ [date issued], [place issued]

IBP No. _____ [date issued], [place issued]

Doc. No. _____
Page No. _____
Book No. _____
Series of _____

OMNIBUS SWORN STATEMENT FOR PARTNERSHIP OR COOPERATIVE

REPUBLIC OF THE PHILIPPINES)
CITY OF _____)SS

A F F I D A V I T

I (Name), of legal age, (Civil Status), (Nationality), and residing at (Address), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of (Name of Bidder) with office address at (Address);
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, accompanied by the duly notarized Special Power of Attorney, Board/Partnership Resolution or Secretary's Certificate (whichever is applicable);
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the PPA General Manager or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers and members of (Name of Bidder) is related to the PPA General Manager, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the end- user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
 - a) Carefully examine all of the Bidding Document;
 - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
 - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
 - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Construction of Additional Fastcraft Berth, Port of Tagbilaran, Bohol*.

- 9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this ___ day of _____ 20__ at _____, Philippines.

Bidder's Representative / Authorized Signatory

SUBSCRIBED AND SWORN to before me this ___ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. _____ and his/her Community Tax Certificate No. _____ issued on ___ at _____.

Witness my hand and seal this ___ day of [month] [year].

NAME OF NOTARY PUBLIC

Serial No. of Commission _____
 Notary Public for _____ until _____
 Roll of Attorneys No. _____
 PTR No. _____ [date issued], [place issued]
 IBP No. _____ [date issued], [place issued]

Doc. No. _____
 Page No. _____
 Book No. _____
 Series of _____

OMNIBUS SWORN STATEMENT FOR CORPORATION OR JOINT VENTURE

REPUBLIC OF THE PHILIPPINES)
CITY OF _____)SS

AFFIDAVIT

I (Name), of legal age, (Civil Status), (Nationality), and residing at (Address), after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of (Name of Bidder) with office address at _____:
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for (Name of Project) of the Philippine Ports Authority, accompanied by the duly notarized Special Power of Attorney, Board Resolution or Secretary's Certificate;
3. (Name of Bidder) is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government / foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board;
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. (Name of Bidder) is authorizing the PPA General Manager or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers, directors, and controlling stockholders of (Name of Bidder) is related to the PPA General Manager, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management office or the or end- user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. (Name of Bidder) complies with existing labor laws and standards; and
8. (Name of Bidder) is aware of and has undertaken the following responsibilities as a Bidder:
 - a) Carefully examine all of the Bidding Document;
 - b) Acknowledge all conditions, local or otherwise, affecting the implementation of the contract;
 - c) Made an estimate of the facilities available and needed for the contract to be bid, if any; and
 - d) Inquire or secure Supplemental / Bid Bulletin(s) issued for the *Construction of Additional Fastcraft Berth, Port of Tagbilaran, Bohol.*

- 9. (Name of Bidder) did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

IN WITNESS WHEREOF, I have hereunto set my hand this ___ day of ___ 20__ at _____, Philippines.

Bidder's Representative / Authorized Signatory

SUBSCRIBED AND SWORN to before me this ___ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. _____ and his/her Community Tax Certificate No. _____ issued on ___ at _____.

Witness my hand and seal this ___ day of [month] [year].

NAME OF NOTARY PUBLIC

Serial No. of Commission _____
 Notary Public for _____ until _____
 Roll of Attorneys No. _____
 PTR No. _____ [date issued], [place issued]
 IBP No. _____ [date issued], [place issued]

Doc. No. _____
 Page No. _____
 Book No. _____
 Series of _____

REPUBLIC OF THE PHILIPPINES)
CITY OF _____)S.S.

BID-SECURING DECLARATION
Invitation to Bid No. _____

To : Philippine Ports Authority
Bonifacio Drive, South Harbor,
Port Area, manila

I, the undersigned, declare that:

1. I understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid-Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1 (b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA 9184; without prejudice to other legal action the government may undertake:
3. I understand that this Bid-Securing Declaration shall cease to be valid on the following circumstances:
 - (a) Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
 - (b) I am declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I failed to timely file a request for reconsideration or (ii) I filed a waiver to avail of said right;
 - (c) I am declared as the bidder with the Lowest Calculated Responsive Bid, and I have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I have hereunto set my hand this _____ day of _____ 20 ____ at _____, Philippines.

Name of Bidder's Authorized Representative
(Signatory's Legal Capacity)
AFFIANT

SUBSCRIBED AND SWORN to before me this ___ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. _____.

Witness my hand and seal this ___ day of [month] [year].

NAME OF NOTARY PUBLIC

Serial No. of Commission _____
Notary Public for _____ until _____
Roll of Attorneys No. _____
PTR No. ___, [date issued], [place issued]
IBP No. ___, [date issued], [place issued]
Doc. No. _____
Page No. _____
Book No. _____
Series of _____.

CONSTRUCTION METHODOLOGY

Name of Project : _____
Proposed Project Description : _____
Location : _____

MINIMUM SCOPE OF CONSTRUCTION METHODOLOGY

A. FASTCRAFT BERTH

1. Demolition and disposal of existing covered walk (48sq.m.)
2. Demolition and disposal of existing fence (13 l.m.)
3. Demolition and disposal of existing plant box (409 sq.m.)
4. Excavation of existing seabed (500 cu.m.)
5. Supply and placing of concrete (413cu.m.)
6. Supply and installation of steel reinforcement (39,621 kg.)
7. Supply and installation of concrete blocks (65 cu.m.)
8. Supply, driving and chipping of PSC sheet piles and corner piles (2,739 l.m.)
9. Supply and installation of core rocks (1,753 cu.m.)
10. Supply and installation of geotextile fabric (1,382 cu.m.)
11. Supply and placing of fill materials (4,268 cu.m.)
12. Supply and placing of aggregate base course (320 cu.m.)
13. Construction of Portland Cement Concrete Pavement (1,598 sq.m.)
14. Supply and installation of Tie-rods (65 sets)
15. Supply and installation of rubber dock fenders and mooring bollards (45 sets)

B. COVERED WALKWAY

1. Construction of covered walkway, complete with concrete foundation, GI pipe column, GI pipe roof framings, polycarbonate roofing, aluminum composite panel, electrical lightings, paintings and other architectural finishes (145.5m x 6.25m)
2. Construction of cyclone wire fence, gates and other accessories (145.5l.m.)

NOTES:

The narrative construction method will guide and familiarize the contractor and the PPA on how the project shall be carried out in accordance with the highest standard of workmanship.

The construction method shall be consistent with the Bar Chart / S-Curve Schedule, Equipment Schedule and Manpower Schedule.

Signature
(Authorized Signing Official)

MANPOWER SCHEDULE

Name of Project : _____

Proposed Project Description : _____

Location : _____

MANPOWER (Minimum)	CONTRACT DURATION (_____ Calendar Days)											
	M O N T H L Y											
	1	2	3	4	5	6	7	8	9	10	11	12
Project Manager												
Project Engineer												
Materials Engineer												
Construction Safety and Health Officer												
Foreman												
Specify other applicable positions, ie.:												
- Carpenter												
- Steelman												
- Mason												
- Electrician												
- Rigger												
- Others												

Signature
(Authorized Signing Official)

CASHFLOW BY QUARTER AND PAYMENT SCHEDULE

Name of Project: : _____

Proposed Project Description : _____

Location : _____

Project Duration (days or months)	Payment Schedule (Monthly, in Pesos)	Cash flow (Quarterly, in Pesos)
TOTAL		

NOTES

- The cash flow by quarter and payment schedule should be consistent with the Bar Chart and S-curb.
- Payment schedule shall not be more than once a month.

Signature
(Authorized Signing Official)

SECTION X
CONTRACT FORM

Republic of the Philippines
PHILIPPINE PORTS AUTHORITY
PPA Building, Bonifacio Drive, South Harbor,
Port Area, Manila, Philippines

CONTRACT
FOR THE CONSTRUCTION OF ADDITIONAL FASTCRAFT BERTH
PORT OF TAGBILARAN, BOHOL

This Contract made and entered into this _____ day of _____ 2019, in Manila, Philippines, by and between:

PHILIPPINE PORTS AUTHORITY, a government instrumentality created under Presidential Decree No. 857, as amended, with principal office at PPA Building, Bonifacio Drive, South Harbor, Port Area, Manila, represented herein by its duly authorized General Manager, **JAY DANIEL R. SANTIAGO**, and hereinafter referred to as "PPA";

- and -

_____, duly organized and existing in accordance with Philippine laws, with office and business address at _____, represented in this act by its _____, as evidenced by _____, a copy of which is hereto attached and made an integral part hereof as Annex "A", and hereinafter referred to as "CONTRACTOR."

WITNESSETH:

WHEREAS, in accordance with Republic Act No. 9184 and its 2016 Implementing Rules and Regulations (IRR), PPA advertised and posted on the PPA website and PhilGEPS, as well as on its bulletin board, an Invitation to Bid for the _____;

WHEREAS, in response to the said advertisement _____ bidders submitted their respective bids for the foregoing project;

WHEREAS, after the opening of bids on _____ and the conduct of bid evaluation and post-qualification, the bid submitted by the CONTRACTOR at its unit and lump sum prices set forth in its proposal was found to be the _____ Bid in the amount of _____ PESOS (), Philippine Currency;

WHEREAS, pursuant to Head Office BAC Resolution No. _____ Series of _____, award of contract was made to the CONTRACTOR in a Notice of Award dated _____, in the amount of _____ PESOS (), after submission of the required documents within the prescribed period and compliance to the conditions stipulated in the IRR;

WHEREAS, the CONTRACTOR duly accepted the award by signing its Conforme on the said Notice of Award;

NOW, THEREFORE, for and in consideration of the foregoing premises and the mutual stipulations herein contained, PPA and the CONTRACTOR have agreed, as follows:

1. In this Contract, words and expressions shall have the same meanings as are respectively assigned to them in the attached Contract Documents.
2. The following documents shall form part of this Contract:
 - A. Bid Documents consisting of the following:
 - A.1 Invitation to Bid;
 - A.2 Instructions to Bidders;
 - A.3 Bid Data Sheet;
 - A.4 General and Special Conditions of Contract;
 - A.5 Specifications
 - A.6 Drawings/Plans;
 - A.7 Addenda and/or Supplemental/Bid Bulletins, if any;
 - B. Technical and Financial Proposals;
 - C. Performance Security;
 - D. Notice of Award of Contract with the Contractor's Conforme thereto; and
 - E. Other contract documents that may be required by existing laws and PPA, such as:
 - E.1 Construction Schedule and S-Curve;
 - E.2 Manpower Schedule;
 - E.3 Construction Methods;
 - E.4 Equipment Utilization Schedule;
 - E.5 Construction Safety and Health Program approved by the DOLE;
 - E.6 Pert/CPM
 - E.7 Duly Approved Program of Works and Cost Estimates;
 - E.8 Certificate of Availability of Funds;
 - E.9 Abstract of Bids; and
 - E.10 Resolution of Award
3. In consideration of the payments to be made by PPA, the CONTRACTOR commits to complete the Works and remedy any defects therein in conformity with the provisions of this Contract and Contract Documents.
4. In consideration of the execution and completion of the Works and remedying any defects therein, PPA commits to pay the Contract Price or such other sum as may become payable under the provisions of this Contract and Contract Documents.

5. This Contract shall become effective after the same shall have been signed by the Parties hereof.

IN WITNESS WHEREOF, the Parties have hereunto signed this Contract on the date and place first hereinabove written.

PHILIPPINE PORTS AUTHORITY

TIN No. _____

By:

JAY DANIEL R. SANTIAGO

General Manager

WITNESSES:

ACKNOWLEDGMENT