

PROJECT FEATURE

PROJECT TITLE	:	CONSTRUCTION OF R.C. PIER	
LOCATION	:	Port of Ubay, Bohol	
SCOPE OF WORK	:	A. DEMOLITION AND REMOVAL WORKS 1 Demolition & disposal of existing RORO ramp deck (99 sq.m.) 2 Cutting & disposal of existing R.C. Pile up to sea-bed elevation (1 no.) 3 Chipping of existing R.C. Curb (32 l.m.) B. CONSTRUCTION OF PIER APPROACH 1 Supply & placing of 3,500 psi concrete for retaining wall & tie-beam (105 cu.m.) 2 Supply & installation of steel reinforcement for the R.C. Curb(5,912 kg.) 3 Supply & installation of core rocks (185 cu.m.) 4 Supply & installation of armor rocks (150 cu.m.) 5 Supply & installation of geotextile fabric (78 sq.m.) 6 Supply & placing of fill materials (118 cu.m.) 7 Supply & placing of aggregate base course (11 cu.m.) 8 Construction of portland cement concrete pavement (58 sq.m.) C. CONSTRUCTION OF R.C. PIER 2 Supply, deliver & drive R.C. square piles (6,711 l.m.) 3 Supply & placing of concrete for the superstructure (888 cu.m.) 4 Supply & installation of steel reinforcement for the superstructure (140,172 kg.) 5 Supply & installation of rubber dock fenders (10 set) 6 Supply & installation of mooring bollards (17 set)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	97,084,311.28
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	109,705,271.75
PROJECT DURATION	:	420 Calendar days	

