PROJECT FEATURE

PROJECT TITLE	:	**LAZI PORT EXPANSION PROJECT**
LOCATION	:	**Port of Lazi, Siquijor**

A. REMOVAL, DISPOSAL AND EXCAVATION WORKS

1 Chipping and disposal existing rc curb (108 l.m.)
2 Removal of existing lamp post including turn over to the authority (for re-installation) (4 set)
3 Excavation of existing fill materials (8 cu.m.)

B. CONSTRUCTION OF PORT OPERATIONAL AREA

1 Supply and placing of 3,500 psi concrete (334 cu.m.)
2 Supply and installation of reinforcing steel bars (10,535 kg.)
3 Supply and placing of gravel bedding (1 cu.m.)
4 Supply and placing of 50 to 100 kg./pc. rocks (2,922 cu.m.)
5 Supply and placing of 1,000 kg./ pc. rocks (2,315 cu.m.)
6 Supply and installation of geotextile fabric (1,198 sq.m.)
7 Supply and placing of fill materials (3,322 cu.m.)
8 Supply and placing of aggregate base course (303 cu.m.)
9 Construction of PCC Pavement (300mm thickness) including dowel bars and construction joints (1,516 sq.m.)
10 Re-installation of removed lamp post including provision of necessary anchor bolts and other incidentals (3 set)
11 Supply deliver and install Port Lighting System including accessories (1 lot)

C. REIMBURSABLE ITEMS

1 Secure approval of environmental compliance certificate (ECC) including application, clearance and other necessary documentary requirements (1 lot)

APPROVED BUDGET FOR THE CONTRACT	:	**Php**	**58,319,332.79**
SOURCES OF FUNDING	:	**PPA Corporate Fund**	
TOTAL PROJECT COST	:	**Php**	**65,900,846.05**
PROJECT DURATION	:	**300 Calendar Days**	