

PROJECT FEATURE

PROJECT TITLE : **CONST. OF BACK-UP AREA & PORT OPERATIONS BUILDING**

LOCATION : **Port of Mauban, Quezon**

SCOPE OF WORK : **A. CONST. OF BACK-UP AREA & WIDENING OF ROCK CAUSEWAY**

- 1 Chipping of existing R.C. Curb (186 l.m.)
- 2 Supply and placing of 3,500 psi concrete (173 cu.m.)
- 3 Supply and installation of steel reinforcement (9,206 kg.)
- 4 Supply and placing of 50-3000 kg/pc. Rocks (9,138 cu.m.)
- 5 Installation of geotextile fabric (1,450 sq.m.)
- 6 Supply and placing of fill materials (12,899 cu.m.)
- 7 Construction of 300mm thk. PCC pavement (3,761 sq.m.)

B. CONST. OF PORT OPERATIONS BUILDING

- 1 Supply and driving of 400 x 400mm PSC foundation piles (840 l.m.)
- 2 Construction of 1-storey Port Operations Building
(625 sq.m., 250 pax)
- 3 Construction of Pumphouse (12.24 sq.m.)
- 4 Construction of R.C. Ductbank, handhole & pedestal (33 cu.m.)
- 5 Supply, delivery, installation of gang chairs (1 lot)

APPROVED BUDGET FOR THE CONTRACT : **Php** **136,670,234.17**

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php** **154,437,364.61**

PROJECT DURATION : **450 Calendar Days**