PROJECT FEATURE

PROJECT TITLE	:	**REPAIR OF PAVEMENT AT PORT OPERATIONAL AREA**
LOCATION	:	**Port of Calapan, Oriental Mindoro**
SCOPE OF WORK	:	**1.00 General Expenses** 1.01 Mobilization, demobilization and cleaning 1.02 Provide Construction Safety and Health Program in execution of the project 1.03 Temporary Site Office and Staffhouse **2.00 Removal and Demolition Works** 2.01 Removal/Dismantling and Turnover of Paving blocks including Demolition and Disposal of CTB as shown in the plan **3.00 Earthworks** 3.01 Drainage Excavation and Subgrade Leveling 3.02 Supply, Spread and Compact Gravel Base Course Materials for Marshalling Area Pavement and Gravel Bedding for Drainage **4.00 Drainage System** 4.01 Supply and Installation of Reinforcing Steel Bars 4.02 Supply, Install, and Removal of Formworks 4.03 Supply and Place 3500 psi Concrete **5.00 Portland Cement Concrete Pavement** 5.01 Supply and Installation of Reinforcing Steel Bars 5.02 Supply and Place 3500 PSI Portland Cement Concrete Pavement including Asphalt Joint Sealer
APPROVED BUDGET FOR THE CONTRACT	:	**Php 64,403,925.99**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 72,776,436.37**
PROJECT DURATION	:	**240 Calendar Days**