DREDGING AND SURVEY DEPARTMENT
HEAD OFFICE, MANILA

BAGONG PILIPINAS

PHILIPPINE PORTS AUTHORITY

Form No. I

PROJECT FEATURE

PROJECT TITLE	:	**Proposed Dredging of Ubay Port, Bohol**
LOCATION	:	**Ubay, Province of Bohol**
MAJOR SCOPE OF WORK	:	**1) Dredging along berths, approaches and maneuvering areas of Ubay Port to a designed depth of 5.00 meter below Mean Lower Low Water (MLLW).** **2) Total Volume to be Dredged : 340,000 cu.m.** **(wherein 94,000 cu.m. at Area I, from Sta. 0-020 to Sta. 0+260 comprising of highly dense/compacted clayeth mud/sand and hard strata at certain depth** **246,000 cu.m. at Area II, Sta. 0+260 to Sta. 1+820 of soft to medium clayish sand/mud, silt, sand and pebbles with possible compacted soil)** **3) Disposal of dredged soil materials 15.00 kms away from the project site**
APPROVED BUDGET FOR THE CONTRACT	:	**P 194,990,193.96**
TOTAL PROJECT COST	:	**P 199,864,948.81**
PROJECT (DREDGING) UNIT COST	:	**P 765.46 per cubic meter @ Area I** **P 475.80 per cubic meter @ Area II** (Unit Cost for Dredging Works Only)
PROJECT DURATION	:	**458 calendar days** (inclusive of Sundays / Holidays and unworkable condition)