## PROJECT FEATURE

| | | |
|---|---|---|
| **PROJECT TITLE** | : | **CONSTRUCTION OF OFFSHORE WIND (OSW) PORT PHASE I** |
| **LOCATION** | : | **Brgy. Pambuhan, Mercedes, Camarines Norte, Bicol** |

: **A TEMPORARY ACCESS ROAD**

1. Excavation of existing seabed including backfilling works
2. Supply & placing of rock and gravel
3. Supply & placing of 1000 kg. armour rocks
4. Supply and placing of gravel bedding
5. Supply & placing of 4,500 psi concrete
6. Supply & installation of reinforcing steel bars
7. Supply & installation of geotextile fabric

**B PORT OPERATIONAL AREA/BERTHING/STAGING AREA**

1. Excavation of existing seabed including disposal and backfilling works
2. Supply, deliver to site & driving of z-type steel sheet piles, 600mm steel pipe sheet pile, 600mm steel pipe pile and anchor pile including pile connectors and application of polyurethane coating
3. Supply and installation of dowel bars for z type steel sheet piles
4. Supply,fabricate and install band tip for the steel pipe piles
5. Supply and installation of steel waling and splice plate for steel sheet piles
6. Extraction of clogged materials inside the SPP including the supply and placing of sand filler, steel cage bar and concrete filler
7. Cutting of newly steel piles
8. Supply & placing of 4,500 psi concrete
9. Supply & installation of reinforcing steel bars
10. Supply and placing of gravel bedding and leveling concrete
11. Supply & placing of 50 to 100 kg. rocks
12. Supply & installation of Tie-rods
13. Supply & installation of geotextile fabric
14. Supply & placing of rock and gravel fill
15. Supply & placing of crushed stones
16. Construction of lateral drainage
17. Construction of catch drain manhole
18. Supply & installation of mooring and fendering system
19. Supply and install port lighting system, generator set and distribution transformer

| | | | |
|---|---|---|---|
| **APPROVED BUDGET FOR THE CONTRACT** | : | **Php** | **2,273,924,087.93** |
| **SOURCES OF FUNDING** | : | | **PPA Corporate Fund** |
| **TOTAL PROJECT COST** | : | **Php** | **2,399,899,482.40** |
| **PROJECT DURATION** | : | **540** | **Calendar Days** |