

PROJECT FEATURE

PROJECT TITLE	:	ALEGRIA PORT DEVELOPMENT PROJECT
LOCATION	:	Port of Alegria, Buruanga, Aklan
SCOPE OF WORK	:	<p>A. CONSTRUCTION OF BACK-UP AREA Area = 3,073 sq.m.</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of RC sheet piles & corner piles (242 l.m.)2 Supply and install tie-rods (4 sets)3 Supply & placing of gravel bedding (11 cu.m.)4 Supply & placing of concrete (292 cu.m.)5 Supply & installation of steel reinforcement (28,781 kg.)6 Supply & placing of rocks (3,689 cu.m.)7 Supply & placing of geotextile fabric (2,202 sq.m.)8 Supply & placing of fill materials (12,569 u.m.)9 Supply & placing of aggregate base course (613 cu.m.)10 Construction of Portland Cement Concrete Pavement (3,067 sq.m.)11 Supply & installation of lateral drainage cover (79 sets)12 Supply & installation of catch drain manhole cover (7 sets)13 Supply & laying of reinforced concrete pipe (1 l.m.) <p>B. RC PLATFORM 1 Area = 1,308 sq.m.</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of 400mm x 400mm PSC piles (3,112 l.m.)2 Supply & placing of concrete (452 cu.m.)3 Supply & installation of steel reinforcement (86,375 kg.) <p>C. RC PLATFORM 2 Area = 1,224 sq.m.</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of 400mm x 400mm PSC piles (2,932 l.m.)2 Supply & placing of concrete (421 cu.m.)3 Supply & installation of steel reinforcement (78,772 kg.) <p>D. RC PIER Area = 1,344 sq.m.</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of 400mm x 400mm PSC piles (4,443 l.m.)2 Supply & placing of concrete (490 cu.m.)3 Supply & installation of steel reinforcement (89,274 kg.)4 Supply and install mooring bollard including furnishing new accessories for removed mooring bollard for re-installation (7 set)5 Supply and install rubber dock fender including furnishing new accessories for removed RDF for re-installation (7 set) <p>E. RORO RAMP, 2 UNITS Area = 198 sq.m.</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of 400mm x 400mm PSC piles (972 l.m.)2 Supply & placing of concrete (144 cu.m.)3 Supply & installation of steel reinforcement (31,546 kg.)4 Supply and install mooring bollard (4 set)5 Supply and install rubber dock fender (6 set) <p>F. BREASTING DOLPHIN</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of 400mm x 400mm PSC piles (632 l.m.)2 Supply & placing of concrete (41 cu.m.)3 Supply & installation of steel reinforcement (1,106 kg.)4 Supply and install mooring bollard (2 set)5 Supply and install rubber dock fender (4 set) <p>G. PORT LIGHTING SYSTEM</p> <ol style="list-style-type: none">1 Supply, deliver and install 10.0 m.ht single bar floodlight steel tapered lamp post in hot-dipped galvanized (5 sets) with 2-units 100 watt LED floodlight fixture each
APPROVED BUDGET FOR THE CONTRACT	:	Php 217,619,862.09
SOURCES OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	Php 245,910,444.16
PROJECT DURATION	:	540 Calendar days