

PROJECT FEATURE

PROJECT TITLE : **CONSTRUCTION OF COASTAL ACCESS ROAD**

LOCATION : **Port of Calapan, Calapan City, Oriental Mindoro**

SCOPE OF WORK **A. CONSTRUCTION OF COASTAL ACCESS ROAD**

(Area = 6,728.98 sq.m.)

1. Construction of rock bulkhead (24,689 cu.m.), fill materials(17,673 cu.m), reinforced concrete for RCDG, rc curb and perimeter fence column (589 cu.m. of concrete and 46,540 kg of reinforcing steel bars of various sizes)
2. Supply and drive of 0.40m x 0.40m PSC piles (180 l.m.) including chipping and cutting of newly driven piles up to required elevation (12 pcs)
3. Construction of CHB wall (438 sq.m.), including plastering (1,094 sq.m.), and various materials for cyclone wire mesh fence (700 sq.m.)
4. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 6,244 sq.m.) including aggregate base course (1,222 cu.m.)
5. Supply and install of geotextile fabric (7,514 sq.m.)

B. PORT LIGHTING SYSTEM

1. Supply and installation of single arm steel tapered lamp post, 10.00m ht., hot dipped galvanized (27 sets) with 100 watt LED roadway fixture (27 sets)

APPROVED BUDGET FOR THE CONTRACT : P **140,960,141.68**
Sources of Funding : **PPA Corporate Fund**

TOTAL PROJECT COST : P **150,827,351.60**

PROJECT DURATION : **450 C.D.**

4