

**PROJECT FEATURE**

**PROJECT TITLE** : **CONST. OF CAUSEWAY, BACK-UP AREA & R.C. WHARF WITH RORO RAMPS**

**LOCATION** : **Port of San Fernando, El Nido, Palawan**

**SCOPE OF WORK** : **A. BACK-UP AREA WITH RORO RAMP, CAUSEWAY & ACCESS ROAD**

- 1 Supply & driving of PSC Sheet pile & R.C. Corner piles (2,124 l.m.)
- 2 Supply & placing of concrete (867 cu.m.)
- 3 Supply & installation of steel reinforcement (46,335 kg.)
- 4 Excavation of existing sea-bed (5,247 cu.m.)
- 5 Supply & installation of core & armor rocks ( 12,345 cu.m.)
- 6 Supply & installation of tie-rods of various sizes (37 sets)
- 7 Supply & installation of geotextile fabric (3,878 sq.m.)
- 8 Supply & placing of fill materials (9,725 cu.m.)
- 9 Supply & placing of aggregate base course (653 cu.m.)
- 10 Construction of Portland Cement Concrete Pavement (3,297 sq.m.)
- 11 Supply, delivery & installation of lamp post and solar street light (7 sets)
- 12 Supply & installation of Rubber dock fenders (9 sets)
- 13 Supply & installation of mooring bollard (4 sets)

**B. R.C. WHARF WITH RORO RAMP**

- 1 Supply & driving of PSC square piles (3,770 l.m.)
- 2 Supply & placing of concrete for R.C. Wharf (512 cu.m.)
- 3 Supply & installation of steel reinforcement for R.C. Wharf (83,636 kg.)
- 4 Supply & installation of construction joint (100 l.m.)
- 5 Supply & installation of Rubber dock fenders (23 sets)
- 6 Supply & installation of mooring bollard (10 sets)

**APPROVED BUDGET FOR THE CONTRACT** : **Php 191,843,947.15**

**SOURCES OF FUNDING** : **PPA Corporate Fund**

**TOTAL PROJECT COST** : **Php 216,783,660.28**

**PROJECT DURATION** : **450 Calendar days**