

LFP BHL NO. 041-2019

Form No. 1

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of the Ports of Tagbilaran, Loay and Clarin, Bohol

LOCATION : Province of Bohol

MAJOR SCOPE OF WORK :

- 1) Dredging along berths, maneuvering areas and entrance channel of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:
7.00m. @ the New Ro-Ro Ramp of Tagbilaran Port
4.00 m along Loboc River of Loay Port
5.00 m for Clarin Port
- 2) Total Volume to be Dredged : 200,000 cu.m.
(16,000 cu.m., 105,500 cu.m. and 78,500 cu.m. for Tagbilaran, Loay and Clarin Ports, respectively)
of soft to highly dense (compacted) clayish sand/mud, silt, sand, pebbles and possible hard materials.
- 3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 103,592,137.39

TOTAL PROJECT COST : P 106,181,940.82

PROJECT (DREDGING) UNIT COST : P 495.03 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-imbursable Items)

PROJECT DURATION : 286 calendar days
(inclusive of Sundays / Holidays and unworkable condition)