



Form 1. Project Feature

(Doc Ref Code: PM: APC: DSD: DW: 01)

LFP PNG NO. 040-2019

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Iloilo River Wharf

LOCATION : Iloilo City, Panay Island

MAJOR SCOPE OF WORK :

- 1) Dredging from the Mouth of Iloilo River up to Aduana Street to a designed depth of 5.00m and progressive depth of 4.50m to 5.00m below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged : 525,000 cu.m. (239,500 cu.m. and 285,500 cu.m. for Grab and Trailing Suction Type Dredger assigned dredging area, respectively) of soft to highly dense (compacted) soil/sand, clayish mud, silt, debris and possible hard materials
- 3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 236,462,412.55

TOTAL PROJECT COST : P 242,373,972.86

PROJECT (DREDGING) UNIT COST : P 434.95 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 443 calendar days
(inclusive of Sundays / Holidays and unworkable condition)