

PROJECT FEATURE

PROJECT TITLE	:	BASIAO PORT DEVELOPMENT PROJECT	
LOCATION	:	Port of Basiao, Ivisan, Capiz	
SCOPE OF WORK	:	A. BACK-UP AREA & CAUSEWAY <ol style="list-style-type: none"> 1 Demolition & disposal of existing concrete pavement (1,016 sq.m.) 2 Subgrade preparation & scrapping of existing fill materials (203 sq.m.) 3 Demolition & disposal portion of existing RC Curb (46 l.m.) 4 Supply & placing of 3,500 psi concrete (329 cu.m.) 5 Supply & installation of steel reinforcement (14,140 kg.) 6 Supply & placing of 1000 kg/pc rocks (4,052 cu.m.) 7 Supply & placing of 50 to 100 kg/pc rocks (4,005 cu.m.) 8 Supply & placing of Geotextile fabric filter (1,682 sq.m.) 9 Supply & placing of fill materials (1,816 cu.m.) 10 Supply & placing of aggregate base course (269 cu.m.) 11 Construction of Portland Cement Concrete Pavement (1,411 sq.m) 12 Supply & installation of Mooring cleats (54 sets) 13 Supply & installation of Mooring bollards (2 sets) B. RORO RAMP <ol style="list-style-type: none"> 1 Supply & driving of PSC square piles (432 l.m.) 2 Supply & placing of 3,500 psi concrete (77 cu.m.) 3 Supply & installation of steel reinforcement (19,649 kg.) 4 Supply & installation of Rubber dock fenders (4 sets) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	61,647,135.01
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	69,661,262.56
PROJECT DURATION	:	300 Calendar Days	

9

8

8