

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Calatagan Port

LOCATION : Calatagan, Batangas

MAJOR SCOPE OF WORK :

- 1) Dredging along the berths and maneuvering areas of the Port to a designed depth of 4.50 meter below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged :
205,000.00 cu.m. of highly dense (compacted) clayish sand /mud, sand, pebbles and possible hard materials
- 3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 127,949,300.63

TOTAL PROJECT COST : P 132,427,526.15

PROJECT (DREDGING) UNIT COST : P 600.00 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 360 calendar days
(inclusive of Sundays / Holidays and unworkable condition)