

## PROJECT FEATURE

**PROJECT TITLE** : **ORMOC PORT EXPANSION PROJECT**

**LOCATION** : **Port of Ormoc, Leyte**

- SCOPE OF WORK**
- A. DEMOLITION, REMOVAL & EXCAVATION WORKS**
    - 1 Excavation & backfilling works (49 cu.m.)
    - 2 Removal of existing bollards & fenders (9 sets)
    - 3 Demolition & disposal of existing R.C. Deck (642 sq.m.)
    - 4 Cutting & disposal of existing R.C. Piles (84 no.)
    - 5 Chipping & disposal of existing R.C. Curb (80 l.m.)
    - 6 Demolition & disposal of existing concrete pavement (96 sq.m.)
  
  - B. BACK-UP AREA**
    - 1 Supply & driving of PSC Sheet Piles & R.C. Corner piles (4,914 l.m.)
    - 2 Supply & placing of 3,500 psi concrete (776 cu.m.)
    - 3 Supply & installation of reinforcing steel bars (62,446 kg.)
    - 4 Supply & installation of geotextile fabric (3,322 sq.m.)
    - 5 Supply & placing of 50 to 1,000 kg. rocks (7,839 cu.m.)
    - 6 Supply & installation of Tie-rods of various sizes (92 sets)
    - 7 Supply & placing of fill materials (55,132 cu.m.)
    - 8 Supply & placing of base course (2,666 cu.m.)
    - 9 Supply & installation of concrete paving blocks (8,651 sq.m.)
    - 10 Construction of CHB perimeter fence (80 l.m.)
    - 11 Restoration of demolished concrete pavement (96 sq.m.)
    - 12 Portlighting system (lot)
    - 13 Drainage system (lot)
  
  - C. PLATFORM AND RORO RAMP**
    - 1 Supply & driving of PSC square piles (6,283 l.m.)
    - 2 Splicing of PSC square piles (171 no.)
    - 3 Supply & placing of 3,500 psi. concrete (720 cu.m.)
    - 4 Supply & installation of reinforcing steel bar (133,953)
    - 5 Supply & installation of construction joints (268 l.m.)
    - 6 Supply & installation of Rubber dock fenders (26 sets)
    - 7 Supply & installation of mooring bollards (15 sets)

<b>APPROVED BUDGET FOR THE CONTRACT</b>	:	Php	262,809,794.53
<b>SOURCES OF FUNDING</b>	:	PPA Corporate Fund	
<b>TOTAL PROJECT COST</b>	:	Php	286,462,676.03
<b>PROJECT DURATION</b>	:	540 Calendar Days	