PROJECT FEATURE

PROJECT TITLE	:	**NASIPIT PORT EXPANSION AND REHABILITATION PROJECT**
LOCATION	:	**Port of Nasipit, Agusan del Norte**
SCOPE OF WORK	:	**A. REMOVAL, EXCAVATION AND DISPOSAL WORKS** 1 Removal and disposal of existing PCCP & pavement of RC platform 2 Excavation and backfilling of existing fill materials 3 Removal and disposal of existing RC wharf 4 Cutting and disposal of existing piles up to required elevation 5 Removal and disposal of existing retaining wall 6 Removal of existing bollard and fender 7 Subgrade preparation for rehabilitation and upgrading of pavement 8 Removal and re-installation of existing trench grate for lateral drainage 9 Removal of existing rock bulkhead 10 Chipping and disposal portion of existing lateral drainage 11 Removal and re-installation of existing trench grate for upgraded catch drain manhole 12 Chipping and disposal portion of existing catch drain manhole to be upgraded up to required elevation 13 Chipping and disposal existing RC curb flush to required elevation and smoothen with mortar 14 Removal and relocation of existing high mast tower 15 Removal and relocation of existing solar lamp post **B. REHABILITATION OF BERTH, CONSTRUCTION OF WHARF ON FILL AND ADDITIONAL PORT OPERATIONAL AREA** 1 Supply & delivery of Steel Pipe Piles including protective coating 2 Handling, pitching & driving of Steel Pipe piles 3 Supply & installation of steel waling and splice plate 4 Extraction of clogged materials inside the SPP 5 Supply & placing of sand filler for SPP 6 Supply & placing of concrete filler for SPP 7 Supply & installation of reinforcing steel cage for SPP 8 Supply & placing of 3,500 psi concrete 9 Supply & installation of reinforcing steel bars 10 Supply & placing of gravel bedding 11 Supply & placing of 50 to 1,000 kg. rocks 12 Supply & installation of Tie-rod 13 Supply & installation of geotextile fabric 14 Supply & placing of fill materials 15 Supply & placing of aggregate base course 16 Construction of reinforced concrete pavement 17 Construction of PCC pavement 18 Supply, delivery & install wires and other port lighting accessories 19 Construct lateral drainage for new construction, upgrading of elevation & reconstruction including trench grate, epoxy bonding compound, outfall drainage and other accessories 20 Construct drain manhole for new construction and upgrading of elevation including trench grate, epoxy bonding compound and other accessories 21 Construction of security fence including painting and accessories 22 Supply & installation of rubber dock fenders 23 Supply & installation of mooring bollards
APPROVED BUDGET FOR THE CONTRACT	:	**Php 530,972,253.18**
SOURCES OF FUNDING	:	**PPA Corporate Fund**
TOTAL PROJECT COST	:	**Php 599,998,646.10**
PROJECT DURATION	:	**660 Calendar Days**