

PROJECT FEATURE

PROJECT TITLE	: EXCAVATION, EXTENSION OF BREAKWATER & CONSTRUCTION OF BOAT MOORING FACILITIES	
LOCATION	: Port of Sabtang, Batanes	
SCOPE OF WORK	A. CONSTRUCTION OF BOAT MOORING FACILITIES AND DEEPENING OF BERTHING AREA <ol style="list-style-type: none"> 1 Supply and install/place geotextile filter (11 sq.m.), gravel bedding (9 cu.m.) and selected fill (26 cu.m.) 2 Supply and place 3,500 psi concrete for superstructure (192 cu.m.) including steel reinforcements (13,053 kg.) 3 Supply and install mooring cleats (7 sets) 4 Supply and install concrete blocks (16 blocks) and sacked concrete (1 cu.m.) 5 Construct portland cement concrete pavement (32 sq.m.) including construction joint (6 Lm.) 6 Excavation of existing seabed up to design elevation of -3.0 m (8,451 cu.m.) B. EXTENSION OF BREAKWATER AND CONSTRUCTION OF BOLLARD BLOCK <ol style="list-style-type: none"> 1 Removal of existing structures (158 cu.m.) 2 Excavation of existing seabed up to design elevation of -2.7 m (1,211 cu.m.) 3 Supply and place 150-200 kg. rocks (437 cu.m.) 4 Supply and place 3,500 psi concrete for superstructure (328 cu.m.) including steel reinforcements (5,210 kg.) 5 Supply and install concrete blocks of various sizes (216 blocks) 6 Supply and install mooring cleat (1 set) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php 40,149,179.38
SOURCES OF FUNDING	:	General Appropriations Act (GAA)
TOTAL PROJECT COST	:	Php 44,967,080.91
PROJECT DURATION	:	240 Calendar Days