

PROJECT FEATURE

PROJECT TITLE	:	CONSTRUCTION OF CAUSEWAY WITH STAIRLANDINGS
LOCATION	:	Port of Tajujura, Basco, Batanes
SCOPE OF WORK	:	A. CONSTRUCTION OF CAUSEWAY WITH STAIRLANDINGS (Length = 60 l.m.) 1. Excavate portion of existing seabed up to required Elevation (37 cu.m.) 2. Supply and place 20-30 kg/pc rocks (96 cu.m.), 50-100 kg/pc rock (225 cu.m.), geotextile fabric (372 sq.m.), selected fill (197 cu.m.) and aggregate base course (29 cu.m.) 3. Supply and place 3,500psi concrete for superstructure (424 cu.m.) including reinforcing steel bars (34,801 kg.) 4. Construct 230mm thk. Portland Cement Concrete Pavement (143 sq.m.) and construction joint (12 l.m.) 5. Supply and install mooring cleats including accessories (4 sets)
APPROVED BUDGET FOR THE CONTRACT	:	P 19,146,146.33
Sources of Funding	:	GAA
TOTAL PROJECT COST	:	P 19,911,992.19
PROJECT DURATION	:	150 DAYS

Handwritten signature/initials

Handwritten signature/initials