



## PROJECT FEATURE

**PROJECT TITLE** : Proposed Dredging of Iloilo Clustered Project II  
Ports of San Jose de Buenavista, Antique and  
Culasi, Roxas City

**LOCATION** : Province of Antique and Capiz, Panay Island

**MAJOR SCOPE OF WORK** :

- 1) Dredging along berths and maneuvering areas of the  
Ports to a designed depth below Mean Lower Low  
Water (MLLW) as follows:  
6.00 m. for San Jose de Buenavista Port  
6.50 m for Culasi Port
- 2) Total Volume to be Dredged : 155,000 cu.m.  
(60,000 cu.m. and 95,000 cu.m., respectively) of  
soft to highly dense (compacted) clayish sand/mud,  
silt, sand, pebbles and possible hard materials.
- 3) Disposal of dredged soil materials 16.00 kms  
away from the project site

**APPROVED BUDGET FOR THE CONTRACT** : P 80,182,389.77

**TOTAL PROJECT COST** : P 82,186,949.51

**PROJECT (DREDGING) UNIT COST** : P 495.58 per cubic meter  
(Dredging Works Only, excluding General Expenses  
and Re-Imbursable Items)

**PROJECT DURATION** : 229 calendar days  
(inclusive of Sundays / Holidays and unworkable  
condition)