



LFP ELS No. 011 - 2020

Form No. 1

## PROJECT FEATURE

**PROJECT TITLE** : Proposed Dredging of Calbayog Port

**LOCATION** : Calbayog City, Samar

**MAJOR SCOPE OF WORK** :

- 1) Dredging along berths, maneuvering area and approach channel of the port to a designed depth of 6.10 meters (20 ft.) below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged : 277,000 cu.m. of soft to medium dense clayish soil, mud, silt and sand
- 3) Disposal of dredged soil materials 15.00 kms away from the project site

**APPROVED BUDGET FOR THE CONTRACT** : P 133,903,804.82

**TOTAL PROJECT COST** : P 137,251,399.94

**PROJECT (DREDGING) UNIT COST** : P 462.02 per cubic meter  
(Dredging Works Only, excluding General Expenses and Re-imbursable Items)

**PROJECT DURATION** : 374 calendar days  
(inclusive of Sundays / Holidays and unworkable condition)