



LFP NLZ No. 010-2020

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Salomague Port

LOCATION : Cabugao, Ilocos Sur

MAJOR SCOPE OF WORK :

- 1) Dredging/Deepening of berths and maneuvering areas up to designed depth of 10.00 and 6.00 meters below Mean Lower Low Water (MLLW)
- 2) Total Volume to be dredged :
92,500.00 cu.m. of medium to highly dense (compacted) clayish soil, mud, sand, pebbles and hard materials such as gravelbars, rock and corals
- 3) Disposal of dredged/excavated soil materials 15.00 km. away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 60,558,576.61

TOTAL PROJECT COST : P 62,072,541.03

PROJECT (DREDGING) UNIT COST : P 593.19 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-imbursable Items)

PROJECT DURATION : 172 calendar days
(inclusive of Sundays / Holidays and unworkable condition)