



LFP MRQ NO. 008 -2020

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of San Andres Port, Quezon

LOCATION : San Andres, Quezon Province

MAJOR SCOPE OF WORK :

- 1) Dredging along berths and maneuvering areas of the Port and Navigational Channel to a designed depth below Mean Lower Low Water (MLLW) as follows:
6.50 m. for Berthing and Maneuvering Areas (120m x 60m)
6.50 m. for Navigational Channel (250m x 60m)
- 2) Total Volume to be Dredged : 43,500 cu.m. for berths and maneuvering area and for Navigational Channel of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials.
- 3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : 24,255,232.75 ✓

TOTAL PROJECT COST : 25,104,165.89

PROJECT (DREDGING) UNIT COST : P 487.46 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 180 calendar days
(inclusive of Sundays / Holidays and unworkable condition)