

## BILL OF QUANTITIES

### REPAIR/REPLACEMENT OF DAMAGED PERIMETER FENCE / LIGHTING SYSTEM AND CLEARING OF DEBRIS AT PORT OF DINGALAN, AURORA

*Name of Project*

#### ITEM # 1 General Expenses

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
1.01	Mobilization and Demobilization	lot	1.00		
1.02	Provide Construction Safety & Health Program	lot	1.00		
SUB-TOTAL FOR ITEM NO. 1					

#### ITEM # 2 Clearing / Removal Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
2.01	Clearing and Removal of debris caused by Typhoon Ulysses at Port of Dingalan	cu.m	241.95		
SUB-TOTAL FOR ITEM NO. 2					

---

Authorized Signature

## BILL OF QUANTITIES

### REPAIR/REPLACEMENT OF DAMAGED PERIMETER FENCE / LIGHTING SYSTEM AND CLEARING OF DEBRIS AT PORT OF DINGALAN, AURORA

*Name of Project*

#### ITEM # 3 Repair of Port Perimeter Fence

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
3.01	Supply and install steel wire mesh fence	li.m	116.00		
	<b>SUB-TOTAL FOR ITEM NO. 3</b>				

#### ITEM # 4 Painting Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
4.01	Application of paint to the steel wire mesh fence	sqm	300.35		
	<b>SUB-TOTAL FOR ITEM NO. 4</b>				

---

Authorized Signature

## BILL OF QUANTITIES

### REPAIR/REPLACEMENT OF DAMAGED PERIMETER FENCE / LIGHTING SYSTEM AND CLEARING OF DEBRIS AT PORT OF DINGALAN, AURORA

*Name of Project*

#### ITEM # 5 Electrical Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
5.01	Supply and install integrated solar powered lightings 80W 11200 lm daylight with 3 years warranty including arms (1.5m) and accessories	units	4.00		
5.02	Dismantle, Pull-out and transport the existing generator set from Port of Dingalan, Aurora	unit	1.00		
SUB-TOTAL FOR ITEM NO. 5					

TOTAL
-------

---

Authorized Signature