# BILL OF QUANTITIES

## MAINTENANCE OF BUSTED PORT LIGHTING SYSTEM AT PORT OF LAMAO, LIMAY, BATAAN (MPF - BNA - 04 - 24)

| NO. (1) | DESCRIPTION OF WORK (2) | UNIT (3) | QTY. (4) | UNIT PRICE (5) | AMOUNT (Pesos) (4) x (5) |
|---|---|---|---|---|---|
| **BILL NO.** | **1 GENERAL EXPENSES** | | | | |
| 1.01 | Mobilization and Demobilization / Clean Up | lot | 1.00 | | |
| 1.02 | Provision of Construction Safety and Health Program | lot | 1.00 | | |
| | **TOTAL FOR BILL NO. 1** | | | | |
| **BILL NO.** | **2 ELECTRICAL WORKS** | | | | |
| 2.01 | Removal of busted lighting fixtures, cable wires and circuit breakers including chipping works | lot | 1.00 | | |
| 2.02 | Supply and installation of electrical wires, circuit breakers with weatherproof housing, PVC pipes and accessories | lot | 1.00 | | |
| 2.03 | Supply and installation of LED Flood Light 230V, 300W, Daylight, 120Lm/W including accessories | unit | 13.00 | | |
| | **TOTAL FOR BILL NO. 2** | | | | |

Name of Bidder/Authorized Representative
(Signatory's Legal Capacity)