BILL OF QUANTITIES

REPAIR/REPAINTING OF OLD TOO BUILDING AT PAG-ASA STREET, LAMAO, LIMAY, BATAAN

Name of Project

ITEM # 1 General Expenses

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
1.01	Mobilization and Demobilization Cost	lot	1.00		
1.02	Provide environmental safety and health program	days	75.00		
	TOTAL FOR ITEM NO. 1				

ITEM # 2 Roofing Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
2.01	Removal of damaged roof including accessories	sq.m.	209.03		
2.02	Installation of Ga.26 pre-painted corrugated roofing	sq.m.	209.03		
	TOTAL FOR ITEM NO. 2				

Authorized Signature

BILL OF QUANTITIES

REPAIR/REPAINTING OF OLD TOO BUILDING AT PAG-ASA STREET, LAMAO, LIMAY, BATAAN

Name of Project

ITEM # 3 Carpentry Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
3.01	Removal of damaged ceiling board, nailers, double wall partition and vertical & horizontal studs	sq.m.	106.13		
3.01	Installation of ceiling board nailers, double wall partition and vertical & horizontal studs	sq.m.	106.13		
	TOTAL FOR ITEM NO. 3				

BILL # 4 Concreting and Demolition Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
4.01	Demolition of existing concrete Column and construct of additional column/footing	lot	1.00		
4.02	Concreting of flooring 3,500psi including formworks	cu.m.	6.78		
	TOTAL FOR ITEM NO. 4				

Authorized Signature

BILL OF QUANTITIES

REPAIR/REPAINTING OF OLD TOO BUILDING AT PAG-ASA STREET, LAMAO, LIMAY, BATAAN

Name of Project

ITEM # 5 Doors and Windows

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
5.01	Doors and Windows Supply and installation of doors w/ jambs and steel window grills	lot	1.00		
	TOTAL FOR ITEM NO. 5				

BILL # 6 Perimeter Fence and Gates

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
6.01	Removal of damaged cyclone fence & gate	lin.m.	21.98		
6.02	Fabrication and installation of steel fence and gates	lin.m.	19.70		
6.03	Plastering of existing CHB Fence	lin.m.	44.49		
	TOTAL FOR ITEM NO. 6				

Authorized Signature

BILL OF QUANTITIES

REPAIR/REPAINTING OF OLD TOO BUILDING AT PAG-ASA STREET, LAMAO, LIMAY, BATAAN

Name of Project

ITEM # 7 Kitchen Cabinet

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
7.01	Removal of existing damaged hanging cabinet and fabrication and installation of cabinets	set	3.00		
	TOTAL FOR ITEM NO. 7				

BILL # 8 Painting Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
8.01	Painting and repainting works	sq.m.	2,506.57		
	TOTAL FOR ITEM NO. 8				

Authorized Signature