

BILL OF QUANTITIES

REPAIR OF DRAINAGE SYSTEM AND TEMPORARY FENCE AT PORT OF CASIGURAN, AURORA

Name of Project

ITEM # 1 GENERAL EXPENSES

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
1.01	Mobilization and Demobilization	lot	1.00		
1.02	Provide Construction Safety & Health Program	lot	1.00		
	SUB-TOTAL FOR ITEM NO. 1				

ITEM # 2 CLEARING/REMOVAL/EXCAVATION WORKS

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
2.01	Clearing and Removal Works of debris for the repair of creek and temporary fence including excavation	cu.m	104.00		
	SUB-TOTAL FOR ITEM NO. 2				

ITEM # 3 REPAIR OF DRAINAGE SYSTEM & TEMPORARY FENCE

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
3.01	Supply, fabricate and install reinforcing steel bar for retaining wall and temporary fence.	kgs	2177.60		
3.02	Supply and place 3500psi concrete for retaining wall	cu.m	15.00		
3.03	Supply and place selected fill along the retaining wall	cu.m	90.60		
3.04	Supply and place 20-50kg core rocks for retaining wall	cu.m	55.00		
3.05	Supply, fabricate and installation of movable fence and steel fence along the retaining wall	l.m	74.46		
3.06	Painting of fences including retaining wall at Port of Casiguran	sqm	274.14		
	SUB-TOTAL FOR ITEM NO. 3				

GRAND TOTAL

Authorized Signature