

BILL OF QUANTITIES

Repair of RC Wharf, RoRo Ramp and Port Lighting System at Port of Casiguran, Aurora

Name of Project

ITEM # 1 General Expenses

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
1.01	Mobilization and Demobilization	lot	1.00		
1.02	Provide Construction Safety & Health Program	lot	1.00		
SUB-TOTAL FOR ITEM NO. 1					

ITEM # 2 Removal and Disposal Works

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
2.01	Removal of existing paving blocks	sqm	1261.00		
2.02	Removal of existing mooring and fendering system	lot	1.00		
2.03	Demolition of RC Deck/Slab Beams, Pile Caps, Curtain Wall, RC Curb, RoRo Ramp and Shear Key including disposal	cu.m	329.05		
SUB-TOTAL FOR ITEM NO. 2					

Authorized Signature

BILL OF QUANTITIES

Repair of RC Wharf, RoRo Ramp and Port Lighting System at Port of Casiguran, Aurora

Name of Project

ITEM # 3 Repair of RC Wharf, RoRo Ramp and Lighting System

ITEM NO.	DESCRIPTION OF WORK	UNIT	QUANTITY	UNIT PRICE (PESOS)	AMOUNT (PESOS)
3.01	Supply and place leveling sand cushion in uneven portion	cu.m	64.00		
3.02	Re-install interlocking paving blocks	sqm	1276.00		
3.03	Supply and install reinforcing bars for RC Deck/Slab Beams, Pile Caps, Curtain Wall, RC Curb, RoRo Ramp and Shear Key	kgs	76141.09		
3.04	Supply and install 3500psi concrete for RC Deck/Slab Beams, Pile Caps, Curtain Wall, RC Curb, RoRo Ramp, Shear Key and Lighting Post pedestal including formworks	cu.m	360.11		
3.05	Supply, deliver and install to site Rubber Dock Fender (V Type 500mm x 1500mm) including accessories	set	10.00		
3.06	Supply, deliver and install to site Mooring Bollard (50T) with complete accessories	set	5.00		
3.07	Supply and install 100mm x 100mm x10mm hot dipped galvanized angle bar for construction joint	li.m	271.00		
3.08	Replacement of damaged Integrated Solar Street Lights 100W, 24Vdc 14000Lm 6500k including sinlge arm lighting post and accessories	unit	4.00		
3.09	Replacement of damaged Integrated Solar Street Lights 100W, 24Vdc 14000Lm 6500k including accessories	unit	6.00		
3.10	Painting/Repainting of Curtain Wall, RC Curb, RoRo Rammp and Mooring Bollard including marking of Mooring Bollard	sqm	227.00		
SUB-TOTAL FOR ITEM NO. 3					
GRAND TOTAL					

Authorized Signature