ANNEX “A”

EQUIPMENT REQUIREMENT
(Owned or Leased)

Name of Project **:** _____
_____

Item No.	DESCRIPTION	No. of Unit	Owned / Leased
1	Concrete Mixer One (1) Bagger	2	Owned
2	Concrete Vibrator, 3.5hp	2	Owned
3	Jack Hammer with Compressor (350cfm)	1	Owned
4	Dumptruck (6cu yd)	1	Owned
5	Backhoe (0.52cu.m. 90hp)	1	Owned
6	Vibratory Plate Compactor (300 - 400mm width)	1	Owned
7	Payloader (1.06 cu.m., 93hp)	1	Owned
8	Road Grader (125hp)	1	Owned
9	Road Roller (10T/130hp vibratory)	1	Owned
10	Water Truck (16000l)	1	Owned
11	Bar Cutter (25mm bar dia Max)	1	Owned
12	Bar Bender (25mm bar dia Max)	1	Owned
13	Concrete Cutter (5hp)	1	Owned
14	Crawler Crane (36T minimum)	1	Owned/Leased
15	Tugboat (500hp)	1	Owned/Leased

PHOMINDORO

ANNEX “B”

CONSTRUCTION, SAFETY AND HEALTH REQUIREMENT

Name of Project **:** _____

_____

The Contractor shall implement the construction safety and health program in accordance in with the applicable provision of Occupational Safety and Health Standard (OSHS) of the Department of Labor and Employment (DOLE).

A. EQUIPMENT / MATERIALS:

1. Safety Gears (Hard Hats, Safety Shoes, Belts, Gloves, etc.) : 1.0 Lot
2. Safety Devices (barricades, warning signs & other appropriate tools) : 1.0 Lot
3. Medical and First Aide System : 180 CD
4. Medical and First Aid System : 180 CD

B. LABOR

5. 1 - Safety Engineer / Officer : 180 CD

NOTE:

The Contractor shall provide the following minimum construction safety and health requirements.

PMO MINDORO

ANNEX “C”

MANPOWER SCHEDULE

Name of Project **:** _____

_____

MANPOWER (Minimum)	**Contract Duration (Calendar Days)**									
	M O N T H L Y									
Project Manager										
Project Engineer										
Materials Engineer										
Construction Safety and Health Officer										
General Foreman										
Specify Other Applicable Positions, etc.										

(Authorized Signing Official)

Signature

PMO MINDORO

ANNEX “D”

EQUIPMENT UTILIZATION SCHEDULE

Name of Project**:** _____

_____

Item No.	DESCRIPTION	No. of Units	Owned / Leased	Contract Duration (Calendar Days)					
				M O N T H L Y					
1.									
2.									
3.									
4.									

PNO MINDORO

(Authorized Signing Official)

Signature

ANNEX “E”

CONSTRUCTION METHODOLOGY

Name of Project**:** _____

_____

Minimum Scope of Construction Methodology

A. Rock Causeway with Stairlanding Rock Causeway with Stairlanding

1. Removal of Portion of the Existing Seawall.
2. Excavation of Existing Seabed Along Retaining Wall and Stairlandings
3. Supply and Place 1,000 kg. Armour Rocks
4. Supply and Place 50-100 kg. Core Rocks
5. Supply and Install Geotextile Fabric
6. Supply, Spread and Compact Selected Fill
7. Supply and Place 3500 psi Concrete for Retaining Wall, RC Curb, Stairlanding and Mooring Blocks
8. Supply and Place Steel Reinforcement for Retaining Wall, RC Curb, Stairlanding and Mooring Blocks
9. Supply, Spread and Compact Gravel Base Course
10. Supply and Install Mooring Cleat including Accessories

(Authorized Signing Official)

Note:

The narrative construction method will guide and familiarize the contractor and the PPA on how the project shall be carried out in accordance with the highest standard of workmanship.

The construction method shall be consistent with the Bar Chart/S-Curve Schedule, Equipment Schedule and Manpower Schedule.

PPO MINDORO

GENERAL INFORMATION

1. Name of Applicant-Firm/Contractor _____

2. Type of Firm:

   (___) Single Proprietor

   (___) Corporation

   (___) Partnership

   (___) Cooperative

   (___) Joint Venture

3. Business Address/Tel. and Fax Numbers/E-mail Address

	Main Office	Branch Office (if any)
Address:	_____	_____
	_____	_____
	_____	_____
	_____	_____

Tel No/: _____

Cel No : _____

_____

Fax No : _____

E-mail : _____

4. Taxpayer Identification Number : _____
   of the Company

5. Government Issued ID and Number of Authorized Representative: _____
   _____

_____
Signature over Printed Name of Authorized Signing Official

_____
Designation

DATE OF OPENING OF BIDS: _____

PMO MINDORO