

BILL OF QUANTITIES

Name of Project : _____

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QUANTITY (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4 X 5)
Bill No. 1.00	GENERAL EXPENSES				
Bill No. 1.01	Mobilization, Demobilization and Clean-up	Lumpsum	1		P
	TOTAL AMOUNT FOR BILL NO. 1.00				P

Name/Signature of Authorized Signing Official

BILL OF QUANTITIES

Name of Project : _____

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QUANTITY (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4 X 5)
Bill No. 2.00	REPAIR OF R.C. PIER				
Bill No. 2.01	Demolish and Dispose Existing Pile Cap, Curtain Wall, Fender Block, Beam, Slab and Curb including Turnover of Items	Lumpsum	1.00		P
Bill No. 2.02	Supply and Place 3500 psi Concrete for Superstructure	Cubic Meter	381.62		
Bill No. 2.03	Supply and Place Reinforcing Steel Bars for Concreting Works	Kilograms	63,352.98		
Bill No. 2.04	Remove and Reinstall Mooring Bollard (35T, T-Head) including accessories	Sets	12.00		
Bill No. 2.05	Supply and Install Rubber Dock Fender, V-400H x 2000mmL including Accessories	Sets	24.00		
Bill No. 2.06	Supply and Install Hot-Dipped Galvanized Angle Bar 100mm x 100mm x 10mm for Construction Joint including Chipping-off Portion of Existing R.C. Pier for Dowel Bars	Linear Meter	9.00		
	TOTAL AMOUNT FOR BILL NO. 2.00				P

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QUANTITY (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4 X 5)
Bill No. 3.00	RORO RAMP 2				
Bill No. 3.01	Demolish and Dispose Existing R.C. Deck including Removal/Turnover of Rubber Dock Fender	Lumpsum	1.00		P
Bill No. 3.02	Supply and Place 3500 psi Concrete for Superstructure	Cubic Meter	21.15		
Bill No. 3.03	Supply and Place Reinforcing Steel Bars for Concreting Works	Kilograms	3,182.01		
Bill No. 3.04	Supply and Install Rubber Dock Fender, V-400H x 2000mmL including Accessories	Sets	3.00		
Bill No. 3.05	Fabrication & Installation of Steel I-Beam & Mild Steel Plate for Top and Corner Ramp Protection	Kilograms	6,401.60		
	TOTAL AMOUNT FOR BILL NO. 3.00				P

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QUANTITY (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4 X 5)
Bill No. 4.00	RORO RAMP 3				
Bill No. 4.01	Demolish and Dispose Existing R.C. Deck including Removal/Turnover of Rubber Dock Fender	Lumpsum	1.00		P
Bill No. 4.02	Supply and Place 3500 psi Concrete for Superstructure	Cubic Meter	21.15		
Bill No. 4.03	Supply and Place Reinforcing Steel Bars for Concreting Works	Kilograms	3,182.01		
Bill No. 4.04	Supply and Install Rubber Dock Fender, V-400H x 2000mmL including Accessories	Sets	3.00		
Bill No. 4.05	Fabrication & Installation of Steel I-Beam & Mild Steel Plate for Top and Corner Ramp Protection	Kilograms	6,401.60		
	TOTAL AMOUNT FOR BILL NO. 4.00				P

SUMMARY OF BILL OF QUANTITIES

Name of Project : _____

BILL NO.	DESCRIPTION OF WORKS	AMOUNT
TOTAL BID PRICE _____		
		Php
Amount in Words		

Name/Signature of Authorized Signing Official