FINANCIAL PROPOSAL

PHILIPPINE PORTS AUTHORITY

PORT MANAGEMENT OFFICE-PALAWAN

Quezon Street, Barangay Bagong Pag-Asa, Port Area,
Puerto Princesa City

FINANCIAL BID

FOR

_____

(Name of Contract to be Bid)

Submitted by

_____

(Name and Address of Bidder)

FINANCIAL BID

FOR

_____

(Name of Contract to be Bid)

TABLE OF CONTENTS

Page No.

1. **Bid Proposal**
2. **Bid Prices in Bill of Quantities**
3. **Detailed Estimates**
4. **Summary Sheet Indicating the Unit Prices of Construction Materials, Labor Rates, and Equipment Rental Rates Used in Coming up with the Bid**
5. **Cash Flow by Quarter and Payment Schedule**

BID FORM

Date :_____
ITB No. : NRP-PLW-01-2019

The Chairperson
PMO-PALAWAN-BAC (Bids and Award Committee)
PMO - Palawan
Philippine Ports Authority
Admin. Building, Barangay Bagong Pag-Asa
Port Area, Puerto Princesa City

We the undersigned, declare that:

(a) We have examined and have no reservation to the Bidding Documents, including Addenda, for the Contract **NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R.C. WHARF AND PLATFORM DECK/SLAB AND JACKETING OF DILAPIDATED PILE CAPS, PORT OF PUERTO PRINCESA, PALAWAN;**

(b) We offer to execute the Works for this Contract in accordance with the Bid and Bid Data Sheet, General and Special Conditions of Contract accompanying this Bid;

The total price of our Bid, excluding any discounts offered below is:

BILL NO.	DESCRIPTION	TOTAL AMOUNT
I	GENERAL EXPENSES	₱
II	CONCRETE PAVEMENT AND DRAINAGE CANAL	
III	R.C. WHARF AND PLATFORM	
IV	PILE CAP JACKETING	
TOTAL ESTIMATED AMOUNT (including VAT)		₱

The discounts offered and the methodology for their application are: **[insert information]**

(c) Our Bid shall be valid for a period of 120 days from the date fixed for the Bid submission deadline in accordance with the Bidding Documents, and it shall remain binding upon us and may be accepted at any time before the expiration of that period;

(d) If our Bid is accepted, we commit to obtain the Performance Security in the amount of percent of the Contract for the due performance of the Contract;

(e) Our firm, including any subcontractors or suppliers for any part of the Contract, have nationalities from the following eligible countries: [insert information]

(f) We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;

(g) Our firm, its affiliates, or subsidiaries, including any subcontractors or suppliers for any part of theContract, has not been declared ineligible by the Funding Source;

(h) We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and

(i) We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.

(j) We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do so, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the **NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R.C. WHARF AND PLATFORM DECK/SLAB AND JACKETING OF DILAPIDATED PILE CAPS, PORT OF PUERTO PRINCESA, PALAWAN.**

(k) We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be ground for the rejection of our bid.

Name: _____

In the capacity of: _____

Signed: _____

Duly authorized to sign the Bid for and on behalf of: _____

Date: _____

APPROVED BUDGET FOR THE CONTRACT

NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R. C. WHARF PLATFORM DECK / SLAB AND JACKETING OF DILAPIDATED PILE CAPS PORT OF PUERTO PRINCESA, PALAWAN

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) X (5)
BILL NO. I	GENERAL EXPENSES	L.S.	1.00	₱	₱
BILL NO. II	CONCRETE PAVEMENT AND DRAINAGE COVER	LOT	1.00	₱	₱
BILL NO. III	R. C. WHARF AND PLATFORM	SQ.M.	954.19	₱	₱
BILL NO. IV	PILE CAP JACKETING	UNIT	71.00	₱	₱
				APPROVED BUDGET FOR THE CONTRACT	₱

BILL OF QUANTITIES

NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R. C. WHARF PLATFORM DECK / SLAB AND JACKETING OF DILAPIDATED PILE CAPS

PORT OF PUERTO PRINCESA, PALAWAN

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) X (5)
BILL NO. I	GENERAL EXPENSES				
1.01	Provide Safety and Health Program in the Execution of the Project	MO.	8.00	₱	₱
				TOTAL FOR BILL NO. I	₱

BILL OF QUANTITIES

NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R. C. WHARF PLATFORM DECK / SLAB AND JACKETING OF DILAPIDATED PILE CAPS

PORT OF PUERTO PRINCESA, PALAWAN

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) X (5)
BILL NO. II	CONCRETE PAVEMENT AND DRAINAGE COVER				
2.01	Demolition of Damaged Concrete Pavement	SQ.M.	1,910.74	₱	₱
2.02	Disposal of Concrete Debris and Unsuitable Materials	CU.M.	1,050.91		
2.03	Supply, Spread and Compact Aggregate Sub-Base Course (150mm thick)	CU.M.	286.61		
2.04	Supply, Spread and Compact Aggregate Base Course (150mm thick)	CU.M.	286.61		
2.05	Supply and Place Mix Concrete for Pavement (3,500 psi @ 7 days)	CU.M.	477.61		
2.06	Concrete Cutting, Curing and Protection	SQ.M.	1,910.74		
2.07	Repair of Damaged Drainage Cover	L.M.	31.60		
				TOTAL FOR BILL NO. II	₱

BILL OF QUANTITIES

NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R. C. WHARF PLATFORM DECK / SLAB AND JACKETING OF DILAPIDATED PILE CAPS

PORT OF PUERTO PRINCESA, PALAWAN

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) X (5)
BILL NO. III	R. C. WHARF AND PLATFORM				
3.01	Demolition of Damaged RC Wharf and Platform Deck/Slab	CU.M.	249.57	₱	₱
3.02	Disposal of R.C. Wharf and Platform Concrete Debris	CU.M.	249.57		
3.03	Supply and Install Reinforcing Bars for Item 3.04	KGS.	34,898.17		
3.04	Supply and Place 3,500 psi Concrete for RC Wharf and Platform Deck/Slab	CU.M.	249.57		
3.05	Supply & Install Galvanized Angle Bar 100mm x 100mm x 10mm thick	L.M.	128.30		
				TOTAL FOR BILL NO. III	₱

BILL OF QUANTITIES

NRP-PLW-01-2019 - REPAIR OF DAMAGED CONCRETE PAVEMENT, DRAINAGE COVER, R. C. WHARF PLATFORM DECK / SLAB AND JACKETING OF DILAPIDATED PILE CAPS

PORT OF PUERTO PRINCESA, PALAWAN

NO. (1)	DESCRIPTION OF WORKS (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) X (5)
BILL NO. IV	PILE CAP JACKETING				
4.01	Removal of Spalled Concrete and Cleaning of Corroded Rebars	LOT	1.00	₱	₱
4.02	Supply and Install Reinforcing Bars	KGS.	3,002.44		
4.03	Supply and Install Formworks	SQ.M.	400.13		
4.04	Supply and Place 4,000psi Concrete with Epoxy Bond	CU.M.	46.32		
				TOTAL FOR BILL NO. IV	₱