SPECIFICATIONS

PROJECT : PROVISION OF MOVABLE COVERED WALK

LOCATION : PORT OF PUERTO PRINCESA, PALAWAN

SCOPE OF WORK :

The work generally includes the furnishing of all labor, materials and equipments required to carry-out the project as shown in the drawings and in conformity with these specifications.

WARNING DEVICES/SIGNAGE/SAFETY

The contractor shall provide warning devices and signage on the worksite, clearly visible, to avoid inconvenience to the port users.

All workers shall wear protective gears or equipment at all times for safety of life purposes.

FABRICATION WORKS/ WELDING WORKS / PAINTING WORKS

1. All materials to be used shall be of standard sizes especially G.I. pipes.
2. All bend shall be smooth if not machine-bents.
3. Bolts and nuts shall be made of stainless steel, Rubber roller caster shall be of heavy-duty type.
4. Fluxes on welded parts shall be properly removed by sanding prior to painting.
5. Surfaces to be painted shall be properly prepared to avoid paint failures. Use specified paint only.
6. Epoxy paint shall be used as primer paint, G.I plain sheets shall be applied with leaching solution.
7. All painting finishes shall be spray-painted.

CLEARING AND CLEAN-UP

The Contractor shall remove all temporary structures erected, excess materials and construction debris within their worksite upon completion of the project.

OTHER CONTRACTOR'S RESPONSIBILITIES

The Contractor shall supply the agency the monthly percentage accomplishment for reporting purposes. He shall submit also an as-built plan of the project, a logbook containing the daily activity report and photographs of the activities with signboards in 4R sizes for billing purposes.