9.2	CHB laying, plastering works and flooring concrete screening	
9.3	Painting works wall and ceiling	
9.4	Ceiling works	
9.5	Electrical works	
9.6	Door and window	
10.0	**EXTENDED WALKWAY**	
10.1	Excavation works, steel works, formworks and concreting works (600mm x 600mm x 150mm) 4 - units footing foundation	
10.2	Welding works of walkway shed. Framing and roofing (5.0 l.m)	
10.3	Walkway concreting with ceramics tiles (16" x 16") 12.0 l.m Volume = 12.0m x 2.0m x 0.10m thk. = 2.4 cu.m	
11.0	**MAINTENANCE OF GUARD HOUSE AND GATE NO. 3**	
11.1	Repainting of guard house and gate no. 3	
11.2	Windows	
12.0	**MAINTENANCE OF PPA LOGO**	
12.1	Replacement of PPA logo at PTB	
13.0	**DEMOLISH AND DISPOSE OF COVERED WALKWAY**	
13.1	Roofing removal of covered walkway at southern portion of wharf 82.0 l.m	
13.2	Cutting of steel column, truss and grills of covered walkway at southern portion of wharf 82.0 l.m.	
13.3	Chipping works of column pedestal, concrete curb and removal of paving blocks of covered walkway at southern portion of wharf 82.0 l.m.	
13.4	Disposal of demolished materials	
B	**CONSTRUCTION OF POWERHOUSE FOR 250 kVA GENERATOR**	
1.0	**EXCAVATION WORKS**	
1.1	Removal of paving blocks, excavation of pedestal column concrete base pad.	
2.0	**REINFORCING BAR WORK**	
2.1	Supply / Install Steel Reinforcing bar for pedestal and concrete flatform (Including 3" Ø Sched. 40 G.I. pipe steel column)	
3.0	**CONCRETING WORKS**	
3.1	Supply and place 3000 psi concrete for Column pedestal and concrete pad flatform	
4.0	**WELDING WORKS**	
4.1	Welding works of Wall framing, roof truss and doors	
5.0	**ROOFING WORKS**	
5.1	Install color roofing rib type, facia board, roof flushing and insolation.	
6.0	**PAINTING WORKS**	
6.1	Painting works of steel wall framing	
TOTAL ESTIMATED COST (Including VAT)		
AMOUNT IN WORDS:		