Bill of Quantities

Name of Project: CLUSTER PROJECT: MAINTENANCE OF VARIOUS PORT PHYSICAL FACILITIES (A190008) AND CONSTRUCTION OF POWERHOUSE FOR 250 kVA GENERATOR (C190039); PORT OF MASBATE CITY

(CONTRACT NO. MBT 2001)

ITEM NO.	DESCRIPTION OF WORKS	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
A	**MAINTENANCE OF VARIOUS PORT FACILITIES**				
1	**GENERAL EXPENSES**				
1.1	Mobilization, Demobilization and Clearing	lot	1.00		
2	**DEMOLITION WORKS**				
2.1	Demolition of damaged ceiling 3-unit toilet , false beam, door jamb 3-unit, chipping works for the urinal and lavatory new pipe line, removal of paving blocks and chipping of concrete pavement for foundation of overhead water tank	lot	1.00		
3	**MAINTENANCE AND REPAIR OF PASSENGER TERMINAL BUILDING**				
3.1	Repair of 3-unit toilets (Senior Citizen/PWD, Male and Female) Interior ceiling, Ceiling false beam and exterior ceiling at PTB.	lot	1.00		
3.2	Repainting works for the interior ceiling PTB ground floor	sq.m	327.83		
3.3	Repainting works for the exterior ceiling ground floor PTB	sq.m	76.48		
3.4	Repainting works for the interior wall ground floor PTB	sq.m	202.32		
3.5	Repainting works for exterior wall ground floor and 2nd floor PTB	sq.m	610.22		
3.6	Replacement and installation of 3- unit (2.10 x 0.75) wooden door jamb at toilet	lot	1.00		
3.7	Supply/install office fixtures	lot	1.00		
3.8	Sanitary works for urinal and lavatory new piping line	lot	1.00		
3.9	Plastering and restoration works for the urinal and lavatory new piping line of toilet	lot	1.00		
3.10	Chipping works of existing concrete pavement and removal of paving blocks. Additional septic vault (5.0m x 2.0m H= 1.50m)	sq.m	10.00		
3.10a	Excavation works (5.0m x 2.0m H=1.20m) Additional septic vault	cu.m	15.00		
3.10b	Steelworks fabrication and installation of additional septic vault. (5.0m x 2.0m H = 1.50m)	lot	1.00		
3.10c	Formworks and installation of additional septic vault. (5.0m x 2.0m H= 1.20)	sq.m	48.00		
3.10d	Concreting works of additional septic vault. (5.0m x 2.0m H= 1.20)	cu.m	2.06		
3.10e	Backfilling works of additional septic vault	lot	1.00		
3.11	Siphoning and declogging of septic tank (Every quarterly) Clear-up clogged and remove the garbage inside the septic vault	lot	1.00		
4	**MAINTENANCE OF MOORING SYSTEM**				
4.1	Painting of mooring 35-T, T-Heads old wharf (12 sets), (11- sets) at New Warf (4-set) at New wharf , (8-sets) at extension wharf, total = 35 units Mooring cleat (10-units) 905kgs 1990 and 2 -	sq.m	94.00		
5	**REPAIR AND MAINTENANCE R.C. CURB**				
5.1	Chipping works of R.C. Curb	l.m	20.00		
5.2	Supply / Install Steel Reinforcement Bars	lot	1.00		
5.3	Formworks fabrication and installation	lot	1.00		
5.4	Concreting works	cu.m	1.80		