5.5	Stripping / Removal of forms and disposal of concrete debris	lot	1.00		
5.6	Painting works of R.C. Curb	sq.m	439.99		
6	**MOVABLE STEEL BARRIER**				
6.1	Provision of movable barrier 18- pcs of Length =2.44 x 1.22 and 8- pcs length = 1.22 x 1.22 , 12 - pcs of length = 2.44 x 0.60 and 8- pcs of Length = 0.60 x 1.22	lot	1.00		
7	**PROVISION OF ELEVATED WATER TANK**				
7.1	Welding works of elevated water tank	lot	1.00		
7.2	Rebar and forms fabrication and installation Overhead water tank foundation (Footing 0.50m x 0.50m) (Pedestal 0.20m x 0.20m)	lot	1.00		
7.3	Concreting works (Footing 0.50m x 0.50m) (Pedestal 0.20m x 0.20m)	lot	1.00		
7.4	Plumbing works	lot	1.00		
7.5	Provision of water pump and electrical works	lot	1.00		
8	**MAINTENANCE OF PORT GATE**				
8.1	Welding works of the port Gate , chipping works, plastering and painting (Gate - 1, Gate - 2 and Gate - 3 and Boom Barrier)	lot	1.00		
9	**MAINTENANCE OF COLLECTION BOOTH (GATE - 2)**				
9.1	Welding works / steel framing and roofing's	lot	1.00		
9.2	CHB laying, plastering works and flooring concrete screeding	lot	1.00		
9.3	Painting works wall and ceiling	lot	1.00		
9.4	Ceiling works	lot	1.00		
9.5	Electrical works	lot	1.00		
9.6	Door and window	lot	1.00		
10	**EXTENDED WALKWAY**				
10.1	Excavation works, steel works, formworks and concreting works (600mm x 600mm x 150mm) 4 - units footing foundation	lot	1.00		
10.2	Welding works of walkway shed. Framing and roofing (5.0 l.m)	lot	1.00		
10.3	Walkway concreting with ceramics tiles (16" x 16") 12.0 l.m Volume = 12.0m x 2.0m x 0.10m thk = 2.4 cu.m	lot	1.00		
11	**MAINTENANCE OF GUARD HOUSE AND GATE NO. 3**				
11.1	Repainting of guard house and gate no. 3	lot	1.00		
11.2	Windows	lot	1.00		
12	**MAINTENANCE OF PPA LOGO**				
12.1	Replacement of PPA logo at PTB	lot	1.00		
13	**DEMOLISH AND DISPOSE OF COVERED WALKWAY**				
13.1	Roofing removal of covered walkway at southern portion of wharf 82.0 l.m	lot	1.00		
13.2	Cutting of steel column, truss and grills of covered walkway at southern portion of wharf 82.0 l.m	l.m	82.00		
13.3	Chipping works of column pedestal, concrete curb and removal of paving blocks of covered walkway at southern portion of wharf 82.0 l.m	lot	1.00		
13.4	Disposal of demolished materials	lot	1.00		
B	**CONSTRUCTION OF POWERHOUSE FOR 250 kVA GENERATOR**				
1	**EXCAVATION WORKS**				
1.1	Removal of paving blocks, excavation of pedestal column concrete base pad.	lot	1.00		
2	**REINFORCING BAR WORK**				
2.1	Supply / Install Steel Reinforcing bar for pedestal and concrete flatform (Including 3" Ø Sched. 40 G.I. pipe steel column)	kg	200.00		