Project: **Maintenance of Structured Cabling Local Area Network (MPF-MOC-23-2025)**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	**Maintenance of Structured Cabling Local Area Network**	1.00	LOT		
	Work Description				
	Supply of labor and materials for the maintenance of structured cabling including including termination/fusion, and testing & commissioning				
	Materials				
	37U Data Cabinet w/ Power Distribution (PDU)	1.00	units		
	1U Cable Manager Loop Alloy	9.00	pcs		
	CAT6 Patch Panel 24 Ports	5	pcs		
	Patch Cord - 1meter (company crip)	120	pcs		
	FOC Patch Panel 12 core	4	units		
	SC to SC pigtail	36	pcs		
	SC to LC Pacth Cord - 2meter (Duplex)	14	pcs		
	SC to SC Patch cord - 2meters (Duplex)	14	pcs		
	28-ports with SFP Ports Later3 Gigabit switch manageable	5	units		
	1000-Base SFP Transceiver	4	units		
	1.5KVA UPS [APC or VERTIV]	4	units		
	Access Point (ceiling type)	5	units		
	CAT6 RJ45 Pass through	150	pcs		
	CAT6 UTP Cable (Pure Copper)	3	rolls		
	1"x1m velcro Tape	40	rolls		
	Outdoor NEMA Enclosure 30x20x20cm	2	pcs		
	1-1/2" dia. PVC (orange)	5	lhs.		
	Equipment				
	NONE				
	Manpower				
	1 Installation, Configuration, Testing and Commisioning	1.00	LOT		
	- Includes Termination/Fusion from the Patch Panel (12 Core)				
	- Includes Orientation to IT Personnel upon turn-over				

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM 1. ₱ _____

TOTAL BID AMOUNT : ₱ _____

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER :: _____

SIGNATURE: _____