Project: **Maintenance of Data Room at Bldg 2 [MPF-MOC-24-2025]**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	**Maintenance of Data Room at Bldg 2**	1.00	LOT		

Work Description

Supply of labor, materials and equipment for the installation of wifi access including configuration, testing and commissioning

Materials

-	24 ports PoE Manageable Switch for internet WIFI with (Cloud remote management capabilities, Bandwidth management, Web Portal and Landing page)	12	unit		
-	Wired Internet Access Point 1GB ethernet Port (Ceiling type)	4.00	units		
-	Cable Management 1U rock mounted 24slot	1.00	units		
-	UTP Cable Patch cord Cat6 (Company crimp) 1 meter	15	pcs		
-	Cat6 UTP Cable (Pure Copper)	2	box		
-	Flexible Hose ½	500	l.m.		
-	Plastic Molding, RJ45 Cat6	1	lot		

Equipment

NONE

Manpower

1	- Installation, Configuration, Testing and Commisioning (includes orientation to IT personnel upon turn-over)	1.00	LOT		

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM 1. ₱ _____

TOTAL BID AMOUNT : ₱ _____

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____