Project: **Maintenance of Gate Counter Booths, Port of Cagayan de Oro [MPF-MPC-20-2025]**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	**Replacement of Dilapidated Guardhouse**	5.00	UNITS		
	Work Description				
	Supply of materials, labor and Equipment for the replacement of guardhouse				
	Materials				
1.)	Post/Framing				
	3mm x 100 x 100 Galv. Square Tube	10.00	lhs.		
	3mm x 50 x 75 Galv. Rectangular tubeSquare bar	25.00	lhs		
	2mm x 50 x 100 C Purlins	20.00	lhs		
2)	Floor/Side framing:				
	3mm x 75 x 100 Galv. Rectangular tubeSquare bar	5.00	lhs		
	3mm x 50 x 75 Galv. Rectangular tubeSquare bar	3.00	lhs		
	3mm x 50 x 50 Galv. Square tube	14.00	lhs		
3)	Floor Finish				
	12"x12" Vinyl Tiles	125.00	pcs.		
	Rugby	3.00	gals.		
4}	Roofing works (11.85 sq.m.):				
	0.40MM x 1.133m Corr. Blue Longspan roofing	93.00	l.m.		
	0.40MM thk x 0.4m x 2.4 m ridge roll	25.00	lhs		
	tekscrew 2" (300pcs/box)	3.00	box		
	blind rivets 5/32 (250pcs/box)	5.00	box		
5)	Electrical Lines/fixture				
	100W floodlight with solar panel	15.00	sets		
6)	Others:				
	Sticker Log Signages (Vinyl Print; Waterproof Sticker)	5.00	lot		
	stainless handle	5.00	pc.		
	12mm thk. X 250mm x 250mm steel plates	20.00	pc.		
	8mm dia. Barreled bolt	5.00	set		
	3/4"thk. Marine plywood	10.00	pc.		
	1/2"thk. Hardiflex	15.00	pc.		
	Epoxy primer	10.00	gals.		
	Enamel White	20.00	gals.		
	Flat Latex White	5.00	gals.		
	Semi-Gloss White	10.00	gals.		
	Body filler	10.00	gals.		
	Lacquer Spot Putty	5.00	gals.		
	Consumable				

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Equipment				
1	unit - Boom Truck	5.00	days		
2	unit - Welding Machine	7.00	days		
	Minor Tools				
	Manpower				
	Steel Works				
1	Foreman	25.00	days		
2	Skilled Laborer	25.00	days		
2	Unskilled Laborer	25.00	days		
	Floor finishes				
1	Foreman	7.50	days		
2	Skilled Laborer	7.50	days		
2	Unskilled Laborer	7.50	days		
	Painting Works				
1	Foreman	30.00	days		
4	Skilled Laborer	30.00	days		
2	Unskilled Laborer	30.00	days		
	Roofing Works:				
1	Foreman	4.00	days		
1	Skilled Laborer	4.00	days		
2	Unskilled Laborer	4.00	days		
	Electrical Works				
1	Skilled Laborer	2.50	days		
2	Unskilled Laborer	2.50	days		

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM 1. ₱ _____

TOTAL BID AMOUNT : ₱ _____

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER :: _____

SIGNATURE: _____