Project: **Maintenance of Concrete curbs- Aprons (Baseport and Terminal Ports) (MPF-MOC-04-2025)**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A.	**Mobilization**	1.00	LOT		
	Work Description				
	Mobilization				
	Materials				
	NONE				
	Equipment				
	Mobilization	1.00	lot		
	Manpower				
	NONE				
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM A.		₱
B.	**Provide Construction Safety and Health Program**	1.00	LOT		
	Work Description				
	Provide Construction Safety and Health Program				
	Materials				
	Personal Protective Equipment				
	Hard Hats	13.00	pcs.		
	Gloves	13.00	pcs.		
	Safety Glasses/Googles	13.00	pcs.		
	Long Sleeve T-shirt	13.00	pcs.		
	Safety Shoes	13.00	pairs		
	Safety Vest	13.00	pcs.		
	Safety Devices				
	Barricades	1.00	lot		
	Warning signs (Signages)	1.00	lot		
	Medical First Aid	1.00	lot		
	Equipment				
	NONE				
	Manpower				
	NONE				
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM B.		₱

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	**Demolition and Disposal of Existing Concrete Curbs**	11.14			
	Work Description				
	Supply of Materials, Labor and equipment for the demolition and disposal of existing concrete curbs				
	Materials				
	NONE				
	Equipment				
	1 unit - Aircompressor	5.00	days		
	1 unit - Jackhammer	5.00	days		
	1 unit - Mini-Dumptruck	5.00	days		
	Manpower				
	1 - Foreman	5.00	days		
	2 - Unskilled Laborer	5.00	days		
		ESTIMATED DIRECT COST		₱	
		ESTIMATED INDIRECT COST		₱	
		TOTAL COST OF WORK ITEM 1.		₱	
2.	**Restoration of Concrete Curbs of Port of Cagayan**	7.69	CU.M.		
	Work Description				
	Supply of Materials, Labor and equipment for the restoration concrete curbs				
	Materials				
	Portland Cement	70.00	bags		
	Washed Sand'	4.00	cu.m.		
	3/4 Gravel	8.00	cu.m.		
	1/2" plywood	3.00	shts		
	2"x2"x10" coco lumbe	135.00	bd.ft.		
	12mm deformed bar	74.00	lhs		
	Concrete Epoxy (A & B)	6.00	gals		
	assorted common nails	10.00	kls		
	Equipment				
	1 one bagger mixer	3.00	days		
	Manpower				
	1 - Foreman	3.00	days		
	2 - Skilled Laborer	3.00	days		
	4 - Unskilled Laborer	3.00	days		
		ESTIMATED DIRECT COST		₱	
		ESTIMATED INDIRECT COST		₱	
		TOTAL COST OF WORK ITEM 2.		₱	

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
3.	**Restoration of Concrete Curbs of Port of Balingoan**	3.45	CU.M.		
	Work Description				
	Supply of Materials, Labor and equipment for the restoration concrete curbs				
	Materials				
	Portland Cement	33.00	bags		
	Washed Sand'	2.00	cu.m.		
	3/4 Gravel	4.00	cu.m.		
	1/2" plywood	1.00	shts		
	2"x2"x10" coco lumbe	60.00	bd.ft.		
	12mm deformed bar	34.00	lhs		
	Concrete Epoxy (A & B)	2.00	gals		
	assorted common nails	2.00	kls		
	Equipment				
	1 one bagger mixer	1.50	days		
	Manpower				
	1 - Foreman	1.50	days		
	2 - Skilled Laborer	1.50	days		
	4 - Unskilled Laborer	1.50	days		
			ESTIMATED DIRECT COST	₱	
			ESTIMATED INDIRECT COST	₱	
			TOTAL COST OF WORK ITEM 3.	₱	
4.	**Repainting of concrete curbs of the Port of Cagayan**	903.25	SQ.M.		
	Work Description				
	Supply of Materials, Labor and tools for the repainting of pedestrian lanes and curbs				
	Materials				
	Concrete Epoxy Primer White	43.00	gals		
	Epoxy Reducer	13.00	gals		
	7" Paint Roller w/ Tray	10.00	pcs.		
	Reflectorized Traffic Paint Yellow	16.00	pcs.		
	Reflectorized Traffic Paint Black	16.00	gals		
	Reflectorized Traffic Paint White	59.00	gals		
	Baby Roller Cotton w/ tray	10.00	pcs.		
	2" Paint Brush	10.00	pcs.		
	3" Paint Brush	10.00	pcs.		
	8" dia. Waste Pad	10.00	kgs.		
	Paint Thinner	13.00	gals		
	Equipment				
	NONE				
	Manpower				
	1 - Foreman	33.00	days		
	2 - Skilled Laborer	33.00	days		
	2 - Unskilled Laborer	33.00	days		
			ESTIMATED DIRECT COST	₱	
			ESTIMATED INDIRECT COST	₱	
			TOTAL COST OF WORK ITEM 5.	₱	

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
5.0	**Repainting of concrete curbs of the Port of Balingoan**	193.25	SQ.M.		
	Work Description				
	Supply of Materials, Labor and tools for the repainting of pedestrian lanes and curbs				
	Materials				
	Concrete Epoxy Primer White	10.00	gals		
	Epoxy Reducer	3.00	gals		
	7" Paint Roller w/ Tray	8.00	pcs.		
	Reflectorized Traffic Paint Yellow	10.00	pcs.		
	Reflectorized Traffic Paint Black	10.00	gals		
	Baby Roller Cotton w/ tray	8.00	pcs.		
	2" Paint Brush	8.00	pcs.		
	3" Paint Brush	8.00	pcs.		
	8" dia. Waste Pad	9.00	kgs.		
	Paint Thinner	4.00	gals		
	Equipment				
	NONE				
	Manpower				
	1 - Foreman	9.00	days		
	1 - Skilled Laborer	9.00	days		
	1 - Unskilled Laborer	9.00	days		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 5.		₱
6.0	**Repainting of concrete curbs of the Port of Jasaan**	96.60	SQ.M.		
	Work Description				
	Supply of Materials, Labor and tools for the repainting of pedestrian lanes and curbs				
	Materials				
	Concrete Epoxy Primer White	5.00	gals		
	Epoxy Reducer	2.00	gals		
	7" Paint Roller w/ Tray	4.00	pcs.		
	Reflectorized Traffic Paint Yellow	5.00	pcs.		
	Reflectorized Traffic Paint Black	5.00	gals		
	Baby Roller Cotton w/ tray	4.00	pcs.		
	2" Paint Brush	4.00	pcs.		
	3" Paint Brush	4.00	pcs.		
	8" dia. Waste Pad	2.00	kgs.		
	Paint Thinner	2.00	gals		
	Equipment				
	NONE				

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Manpower				
	1 - Foreman	5.00	days		
	2 - Skilled Laborer	5.00	days		
	2 - Unskilled Laborer	5.00	days		
				ESTIMATED DIRECT COST	₱
				ESTIMATED INDIRECT COST	₱
				TOTAL COST OF WORK ITEM 6.	₱

TOTAL BID AMOUNT : ₱

BID AMOUNT IN WORDS :

NAME OF BIDDER ::

SIGNATURE: