Project: **Maintenance of Sobs and Other Greeneries, Baseport and Terminal Ports [MPF-MOC-05-2025]**
Location: Port of Misamis Oriental/Cagayan de Oro City

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Greeneries for PMO Building 2 Ground, Baseport**				
1.1	**Supply and Delivery of Materials, Including Labor for Landscaping, Area Cleaning and Preparation**	326.40	SQ.M.		
	Work Description				
	Supply and Delivery of Materials, Including Labor for Landscaping, Area Cleaning and Preparation				
	Materials				
	Garden Soil	12	cu.m.		
	Peeble Stones, White	50	bag		
	Peeble Stones, Orange	10	bag		
	Crushed Stones	15	bag		
	Boulder Stones	20	bag		
	Weed Blocker	20	roll		
	Bermuda Grass (5"x5")	9,000	pc.		
	Equipment				
	1 unit - Elf/Truck	5.00	days		
	Manpower				
	1 - Foreman	14.00	days		
	2 - Skilled Worker	14.00	days		
	2 - Non Skilled Worker	14.00	days		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 1.1		₱
1.2	**Supply and Delivery, Placing of Ornamental Plants**	1.00	LOT		
	Work Description				
	Supply and Delivery, Placing of Ornamental Plants				
	Materials				
	Topiary, Spiral, Big	8.00	pc.		
	Topiary, Jar	4.00	pc.		
	Topiary, Round, Big	7.00	pc.		
	Topiary, Round, Medium	15.00	pc.		
	Plant, Direct sunlight, Assorted	100.00	pc.		
	Plant, Shade, Big leaf	6.00	pc.		
	Plant, Shade, Medium leaf	8.00	pc.		
	Bougainvilla	2.00	pc.		
	Equipment				
	1 unit - Elf/Truck	4.00	days		
	Manpower				
	1 - Foreman	7.00	days		
	2 - Skilled Worker	7.00	days		
	2 - Non Skilled Worker	7.00	days		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 1.2				₱
1.3	**Supply, Delivery, and Install Water Sprinkler System, Including Trenching for Water Line**	1.00	LOT		
	Work Description				
	Supply, Delivery, and Install Water Sprinkler System, Including Trenching for Water Line				
	Materials				
	Pipe, Polyethylene, 3/4"Ø x 100mL	3.00	roll		
	Tee Socket, P.E., 3/4"Ø	50.00	pc.		
	Sprikler Head	50.00	pc.		
	Tapelon Tape	11.00	roll		
	Cement	4.00	bag		
	Sand	8.00	bag		
	Gravel	6.00	bag		
	Equipment				
	1 unit - Chipping Gun	4.00	days		
	1 unit - Concrete Cutting Machine	4.00	days		
	Manpower				
	1 - Foreman	3.00	days		
	2 - Skilled Worker	3.00	days		
	2 - Non Skilled Worker	3.00	days		
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 1.3				₱
2.0	**Greeneries for Port Manager's Quarter Ground, Baseport**				
2.1	**Supply and Delivery of Materials, Including Labor for Landscaping, Area Cleaning and Preparation**	187.50	SQ.M.		
	Work Description				
	Supply and Delivery of Materials, Including Labor for Landscaping, Area Cleaning and Preparation				
	Materials				
	Cement Pots	10.00	pc.		
	Peeble Stones, White	50.00	bag		
	Peeble Stones, orange	50.00	bag		
	Gravel	8.00	cu.m		
	Equipment				
	1 unit - Elf/Truck	3.00	days		
	Manpower				
	1 - Foreman	8.00	days		
	2 - Skilled Worker	8.00	days		
	2 - Non Skilled Worker	8.00	days		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 2.1		₱
2.2	**Supply and Delivery, Placing of Ornamental Plants**	1.00	LOT		
	Work Description				
	Supply and Delivery, Placing of Ornamental Plants				
	Materials				
	Arrica Palm	20.00	pcs.		
	Foxtail Pam	10.00	pcs.		
	Assylum	100.00	pcs.		
	Shade Plants	30.00	pcs.		
	Equipment				
	1 unit - Elf/Truck	4.00	days		
	Manpower				
	1 - Foreman	6.00	days		
	2 - Skilled Worker	6.00	days		
	2 - Non Skilled Worker	6.00	days		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 2.2		₱
2.3	**Supply and Delivery, Placing of Potted Palmera Trees, 6 feet high**	28.00	PCS.		
	Work Description				
	Supply and Delivery, Placing of Potted Palmera Trees, 6 feet high				
	Materials				
	Palmera Tree, Potted, 5 feet high	28.00	pcs.		
	Equipment				
	1 unit - Elf/Truck	3.00	days		
	Manpower				
	1 - Foreman	1.00	day		
	2 - Non Skilled Worker	1.00	day		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 2.3		₱
3.0	**Greeneries for Port of Balingoan, Misamis Oriental**				
3.1	**Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs**	21.00	PCS.		
	Work Description				
	Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs				
	Materials				
	Plants, Indoor, Potted, 50cm.Dia X 60cm. High	21.00	pcs.		
	Big leaf, Assorted				
	Steel Chairs for Plant	21.00	pcs.		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Equipment				
	1 unit - Elf/Truck	1.00	day		
	Manpower				
	1 - Non Skilled Worker	1.00	day		
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM 3.1			₱
4.0	**Greeneries for Port of Opol, Misamis Oriental**				
4.1	**Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs**	8.00	PCS.		
	Work Description				
	Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs				
	Materials				
	Plants, Indoor, Potted, 50cm.Dia X 60cm. High	8.00	pcs		
	Big leaf, Assorted				
	Steel Chairs for Plant	8.00	pcs		
	Equipment				
	1 unit - Elf/Truck	1.00	day		
	Manpower				
	1 - Non Skilled Worker	1.00	day		
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM 4.1			₱
5.0	**Greeneries for Port of Benoni, Camiguin**				
5.1	**Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs**	12.00	PCS.		
	Work Description				
	Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs				
	Materials				
	Plants, Indoor, Potted, 50cm.Dia X 60cm. High	12.00	pcs.		
	Big leaf, Assorted				
	Steel Chairs for Plant	12.00	pcs.		
	Equipment				
	1 unit - Elf/Truck	1.00	day		
	Manpower				
	2 - Non Skilled Worker	2.00	days		
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM 5.1			₱

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
6.0	**Greeneries for Port of Balbagon, Camiguin**				
6.1	**Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs**	12.00	pcs.		
	Work Description				
	Supply and Delivery, Placing of Indoor Potted Plants, Including Steel Chairs				
	Materials				
	Plants, Indoor, Potted, 50cm.Dia X 60cm. High	12.00	pcs.		
	Big leaf, Assorted				
	Steel Chairs for Plant	12.00	pcs.		
	Equipment				
	1 unit - Elf/Truck	1.00	day		
	Manpower				
	2 - Non Skilled Worker	2.00	days		
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 5.1				₱
	TOTAL BID AMOUNT :				₱

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____