Project: **Maintenance of Safety and Environmental Signages, Baseport and Terminal Ports (MPF-MOC-06-2025)**
Location: Baseport and Terminal Ports

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	**Fabrication of Safety aluminum cladding signages and Environmental Vinyl Sticker**	1.00	LOT		
	Work Description Supply of labor and materials for the fabrication of safety and environmental signages				
	Materials				
	Aluminum Cladding signboard with reflective Cutt-out Sticker Letters - (Size: 2 feet x 3 feet);				
	SPEED LIMIT 20 KPH	6.00	pcs.		
	PPE MUST BE WORN IN THIS AREA	6.00	pcs.		
	HEAVY EQUIPMENT OPERATING IN THIS AREA	6.00	pcs.		
	THIS IS A SMOKE-FREE FACILITY ETC.	6.00	pcs.		
	DANGER: FALL HAZARD: NO LOITERING: NO SMOKING	6.00	pcs.		
	USE PEDERSTRIAN WALKWAY	6.00	pcs.		
	CAUTION: WATCH FOR MOVING VEHICLES	6.00	pcs.		
	NO PARKING	6.00	pcs.		
	Sintra Board signboard with reflective Vinyl Sticker, Water Proof - (Size: 30 " x 38 ");				
	NO SMOKING OPEN BURNING	6.00	pcs.		
	NO LITTERING INSIDE THE PORT	6.00	pcs.		
	KEEP OUT AUTHORIZED PERSONNEL ONLY	6.00	pcs.		
	KEEP AREA CLEAN	5.00	pcs.		
	NO GARBAGE DUMPING	5.00	pcs.		
	NO IDLING	5.00	pcs.		
	Aluminum Cladding signboard with reflective Vinyl Sticker, Water Proof - (Size: 2ft X 5ft)				
	NOTICE - PPA MC-11-2021 (size: 24" x 60")	5.00	pcs.		
	Aluminum Cladding signboard with reflective Vinyl Sticker, Water Proof - (Size: 3ft X 5ft)				
	NO FIXING, LITTERING, LOITERING, ETC. ZONE	5.00	pcs.		
	Sintra Board signboard with reflective Vinyl Sticker, Water Proof - (Size: 11" x 8.5")				
	FIRE EXTINGUISHER	23.00	pcs.		
	FIRE ALARM	8.00	pcs.		
	Sintra Board signboard with reflective Vinyl Sticker, Water Proof - (Size: 5" x 13")				
	WATCH YOUR STEPS	10.00	pcs.		
	Sintra Board signboard with reflective Vinyl Sticker, Water Proof, Lumnescent - (Size: 5" x 13")				
	EXIT (DOWN RIGHT)	5.00	pcs.		
	EXIT (RIGHT)	5.00	pcs.		
	EXIT (DOWN LEFT)	5.00	pcs.		
	EXIT	5.00	pcs.		
	EXIT (LEFT)	5.00	pcs.		
	Sintra Board signboard with reflective Vinyl Sticker, Water Proof - (Size: 8ft X 5ft)				
	SAFETY MONITORING BOARD	5.00	pcs.		
	THIS WAY TO EXIT GATE (RIGHT)	5.00	pcs.		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	THIS WAY TO EXIT GATE (LEFT)	5.00	pcs.		
	Vinyl Label Sticker Sign, Water Proof-(Size: 6.5" x 12.5")				
	INFECTIOUS WASTES	6.00	pcs.		
	BIODEGRADABLE WASTES	5.00	pcs.		
	RECYCLABLES	5.00	pcs.		
	SPECIAL WASTES	5.00	pcs.		
	RESIDUAL WASTES	5.00	pcs.		
	Vinyl Label Sticker Sign, Water Proof- (Size: 9.5" x 17")				
	INFECTIOUS WASTES	5.00	pcs.		
	BIODEGRADABLE WASTES	5.00	pcs.		
	RECYCLABLES	5.00	pcs.		
	SPECIAL WASTES	5.00	pcs.		
	RESIDUAL WASTES	5.00	pcs.		
	Vinyl Label Sticker Sign, Water Proof- Size: 30cm x 30cm (HAZARDOUS WASTE)				
	HW - EMPTY PAINT CANS	5.00	pcs.		
	HW - EMPTY PLASRIC FROM BATT. SOL.	5.00	pcs.		
	HW - LED BULBS	5.00	pcs.		
	HW - PRINTER CARTRIDGES	5.00	pcs.		
	HW - USED LEAD ACID BATT	5.00	pcs.		
	HW - USED OIL	5.00	pcs.		
	HW - BLANKS	5.00	pcs.		
	Vinyl Label Sticker Sign, Water Proof- (Size: 30cm x 30cm)				
	TOXIC	10.00	pcs.		
	REACTIVE	10.00	pcs.		
	WARNING	10.00	pcs.		
	Framing of Signages				
	1" x 1" X 6MM thk. Angle Bar Frame	43.00	lgs		
	2” dia. G.I Pipe Sched. 40	18.00	lgs		
	1 x 2 x 6mm THK. Rectangular Tube	11.00	lgs		
	Portland Cement	20.00	bags		
	Sand	1.00	cu.m		
	Gravel	2.00	cu.m		
	1" X 2" X 6MM thk. Rectangular Tube	3.00	gals		
	1/8mm Welding Rod - 6012 (5 kls.)	5.00	box		
	Quick Dry Enamel Paint	6.00	gals		
	Epoxy Primer White	5.00	gals		
	Epoxy Reducer	5.00	gals		
	2" Paint Brush	5.00	pcs		
	Baby Roller With Handle - Cotton	5.00	sets		
	3/16 dia. x 1/2 Blind Rivets	1.00	box		
	Equipment				
	NONE				

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Manpower				
	1 - Foreman	30.00	days		
	2 - Skilled Laborer	30.00	days		
	4 - Unskilled Laborer	30.00	days		

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM 1. ₱ _____

TOTAL BID AMOUNT : ₱ _____

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____