Project: **Maintenance of Public Toilets, Port of Cagayan de Oro (MPF-MOC-08-2025)**
Location: Port of Cagayan de Oro

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|

**I. REPLACEMENT OF PLUMBING FIXTURES OF AMENITY BUILDING**

| | | | | | |
|---|---|---|---|---|---|
| 1. | **Chipping and Disposal of Wall Tiles** | 1.00 | LOT | | |

Work Description

Supply of labor and equipment for the chipping and disposal of wall tiles

Materials

NONE

Equipment

| | | | | | |
|---|---|---|---|---|---|
| 1 | Portable Chipping gun | 1.50 | days | | |
| 1 | Mini Dumptruck | 1.50 | days | | |

Manpower

| | | | | | |
|---|---|---|---|---|---|
| 1 | - Foreman | 1.50 | days | | |
| 2 | - Skilled Laborer | 1.50 | days | | |

| | | |
|---|---|---|
| ESTIMATED DIRECT COST | ₱ | |
| ESTIMATED INDIRECT COST | ₱ | |
| TOTAL COST OF WORK ITEM 1. | ₱ | |

| | | | | | |
|---|---|---|---|---|---|
| 2. | **Installation of Plumbing Fixtures** | 1.00 | LOT | | |

Work Description

Supply of labor for the installation of plumbing fixtures

Materials

| | | | | | |
|---|---|---|---|---|---|
| | Water Closet -Dual Flush Siphon Jet Dual Flush - 3Ltrs / 6Ltrs(soft closed) | 19.00 | sets | | |
| | Wall hung Lavatory with stainless P-trap | 2.00 | sets | | |
| | 1/2"dia. Stainless Bidet | 19.00 | sets | | |
| | Urinal | 4.00 | sets | | |
| | Lavatory stainless faucet | 7.00 | bd.ft. | | |
| | PPR reducer 1" to 1/2" dia. | 19.00 | pcs. | | |
| | PPR elbow 1/2" dia. | 19.00 | pcs. | | |
| | PPR elbow female 1/2" dia. | 19.00 | pcs. | | |
| | PPR pipe 1/2" dia x 4m | 5.00 | pcs. | | |
| | 3-way stainless angle valve | 19.00 | pcs. | | |
| | consumables | | | | |

Equipment

| | | | | | |
|---|---|---|---|---|---|
| | Minor Tools | | | | |

Manpower

| | | | | | |
|---|---|---|---|---|---|
| 1 | - Foreman | 10.00 | days | | |
| 1 | - Skilled Laborer | 10.00 | days | | |
| 1 | - Unskilled Laborer | 10.00 | days | | |

| | | |
|---|---|---|
| ESTIMATED DIRECT COST | ₱ | |

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| | | | ESTIMATED INDIRECT COST | | ₱ |
| | | | TOTAL COST OF WORK ITEM 2. | | ₱ |
| 3. | **Tileworks** | 10.80 | SQ.M. | | |
| | Work Description | | | | |
| | Supply labor,materials and equipment for the tile works | | | | |
| | Materials | | | | |
| | 30cmx60cm Unglazed Ceramic Tiles (non-skid) | 60.00 | pcs. | | |
| | Tile Adhesive, 25kg | 2.00 | | | |
| | Tile Grout, 2kg | 1.00 | | | |
| | Equipment | | | | |
| | minor tools | | | | |
| | Manpower | | | | |
| | 1 - Foreman | 2.00 | days | | |
| | 1 - Skilled Laborer | 2.00 | days | | |
| | 1 - Unskilled Laborer | 2.00 | days | | |
| | | | ESTIMATED DIRECT COST | | ₱ |
| | | | ESTIMATED INDIRECT COST | | ₱ |
| | | | TOTAL COST OF WORK ITEM 3. | | ₱ |
| II. CONSTRUCTION OF TANK ELEVATED PLATFORM | | | | | |
| 1. | **Demolition/Excavation of Existing Pavement** | 5.47 | CU.M. | | |
| | Work Description | | | | |
| | Supply of labor and equipment for the demolition and excavation of existing pavement of the platform foundation | | | | |
| | Materials | | | | |
| | NONE | | | | |
| | Equipment | | | | |
| | 1 Backhoe (0.28 cu.m) | 1.50 | days | | |
| | 1 Concrete Saw | 1.50 | days | | |
| | 1 Mini Dumptruck | 1.50 | days | | |
| | Manpower | | | | |
| | 1 - Foreman | 1.50 | days | | |
| | 4 - Unskilled Laborer | 1.50 | days | | |
| | | | ESTIMATED DIRECT COST | | ₱ |
| | | | ESTIMATED INDIRECT COST | | ₱ |
| | | | TOTAL COST OF WORK ITEM 5. | | ₱ |
| 2.0 | **Concrete (Foundation)** | 2.49 | CU.M. | | |
| | Work Description | | | | |
| | Supply of materials, labor and equipment for the spread of concrete for footing, column and tie beam | | | | |
| | Materials | | | | |
| | Concrete Epoxy Primer White | 10.00 | gals | | |
| | Epoxy Reducer | 3.00 | gals | | |
| | 7" Paint Roller w/ Tray | 8.00 | pcs. | | |
| | Reflectorized Traffic Paint Yellow | 10.00 | pcs. | | |

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| | Reflectorized Traffic Paint Black | 10.00 | gals | | |
| | Baby Roller Cotton w/ tray | 8.00 | pcs. | | |
| | 2" Paint Brush | 8.00 | pcs. | | |
| | 3" Paint Brush | 8.00 | pcs. | | |
| | 8" dia. Waste Pad | 9.00 | kgs. | | |
| | Paint Thinner | 4.00 | gals | | |
| | Equipment | | | | |
| | NONE | | | | |
| | Manpower | | | | |
| | 1 - Foreman | 8.00 | days | | |
| | 1 - Skilled Laborer | 8.00 | days | | |
| | 1 - Unskilled Laborer | 8.00 | days | | |
| | | ESTIMATED DIRECT COST | | ₱ | |
| | | ESTIMATED INDIRECT COST | | ₱ | |
| | | TOTAL COST OF WORK ITEM 5. | | ₱ | |
| 6.0 | **Repainting of concrete curbs of the Port of Jasaan** | 96.60 | SQ.M. | | |
| | Work Description | | | | |
| | Supply of Materials, Labor and tools for the repainting of pedestrian lanes and curbs | | | | |
| | Materials | | | | |
| | Concrete Epoxy Primer White | 5.00 | gals | | |
| | Epoxy Reducer | 2.00 | gals | | |
| | 7" Paint Roller w/ Tray | 4.00 | pcs. | | |
| | Reflectorized Traffic Paint Yellow | 5.00 | pcs. | | |
| | Reflectorized Traffic Paint Black | 5.00 | gals | | |
| | Baby Roller Cotton w/ tray | 4.00 | pcs. | | |
| | 2" Paint Brush | 4.00 | pcs. | | |
| | 3" Paint Brush | 4.00 | pcs. | | |
| | 8" dia. Waste Pad | 2.00 | kgs. | | |
| | Paint Thinner | 2.00 | gals | | |
| | Equipment | | | | |
| | NONE | | | | |
| | Manpower | | | | |
| | 1 - Foreman | 4.00 | days | | |
| | 2 - Skilled Laborer | 4.00 | days | | |
| | 2 - Unskilled Laborer | 4.00 | days | | |
| | | ESTIMATED DIRECT COST | | ₱ | |
| | | ESTIMATED INDIRECT COST | | ₱ | |
| | | TOTAL COST OF WORK ITEM 6. | | ₱ | |
| | | TOTAL BID AMOUNT : | | ₱ | |

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____