Project: **Supply of Materials, Labor and Equipment for the Cleaning/Scrubbing and Repainting of Underground and Elevated Water Tank**

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Cleaning/Scrubbing of underground and elevated water tank**	1.00	lot		
	Work Description				
	To supply materials, labor, tools and scaffolding for the cleaning/scrubbing of underground and elevated water tank				
	Materials				
	Tile Cleaner Liquid Solution	20.00	Gal		
	Comfort Grip Brush Scrub	25.00	Pc.		
	Long handle Multi-purpose Cleaning Brush	25.00	Pc.		
	Detergent Soap Powder	10.00	Kg.		
	Cleaning Mop-Cotton w/ Long Wood Handle	6.00	pcs		
	8" dia. Waste Cotton Pad	8.00	Kilo		
	Steel Scaffolding Rental Sizes:				
	38mm dia x 6 m. G.I. Pipe	232.00	Pc.		
	38mm dia x 3 m. G.I. Pipe	14.00	Pc.		
	38mm dia x 1.5 m. G.I. Pipe	104.00	Pc.		
	G.I. Pipe Clamp	1,118.00	pc.		
	Equipment				
	1 Pressure Washer	6.00	day(s)		
	Manpower				
	1 Foreman	6.00	day(s)		
	4 Skilled Worker (Installation of Scaffolding)	6.00	day(s)		
	8 Unskilled Worker (Cleaing of Water Tank)	6.00	day(s)		
				ESTIMATED DIRECT COST	P-
				ESTIMATED INDIRECT COST	P-
				TOTAL COST OF WORK ITEM 1	P-
2.0	**Repainting of water pump flooring , fixtures valves, pipes and elevated water tank structure**	1.00	lot		
	Work Description				
	To supply materials, labor and tools for the repainting of water pump flooring , fixtures valves, pipes and elevated water tank structure				
	Materials				
	Elastomeric Paint - Light Beige	24.00	Gal.		
	Elastomeric Paint - Denim Blue	6.00	Gal.		
	Concrete Epoxy Primer White	19.00	Gal.		
	Epoxy Enamel Aluminum -890	6.00	Gal.		
	Epoxy Primer Gray-850	4.00	Gal.		
	Aqua Epoxy Light Blue	5.00	Gal.		
	Epoxy Enamel Ultra Marine Blue	3.00	Gal.		
	8" Paint Roller w/ Tray	10.00	Set		
	4" Paint Metal Scrapper w/ Handle	10.00	Pc.		
	2" Paint Brush	10.00	Pc.		
	Reflectorized Traffic Paint Yellow	1.00	Gal.		
	Baby Roller	5.00	Pc.		
	8" Waste Pad	5.00	Kilo		
	Equipment				
	Manpower				
	1 Foreman	11.00	day(s)		
	3 Skilled Worker	11.00	day(s)		
	3 Unskilled Worker	11.00	day(s)		
				ESTIMATED DIRECT COST	P-
				ESTIMATED INDIRECT COST	P-
				TOTAL COST OF WORK ITEM I.2	P-
				TOTAL AMOUNT	**P-**

Prepared by:

_____

Name & Signature

Designation: _____

Date: _____