Project: Supply of Materials, Labor, and Equipment for the Materials Recovery Facility, Port of Balingoan [MPF-MOC-34-2025]
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A. Structural Framing					
1.01	**Posts and Base Floor Framing**	9.76	SQ.M.		
	Work Description				
	Supply of materials, labor and equipment for the Posts and Base Floor Framing				
	Materials				
	Steel Channel, 100mmx50mmx4mm thk x 6mL	5.00	length		
	Angle Bar, 75mmx75mmx4mm thk x 6mL	3.00	length		
	Cutting Disc, 400mmØ	1.00	pc.		
	Welding Rod, 1/8" x 6012	7.00	kilo		
	Grinding Disc, 100mmØ	4.00	pc.		
	Manpower				
1	Foreman	3.00	day(s)		
1	Fabricator	3.00	day(s)		
1	Welder	3.00	day(s)		
	Equipment				
1	Welding Machine	3.00	day(s)		
1	Wheel Bar Cutter	2.00	day(s)		
1	Portable grinder	2.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM I.1		₱
1.02	**Girt, Walling, Partitions, and Doors**	43.44	SQ.M.		
	Work Description				
	Supply of materials, labor and equipment for the Girt, Walling, Partitions, and Doors				
	Materials				
	Angle Bar, 50x50x4mmx6mL	3.00	length		
	Angle Bar, 38x38x3mmx6mL	11.00	length		
	Angle Bar, 25x25x3mmx6mL	24.00	length		
	Cutting Disc, 400mmØ	1.00	pc.		
	Welding Rod, 1/8" x 6012	9.50	kilo		
	Grinding Disc, 100mmØ	4.00	pc.		
	Barrel Bolt, assembly	1.00	set		
	Manpower				
1	Foreman	3.00	day(s)		
1	Fabricator	3.00	day(s)		
1	Welder	3.00	day(s)		
	Equipment				
1	Welding Machine	3.00	day(s)		
1	Wheel Bar Cutter	2.00	day(s)		
1	Portable grinder	2.00	day(s)		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM I.2				₱
1.03	**Roof Framing**	20.80	SQ.M.		
	Work Description				
	Supply of materials, labor and equipment for the Roof Framing				
	Materials				
	Angle Bar, 50x50x4mmx6mL	5.00	length		
	C-Purlins, 50x75x1.2mm thk.	10.00	length		
	Cutting Disc, 400mmØ	2.00	pc.		
	Welding Rod, 1/8" x 6012	9.50	kilo		
	Grinding Disc, 100mmØ	4.00	pc.		
	Manpower				
	1 Foreman	4.00	day(s)		
	1 Fabricator	4.00	day(s)		
	1 Welder	4.00	day(s)		
	Equipment				
	1 Welding Machine	4.00	day(s)		
	1 Wheel Bar Cutter	2.00	day(s)		
	1 Portable grinder	2.00	day(s)		
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM I.3				₱
2.0	**Flooring**	9.76	sq.m.		
	Work Description				
	Supply of materials, labor and equipment for the Flooring				
	Materials				
	Phenolic Board, 1.2m x 2.4m x 3/4" thk.	4.00	sheet		
	Angle bar, 38x38x3mmthk. X 6mL	3.00	length		
	Welding Rod, 1/8" x 6012	1.50	kilo		
	Grinding Disc, 100mmØ	2.00	pc.		
	Manpower				
	1 Foreman	2.00	days		
	1 Fabricator	2.00	days		
	1 Welder	2.00	days		
	Equipment				
	1 Welding Machine	2.00	day		
	1 Cutting Outfit	2.00	day		
	1 Portable grinder	1.00	day		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 2.0				₱
3.0	**Roofing**	17.68	SQ.M.		
	Work Description				
	Supply of materials, labor and equipment for roofing				
	Materials				
	Roofing Sheet, 0.4mm thk., Rib-Type, Pre-Painted	20.80	l.m.		
	Ridge Roll, Pre-bended, Pre-painted, 2.4mL	3.00	length		
	Teck Screw, 1/8" x 1 1/2	132.00	pc.		
	Blind Rivets	0.50	box		
	consumables				
	Manpower				
	1 Foreman	1.00	day(s)		
	1 Skilled Laborer	1.00	day(s)		
	2 Unskilled Laborer	1.00	day(s)		
	Equipment				
	Minor Tools				
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 3.0				₱
4.0	**Steel Matting and Metal Sheet Walling**	41.06	SQ.M.		
	Work Description				
	Supply of materials, and labor for the Steel Matting and Metal Sheet Walling				
	Materials				
	Steel Matting 1.20x2.40x3mm thk wire, 50mm sq. hole	11.00	sheet		
	Metal Sheet, Pre-painted, Rib-Type, 0.4mmthk x 1mW	14.00	l.m.		
	Teck Screw, 1/8" x 1 1/2	160.00	pc.		
	Welding Rod	3.00	kl.		
	Manpower				
	1 Foreman	3.00	day(s)		
	2 Installer	3.00	day(s)		
	1 Welder	3.00	day(s)		
	Equipment				
	1 Portable grinder	2.00	day(s)		
	1 Electric Drill	2.00	day(s)		
	ESTIMATED DIRECT COST				₱
	ESTIMATED INDIRECT COST				₱
	TOTAL COST OF WORK ITEM 4.0				₱
5.0	**Singages/Painting**	1.00	LOT		
	Work Description				
	Supply of materials, and labor for the Singages/Painting				

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Materials				
	Acrylic Signages (Hazardous,Recyclable & Authorized Personnel Only)	1.00	lot		
	Red Oxide Primer	1.00	gal		
	Quick Dry Enamel gray	2.00	gal		
	2" Paint Brush	3.00	pc		
	Equipment				
	NONE				
	Manpower				
	1 Foreman	1.00	day		
	2 Skilled Laborer	1.00	day		
				ESTIMATED DIRECT COST	P
				ESTIMATED INDIRECT COST	P
				TOTAL COST OF WORK ITEM I.7	P

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____